					NT OF N	OF UTAH ATURAL RESO GAS AND MI		;			AMENDED RE	FORM 3		
		APPL	ICATION FOR	PERMIT TO DRILI	_				1. WELL N	IAME and NUI	MBER NBU 1022-9J10	:s		
2. TYPE OF		NII NEWWELL	DEENTED DO	AWELL A DEED	ENIMELL (<u> </u>			3. FIELD OR WILDCAT NATURAL BUTTES					
4. TYPE OF		RILL NEW WELL 📵	REENTER P8		EN WELL (J			5. UNIT or COMMUNITIZATION AGREEMENT NAME					
6. NAME OF	OPERATOR	Gas V	/ell Coalt	ed Methane Well: NO					7. OPERA	NATURAL BUTTES 7. OPERATOR PHONE				
	S OF OPERATOR	KER	R-MCGEE OIL &	GAS ONSHORE, L.P.							720 929-610)		
). Box 173779, D	Denver, CO, 80217 9. OPERATOR E-MAIL Andy.Lytle@anadarko.com										
	L LEASE NUMBER INDIAN, OR STAT UTU			11. MINERAL OWNERSHIP 12. SURFACE OWNERSHIP FEDERAL INDIAN STATE FEE FEE						FEE				
13. NAME C	F SURFACE OWN	NER (if box 12 = 'fe	ee')						14. SURF	ACE OWNER	PHONE (if box	(12 = 'fee')	
15. ADDRESS OF SURFACE OWNER (if box 12 = 'fee')									16. SURF	ACE OWNER	E-MAIL (if bo	x 12 = 'fee	')	
17. INDIAN ALLOTTEE OR TRIBE NAME (if box 12 = 'INDIAN')				18. INTEND TO CO MULTIPLE FORMAT	IONS	PRODUCTION		_	19. SLAN	_	ECTIONAL (a)	HORIZO	ONITAL (T)	
	"ON OF WELL													
	TION OF WELL			OOTAGES	Q	TR-QTR		CTION	-	/NSHIP	RANGE	_	MERIDIAN	
	AT SURFACE			SL 1793 FEL	_	NWSE		9	-	0.0 S	22.0 E	_	S	
	permost Producir	ng Zone		SL 1814 FEL	-	NWSE		9	10.0 S		22.0 E	_	S	
At Total D			2273 F	SL 1814 FEL		NWSE		9		0.0 S	22.0 E		S	
21. COUNT		NTAH		22. DISTANCE TO N		830	·		23. NUMB	ER OF ACRES	320	UNIT		
				25. DISTANCE TO N (Applied For Drillin	ng or Com		POOL		26. PROP	OSED DEPTH MD: 1	0035 TVD:	10009		
27. ELEVAT	TON - GROUND L			28. BOND NUMBER					29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPLICABLE 43-8496					
<u> </u>		5208		Hole Casi		Cement Info	rmation	`			43-8490			
String	Hole Size	Casing Size	Lengt			de & Thread		Max Mu	Mud Wt. Cement Sacks Yield Weight					
Surf	11	8.625	0 - 24	-		J-55 LT&C	\neg	0.2	!	Type V	180	1.15	15.8	
										Class G	270	1.15	15.8	
Prod	7.875	4.5	0 - 100	35 11.6	HC	P-110 LT&C	_	12.	5	Class G	300	3.38	12.0	
					ATTAC	HMENTS				Class G	1470	1.31	14.3	
					ATTAC	HWENTS								
	VERIFY	THE FOLLOWIN	IG ARE ATTA	CHED IN ACCORD	ANCE W	ITH THE UTA	AH OIL A	AND GAS	CONSER	VATION GE	NERAL RUL	.ES		
₩ WEI	LL PLAT OR MAP F	PREPARED BY LICE	NSED SURVEYO	R OR ENGINEER		№ COM	PLETE DI	RILLING PL	-AN					
AFFI	DAVIT OF STATUS	S OF SURFACE OW	NER AGREEMEN	IT (IF FEE SURFACE)		FORM	1 5. IF OP	ERATOR IS	S OTHER T	HAN THE LEA	ASE OWNER			
DIRE	ECTIONAL SURVE	Y PLAN (IF DIRECT	TIONALLY OR H	ORIZONTALLY DRILL	ED)	торо	GRAPHIC	CAL MAP						
NAME Joel	Malefyt			TITLE Regualtory A	nalyst			PHONE	720 929-6	828				
SIGNATUR	E			DATE 03/04/2015				EMAIL jo	joel.malefyt@anadarko.com					
	er assigned 4755266000	00		APPROVAL				B	09.ju					
								Perm	Permit Manager					

NBU 1022-9J Pad Drilling Program
1 of 6

Kerr-McGee Oil & Gas Onshore. L.P.

NBU 1022-9J1CS

Surface: 1913 FSL / 1793 FEL NWSE BHL: 2273 FSL / 1814 FEL NWSE

Section 9 T10S R22E

Unitah County, Utah Mineral Lease: UTU-01196D

ONSHORE ORDER NO. 1

DRILLING PROGRAM

1. & 2.a <u>Estimated Tops of Important Geologic Markers</u>: <u>Estimated Depths of Anticipated Water, Oil, Gas, or Mineral Formations</u>:

<u>Formation</u>	<u>Depth</u>	<u>Resource</u>
Uinta	0 - Surface	
Green River	1,215'	
Birds Nest	1,496'	Water
Mahogany	1,960'	Water
Wasatch	4,323'	Gas
Mesaverde	6,802'	Gas
Sego	8,880'	Gas
Castlegate	8,961'	Gas
Blackhawk	9,409'	Gas
TVD =	10,009'	
TD =	10,035'	

2.b Kerr McGee Oil & Gas Onshore LP (Kerr McGee) may elect to drill to (i) the Blackhawk formation (part of the Mesaverde Group), (ii) to a shallower depth within the Mesaverde Group, or (iii) to the Wasatch Formation. If Kerr McGee drills to the Blackhawk formation, please refer to Blackhawk as the bottom formation. The attached Blackhawk Drilling Program includes Total Vertical Depth, Total Depth, and appropriate casing and cement programs for the deeper formation.

If Kerr-McGee drills to a shallower depth in the Mesaverde Group or to the Wasatch Formation, please refer to the attached Wasatch/Mesaverde Drilling Program which includes Total Vertical Depth, Total Depth, and appropriate casing and cement programs for the shallower formations.

3. Pressure Control Equipment

Please refer to the Standard Operating Practices on file with the BLM Vernal Field Office.

NBU 1022-9J Pad Drilling Program 2 of 6

4. Proposed Casing & Cementing Program:

Please refer to the Standard Operating Practices on file with the BLM Vernal Field Office.

5. <u>Drilling Fluids Program:</u>

Please refer to the attached Blackhawk Drilling Program and the Wasatch/Mesaverde Drilling Program

6. <u>Evaluation Program</u>:

Please refer to the attached Blackhawk Drilling Program and the Wasatch/Mesaverde Drilling Program

7. <u>Abnormal Conditions</u>:

7.a Blackhawk (Part of Mesaverde Group)

Maximum anticipated bottom hole pressure calculated at 6,406 psi (0.64 psi/ft = actual bottomhole gradient)

Maximum Anticipated Bottom Hole Pressure (MABHP) = Pore Pressure at TD

Maximum anticipated surface pressure equals approximately 4,190 psi (bottom hole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot, per Onshore Order No. 2).

Per Onshore Order No. 2 - Max Anticipated Surf. Press.(MASP) = (Pore Pressure at next csg point-(0.22 psi/ft-partial evac gradient x TVD of next csg point))

7.b Wasatch Formation/Mesaverde Group

Maximum anticipated bottom hole pressure calculated at 8880' TVD, approximately equals 5,417 psi (0.61 psi/ft = actual bottomhole gradient)

Maximum Anticipated Bottom Hole Pressure (MABHP) = Pore Pressure at TD

Maximum anticipated surface pressure equals approximately 3,487 psi (bottom hole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot, per Onshore Order No. 2).

Per Onshore Order No. 2 - Max Anticipated Surf. Press.(MASP) = (Pore Pressure at next csg point-(0.22 psi/ft-partial evac gradient x TVD of next csg point))

8. <u>Anticipated Starting Dates:</u>

Drilling is planned to commence immediately upon approval of this application.

9. Variances:

Please refer to the Standard Operating Practices on file with the BLM Vernal Field Office.

10. Other Information:


Please refer to the attached Blackhawk Drilling Program and the Wasatch/Mesaverde Drilling Program

NBU 1022-9J Pad Drilling Program 3 of 6



KERR-McGEE OIL & GAS ONSHORE LP Blackhawk Drilling Program

COMPANY NAME KERR-McGEE OIL & GAS ONSHORE LP DATE March 3, 2015 NBU 1022-9J1CS WELL NAME TD 10,009' TVD 10,035' MD **FIELD** Natural Buttes **COUNTY Uintah** STATE Utah FINISHED ELEVATION 5,208' SURFACE LOCATION **NWSE** 1913 FSL 1793 FEL Sec 9 T 10S R 22E Latitude: 39.961504 Longitude: -109.441752 **NAD 83** T 10S BTM HOLE LOCATION **NWSE** 2273 FSL 1814 FEL Sec 9 R 22E Latitude: 39.962493 Longitude: -109.441830 NAD 83 OBJECTIVE ZONE(S) BLACKHAWK (Part of the Mesaverde Group) ADDITIONAL INFO Regulatory Agencies: BLM (Minerals), BLM(Surface), UDOGM Tri-County Health Dept.



Drilling Program NBU 1022-9J Pad



KERR-McGEE OIL & GAS ONSHORE LP **Blackhawk Drilling Program**

CASING PROGRAM

CONDUCTOR

SURFACE

CPLG. **BURST** COLLAPSE SIZE INTERVAL WT. GR. 0-40' 14" 3,390 1,880 348,000 8-5/8" 0 2,410 28.00 IJ-55 LTC 2.23 1.67 to 279,000 10,690 8,650 0 to 5,000 11.60 HCP-110 DQX 1.19 HCP-110 4-1/2" to 10,035 11.60 **LTC** 1.19

Surface Casing:

PRODUCTION

12.5 0.73 psi/ft = frac gradient @ surface shoe (Burst Assumptions: TD = ppg)

Fracture at surface shoe with 0.1 psi/ft gas gradient above

(Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing*Buoy.Fact. of water)

Production casing:

0.64 psi/ft = bottomhole gradient (Burst Assumptions: Pressure test with 8.4ppg @ 9000 psi) (Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing*Buoy.Fact. of water)

CEMENT PROGRAM

		FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGHT	YIELD
SURFACE	LEAD	500'	Premium cmt + 2% CaCl	180	60%	15.80	1.15
Option 1			+ 0.25 pps flocele				
TOP OUT C	MT (6 jobs)	1,200'	20 gals sodium silicate + Premium cmt	270	0%	15.80	1.15
			+ 2% CaCl + 0.25 pps flocele				
SURFACE			NOTE: If well will circulate water to surface,	option 2 will	be utilized	-	
Option 2	LEAD	1,910'	Premium cmt + 16% Gel + 10 pps gilsonite	280	35%	12.00	2.86
			+ 0.25 pps Flocele + 3% salt BWOC + GR 3 pps				
	TAIL	500'	Premium cmt + 2% CaCl	170	35%	15.80	1.15
			+ 0.25 pps flocele				
TOP	OUT CMT	as required	Premium cmt + 2% CaCl	as req.		15.80	1.15
PRODUCTION	LEAD	3,815'	35/65 Poz/G + 0.25 pps celloflake + 0.4% HALAD-344 (PB)	300	35%	12.00	3.38
			+ 3 pps Silicalite + 0.35% HR-5 (PB) + 6% Bentonite +				
			0.1%SA-1015 (PB) + 1 pps Granulite TR 1/4 + 0.25 pps Kwik seal				
	TAIL	6,220'	50/50 Poz/G + 2% Bentonite + 0.25% HR-5 (PB)	1,470	35%	14.30	1.31
			+ 0.5% HALAD-344 (PB) + 0.2% Super CBL				
			+ 1 pps Granulite TR 1/4 + 0.25 pps Kwik seal				

^{*}Substitute caliper hole volume plus 0% excess for LEAD if accurate caliper is obtained

FLOAT EQUIPMENT & CENTRALIZERS

SURFACE

Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe

PRODUCTION

Float shoe, 1 jt, float collar. 15 centralizers for a Mesaverde and 20 for a Blackhawk well centralizer on the first 3 joints and one every third joint thereafter

ADDITIONAL INFORMATION

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.

BOPE: 11" 5M with one annular and 2 rams. The BOPE will be installed before the production hole is drilled and tested to 5,000 psi (annular to 2,500 psi) prior to drilling out the surface casing shoe. Record on chart recorder and tour sheet. Function test rams on each trip. Maintain safety valve and inside BOP on rig floor at all times. Most rigs have top drives; however, if used, the Kelly is to be equipped with upper and lower kelly valves.

Surveys will be taken at 1,000' minimum intervals.

Most rigs have PVT System for mud monitoring. If no PVT is available, visual monitoring will be utilized.

	IF extreme mud losses are observed	OR cement doesn't reach surface on a well on the pad, a	DV Tool may be used. With Cement Baskets above and B	elow it.
DRILLING	ENGINEER:		DATE:	
		Matt Stiasny/Toni Newville		
DRILLING	SUPERINTENDENT:		DATE:	
		Lovel Young	-	

DESIGN FACTORS

LTC

5.89

DQX

N/A

N/A

367,174

3.90


TENSION


^{*}Substitute caliper hole volume plus 10% excess for TAIL if accurate caliper is obtained

NBU 1022-9J Pad Drilling Program 5 of 6



KERR-McGEE OIL & GAS ONSHORE LP Wasatch/Mesaverde Drilling Program





Drilling Program NBU 1022-9J Pad



KERR-McGEE OIL & GAS ONSHORE LP Wasatch/Mesaverde Drilling Program

CASING PROGRAM

CONDUCTOR

SURFACE PRODUCTION

										LTC	DQX
	SIZE	INTERVAL		WT.	GR.	CPLG.	BURST COLLAPSE		TENSION		
	14"	0-40'									
								3,390	1,880	348,000	N/A
8	3-5/8"	0	to	2,410	28.00	IJ-55	LTC	2.23	1.67	5.89	N/A
								7,780	6,350		267,035
4	4-1/2"	0	to	5,000	11.60	I-80	DQX	1.11	1.15		3.17
								7,780	6,350	223,000	
4	4-1/2"	5,000	to	8,906'	11.60	I-80	LTC	1.11	1.15	6.03	

Surface Casing:

(Burst Assumptions: TD =

12.0

ppg)

0.73 psi/ft = frac gradient @ surface shoe

DESIGN FACTORS

Fracture at surface shoe with 0.1 psi/ft gas gradient above

(Collapse Assumption: Fully Evacuated Casing, Max MW)

(Tension Assumptions: Air Weight of Casing*Buoy.Fact. of water)

Production casing:

(Burst Assumptions: Pressure test with 8.4ppg @

(iza

0.61 psi/ft = bottomhole gradient

(Collapse Assumption: Fully Evacuated Casing, Max MW)

(Tension Assumptions: Air Weight of Casing*Buoy.Fact. of water)

CEMENT PROGRAM

		FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGH1	YIELD
SURFACE	LEAD	500'	Premium cmt + 2% CaCl	180	60%	15.80	1.15
Option 1	Option 1		+ 0.25 pps flocele				
TOP OUT	CMT (6 jobs)	1,200'	20 gals sodium silicate + Premium cmt	270	0%	15.80	1.15
			+ 2% CaCl + 0.25 pps flocele				
SURFACE			NOTE: If well will circulate water to surface,	option 2 will	be utilized	•	•
Option 2	LEAD	1,910'	Premium cmt + 16% Gel + 10 pps gilsonite	280	35%	12.00	2.86
			+ 0.25 pps Flocele + 3% salt BWOC + GR 3 pps				
	TAIL	500'	Premium cmt + 2% CaCl	150	35%	15.80	1.15
			+ 0.25 pps Flocele + 3% salt BWOC + GR 3 pps				
TO	OP OUT CMT	as required	Premium cmt + 2% CaCl	as req.		15.80	1.15
PRODUCTION	LEAD	3,816'	35/65 Poz/G + 0.25 pps celloflake + 0.4% HALAD-344 (PB)	300	35%	12.00	3.38
			+ 3 pps Silicalite + 0.35% HR-5 (PB) + 6% Bentonite +				
			0.1%SA-1015 (PB) + 1 pps Granulite TR 1/4 + 0.25 pps Kwik seal				
	TAIL	5,090'	50/50 Poz/G + 2% Bentonite + 0.25% HR-5 (PB)	1,200	35%	14.30	1.31
			+ 0.5% HALAD-344 (PB) + 0.2% Super CBL				
			+ 1 pps Granulite TR 1/4 + 0.25 pps Kwik seal				

^{*}Substitute caliper hole volume plus 0% excess for LEAD if accurate caliper is obtained

FLOAT EQUIPMENT & CENTRALIZERS

SURFACE

Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe

PRODUCTION

Float shoe, 1 jt, float collar. 15 centralizers for a Mesaverde and 20 for a Blackhawk well. 1 centralizer on the first 3 joints and one every third joint thereafter.

ADDITIONAL INFORMATION

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.

BOPE: 11" 5M with one annular and 2 rams. The BOPE will be installed before the production hole is drilled and tested to 5,000 psi (annular to 2,500 psi) prior to drilling out the surface casing shoe. Record on chart recorder and tour sheet. Function test rams on each trip. Maintain safety valve and inside BOP on rig floor at all times. Most rigs have top drives; however, if used, the Kelly is to be equipped with upper and lower kelly valves.


Surveys will be taken a	at 1,000'	minimum	intervals.
-------------------------	-----------	---------	------------

Most rigs have PVT System for mud monitoring. If no PVT is available, visual monitoring will be utilized.


IF extreme mud losses are observed OR cement doesn't reach surface on a well on the pad, a DV Tool may be used. With Cement Baskets above and Below it.


DRILLING ENGINEER:		ı	DATE:
	Matt Stiasny/Toni Newville		
DRILLING SUPERINTENDENT:			DATE:
	Lovel Young	•	


^{*}Substitute caliper hole volume plus 10% excess for TAIL if accurate caliper is obtained



			SURFACE POS	SITION		BOTTOM HOLE						
WELL NAME	NAME NAD83		83 NAD27				1 4	NAD		NAC		FOOTAGES
NBU	LATITUDE 39°57'41.639"	LONGITU N 109°26'29.7		DE LONG '63"N 109°26'2	7.278"W	1935' FSL	LATIT 39°57'49		LONGITUDE 109°26'13.625"W	LATITUDE 39°57'49.131"N	LONGITUDE 109°26'11.167"W	FOOTAGES 2613 FNL
1022-9H4CS NBU	39.961566°N 39°57'41.594"	109.441593°	W 39.961601	°N 109.4409		1748' FEL 1931' FSL	39.9636 39°57'45	13°N	109.437118°W 109°26'13.630"W	39.963648°N	109.436435°W 109°26'11.172"W	492' FEL 2331' FSL
1022-911BS	39.961554°N	109.441625°	W 39.961588	°N 109.4409	942°W	1757' FEL	39.9626	53°N	109.437119°W	39.962688°N	109.436437°W	493¹ FEL
NBU 1022-9H3AS	39°57'41.549" 39.961541°N	N 109°26'29.90 109.441657°		1.00 =0 =	7.507"W 974°W	1926' FSL 1766' FEL	39°57'52 39.96469		109°26'15.929"W 109.437758°W	39°57'53.008"N 39.964724°N	109°26'13.470"W 109.437075°W	2219' FNL 671' FEL
NBU 1022-911DS	39°57'41.503" 39.961529°N		79"W 39°57'41.6	27"N 109°26'2	7.620"W	1922' FSL 1775' FEL	39°57'42 39.96169	2.084"N	109°26'11.157"W 109.436432°W	39°57'42.208"N 39.961725°N	109°26'8.699"W 109.435750°W	1980' FSL 301' FEL
NBU	39°57'41.459"	N 109°26'30.19	94"W 39°57'41.5	83"N 109°26'2	7.735"W	1917' FSL	39°57'51	1.394"N	109°26'30.744"W	39°57'51.518"N	109°26'28.285"W	2359' FNL
1022-9G4CS NBU	39.961516°N 39°57'41.414"	N 109°26'30.30)38°W 7.849"W	1784' FEL 1913' FSL	39.96427 39°57'44		109.441873°W 109°26'30.590"W	39.964311°N 39°57'45.097"N	109.441190°W 109°26'28.131"W	1825' FEL 2273' FSL
1022-9J1CS NBU	39.961504°N 39°57'41.369"	109.441752° N 109°26'30.42			069°W 7.963"W	1793' FEL 1908' FSL	39.96249 39°57'47		109.441830°W 109°26'30.340"W	39.962527°N	109.441147°W 109°26'27.881"W	1814' FEL
1022-9J1BS	39.961491°N	109.441784°	W 39.961526	°N 109.4411	01°W	1802¹ FEL	39.96332		109°26'30.340'W 109.441761°W	39.963359°N	109°26°27.881°W 109.441078°W	2576' FSL 1794' FEL
NBU 1022-9J	39°57'41.683" 39.961579°N	N 109°26'29.62 109.441562°			7.164"W 879°W	1940' FSL 1 <i>7</i> 39' FEL						
NBU 205	39°57'42.114" 39.961698°N	N 109°26'30.50			8.043"W	1984' FSL 1808' FEL						
	33.30103011	103.441000				From Surface	Position	to Botto	om Hole			
WELL NAME	NORTH	EAST	WELL NAME	NORTH	EAS		NAME	NOR	TH EAST	WELL NAM	E NORTH	EAST
NBU 1022-9H4CS	746.2	1254.6'	NBU 1022-911BS	401.0'	1263.3	3 NBU 1022-9	H3AS	1147.	6' 1092.9'	NBU 1022-911DS	59.21	1473.8'
WELL NAME	NORTH	EAST	WELL NAME	NORTH	EAS		NAME	NOR	TH EAST		1	ر ا
NBU 1022-9G4CS	1005.6	-43.1'	NBU 1022-9J1CS	360.31	-22.1	NBU 1022-9	J1BS	667.9		AZ 59.2581 AZ 59.2581 159.1531 E. TO BOMO!	\	
Az=0.53222° (To Bottom Hole) N00°31′56″E - 667.90' EXISTING WELL: NBU 205 © (Dry Hole Marker) Az=356.49694° (To Bottom Hole) N03°30′11″W - 360.97' Az=87.69833° (To Bottom Hole) N03°30′11″W - 360.97' Az=87.69833° (To Bottom Hole) N87°41′54″E - 1474.96' R87°41′54″E -												
THE SE ¼ OI S.L.B.&M. V GLOBAL PC OBSERVATI Kerr-Mc(1099 13 WELL NBU NBU NBU NBU	8th Street - D LL PAD - PAD INT WELLS - NBI 1022-911BS 1022-911DS 1022-9J1CS	AKEN FROM G SATELLITE AR NO0°07' Conver, Color NBU 10 ERFERENO U 1022-9H4 NBU 1022 NBU 1022 NBU 1022 NBU 1022 NBU 1022	E, 20"W. Dnshore, I ado 80202 D22-9J CE PLAT CS, -9H3AS, -9G4CS, 22-9J1BS		CONSU 2155 No	7. to 18U 1022-91 62. 88889 69 7 1 10 18U 1022-91 62. 88889 69 7 1 10 10 10 10 10 10 10 10 10 10 10 10 1	#67:37306	DATE 06-17 DATE	ENGINEERIN 209 NORTH SURVEYED: 7-13 EDRAWN:	いる & LAND	SURVEYINC RNAL, UTAH 84 Y: J.W.	
LOCA	TED IN SEC	TION 9, T10	S, R22E,			n, wr 8280. 307-674-060!		07-16		Date Last Rev		O
S.L.B.	&M., UINTA	H COUNTY	, UTAH.		Fax 3	07-674-0182		S	CALE: 1" = 60'	2-25-15 D.A		8 OF 19







NBU 1022-9I1DS, NBU 1022-9G4CS,

NBU 1022-9J1CS & NBU 1022-9J1BS

LOCATED IN SECTION 9, T10S, R22E,

S.L.B.&M., UINTAH COUNTY, UTAH

2155 North Main Street

Sheridan, WY 82801 Phone 307-674-0609 Fax 307-674-0182

TIMBERLINE




PHOTO VIEW: FROM CORNER #5 TO LOCATION STAKE

CAMERA ANGLE: NORTHERLY



PHOTO VIEW: FROM EXISTING ACCESS ROAD

CAMERA ANGLE: SOUTHWESTERLY

Kerr-McGee Oil & Gas Onshore, LP 1099 18th Street - Denver, Colorado 80202

WELL PAD - NBU 1022-9J

LOCATION PHOTOS

NBU 1022-9H4CS, NBU 1022-911BS, NBU 1022-9H3AS, NBU 1022-911DS, NBU 1022-9G4CS, NBU 1022-9J1CS, NBU 1022-9J1BS LOCATED IN SECTION 9, T10S, R22E, S.L.B.&M., UINTAH COUNTY, UTAH.



CONSULTING, LLC

2155 North Main Street Sheridan, WY 82801 Phone 307-674-0609 Fax 307-674-0182


TIMERRUNE
ENGINEERING & LAN


(435) 789-1365


12 OF 19


GINEERING & LAND SURVEYING, INC. 209 NORTH 300 WEST - VERNAL, UTAH 84078


DATE PHOTOS TAKEN: 06-17-13	PHOTOS TAKEN BY: J.W.	SHEET NO:
DATE DRAWN: 07-16-13	DRAWN BY: J.G.C.	12
Date Last Revised: 2-25-15	D.A.	12 OF 19














Kerr-McGee Oil & Gas Onshore, LP WELL PAD – NBU 1022-9J WELLS - NBU 1022-9H4CS, NBU 1022-9I1BS, NBU 1022-9H3AS, NBU 1022-9I1DS & NBU 1022-9G4CS, NBU 1022-9J1CS & NBU 1022-9J1BS SECTION 9, T10S, R22E, S.L.B.&M. UINTAH COUNTY, UTAH

From the intersection of U.S. Highway 40 and 500 East street in Vernal, Utah, proceed in an easterly, then southerly direction along U.S. Highway 40 approximately 3.3 miles to the junction of State Highway 45; exit right and proceed in a southerly direction along State Highway 45 approximately 20.2 miles to the junction of the Glen Bench Road (County B Road 3260). Exit right and proceed in a southwesterly direction along the Glen Bench Road approximately 18.7 miles to a Class D County Road to the northeast. Exit left and proceed in a northeasterly direction along the Class D County Road approximately 0.1 miles to a second Class D County Road to the southeast. Exit right and proceed in a southeasterly direction along the second Class D County Road approximately 5.9 miles to a third Class D County Road to the northeast. Exit left and proceed in a northeasterly direction along the third Class D County Road approximately 0.5 miles to a service road to the southeast. Exit right and proceed in a southeasterly direction along the service road approximately 45 feet to the proposed well location.

Total distance from Vernal, Utah to the proposed well location is approximately 48.7 miles in a southerly direction.

SHEET 19 OF 19

API Well Number: 43047556j2c6.6012AHO UTM (feet), NAD27, Zone 12N

Scientific Drilling

Site: NBU 1022-9J PAD Well: NBU 1022-9J1CS

Wellbore: OH


Design: PLAN #1 PRELIMINARY




Azimuths to True North Magnetic North: 10.67°

> Magnetic Field Strength: 51834.3snT Dip Angle: 65.73° Date: 3/2/2015

Model: BGGM2013







US ROCKIES REGION PLANNING

UTAH - UTM (feet), NAD27, Zone 12N NBU 1022-9J PAD NBU 1022-9J1CS

OH

Plan: PLAN #1 PRELIMINARY

Standard Planning Report

03 March, 2015





Planning Report



Denver Sales Database:

Company: US ROCKIES REGION PLANNING Project: UTAH - UTM (feet), NAD27, Zone 12N

NBU 1022-9J PAD Site: Well: NBU 1022-9J1CS

Wellbore: ОН

PLAN #1 PRELIMINARY Design:

Local Co-ordinate Reference:

TVD Reference: MD Reference: North Reference:

Survey Calculation Method:

Well NBU 1022-9J1CS

GL 5208 & KB 4 @ 5212.00ft (ASSUMED) GL 5208 & KB 4 @ 5212.00ft (ASSUMED)

Minimum Curvature

Project UTAH - UTM (feet), NAD27, Zone 12N

Map System: Universal Transverse Mercator (US Survey Feet)

NAD 1927 (NADCON CONUS) Geo Datum: Map Zone:

System Datum: Mean Sea Level

Zone 12N (114 W to 108 W)

NBU 1022-9J PAD, SECTION 9 T10S R22E Site

Northing: 14,515,880.34 usft Site Position: Latitude: 39.9616010 From: Lat/Long Easting: 2,077,306.51 usft Longitude: -109.4409110 **Position Uncertainty:** 0.00 ft Slot Radius: **Grid Convergence:** 1.00 9

13.200 in

Well NBU 1022-9J1CS, 1913 FSL 1793 FEL

Well Position +N/-S -22.95 ft 14,515,856.62 usft Latitude: 39.9615380 Northing: +E/-W -44.28 ft Easting: 2,077,262.63 usft Longitude: -109.4410690

Position Uncertainty 0.00 ft Wellhead Elevation: 0.00 ft **Ground Level:** 5,208.00 ft

Wellbore ОН Magnetics **Model Name** Sample Date Declination **Dip Angle** Field Strength (nT) (°) (°) 3/2/2015 BGGM2013 10.67 65.73 51,834

PLAN #1 PRELIMINARY Design Audit Notes: Version: Phase: PLAN Tie On Depth: 0.00 **Vertical Section:** Depth From (TVD) +N/-S +E/-W Direction (ft) (ft) (ft) (°) 0.00 0.00 0.00 356.53

Plan Sections										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00	
750.00	9.00	356.53	748.15	35.21	-2.14	2.00	2.00	0.00	356.53	
2,605.91	9.00	356.53	2,581.21	325.00	-19.72	0.00	0.00	0.00	0.00	
3,055.91	0.00	0.00	3,029.36	360.21	-21.86	2.00	-2.00	0.00	180.00	
10,035.55	0.00	0.00	10,009.00	360.21	-21.86	0.00	0.00	0.00	0.00	PBHL_NBU 1022-9J1



Planning Report



Database: Denver Sales

Company: US ROCKIES REGION PLANNING
Project: UTAH - UTM (feet), NAD27, Zone 12N

 Site:
 NBU 1022-9J PAD

 Well:
 NBU 1022-9J1CS

Wellbore: OH

Design: PLAN #1 PRELIMINARY

Local Co-ordinate Reference:

TVD Reference:
MD Reference:
North Reference:

Survey Calculation Method:

Well NBU 1022-9J1CS

GL 5208 & KB 4 @ 5212.00ft (ASSUMED) GL 5208 & KB 4 @ 5212.00ft (ASSUMED)

True

Measured	ed Survey									
Depth Inclination Azimuth Oepht +N.S. +P.W Section Rate (*190usth) (*1										
100.00	Depth			Depth			Section	Rate	Rate	Rate
200.00 0.00 0.00 0.00 200.00 0.00 0.00	0.00						0.00	0.00	0.00	0.00
Start Build 2.00										
### Start Build 2.00 ### 400.00 ### 2.00 ### 359.53 ### 399.84 ### 4.697 ### -0.42 ### 6.97 ### -0.42 ### 6.98 ### 2.00 ### 2										
\$\ \begin{array}{c c c c c c c c c c c c c c c c c c c			0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00
500.00			256 52	200.00	1 74	0.11	1 75	2.00	2.00	0.00
600.00										
T00.00										
Start 1855 00 bold at 750 00										
Start 1855.90 hold at 750.00 MD										
800.00 9.00 356.53 797.54 43.01 -2.61 43.09 0.00 0.00 0.00 90.00 90.00 90.00 356.53 995.07 74.24 -4.51 74.38 0.00 0.00 0.00 0.00 1.000.00 9.00 356.53 1995.07 74.24 -4.51 74.38 0.00 0.00 0.00 0.00 1.200.00 9.00 356.53 1.192.61 105.47 -6.40 105.67 0.00 0.00 0.00 1.200.00 9.00 356.53 1.192.61 105.47 -6.40 105.67 0.00 0.00 0.00 0.00 1.200.00 9.00 356.53 1.192.61 105.47 -6.40 105.67 0.00 0.00 0.00 0.00 1.200.00 9.00 356.53 1.215.00 109.01 -6.62 109.21 0.00 0.00 0.00 0.00 1.200.00 9.00 356.53 1.291.38 121.09 -7.35 121.31 0.00 0.00 0.00 1.400.00 1.400.00 9.00 356.53 1.390.15 136.70 -8.30 136.95 0.00 0.00 0.00 1.500.00 9.00 356.53 1.489.00 153.44 -9.31 153.72 0.00 0.00 0.00 0.00 1.500.00 9.00 356.53 1.489.60 153.44 -9.31 153.72 0.00 0.00 0.00 0.00 1.500.00 9.00 356.53 1.489.60 153.44 -9.31 153.72 0.00 0.00 0.00 0.00 1.500.00 9.00 356.53 1.896.00 153.44 -9.31 153.72 0.00 0.00 0.00 0.00 1.700.00 9.00 356.53 1.896.00 153.44 -9.31 153.72 0.00 0.00 0.00 0.00 1.700.00 9.00 356.53 1.896.00 153.44 -9.31 153.72 0.00 0.00 0.00 0.00 1.700.00 1.700.00 9.00 356.53 1.888.60 183.55 -11.14 183.88 0.00 0.00 0.00 0.00 1.700.00 1.700.00 9.00 356.53 1.785.22 199.16 -12.09 199.53 0.00 0.00 0.00 0.00 1.700.00 9.00 356.53 1.786.22 199.16 -12.09 199.53 0.00 0.00 0.00 0.00 1.766.55 9.00 356.53 1.860.00 26.67 9 -13.76 227.21 0.00 0.00 0.00 0.00 1.766.55 9.00 356.53 1.860.00 26.79 -13.76 227.21 0.00 0.00 0.00 0.00 1.766.55 9.00 356.53 1.860.00 26.79 -13.76 227.21 0.00 0.00 0.00 0.00 1.766.55 9.00 356.53 2.281.53 246.00 1.483 224.64 0.00 0.00 0.00 0.00 2.200.00 9.00 356.53 2.281.53 246.00 1.483 224.64 0.00 0.00 0.00 0.00 2.200.00 9.00 356.53 2.281.53 246.00 0.14.93 246.46 0.00 0.00 0.00 0.00 2.200.00 9.00 356.53 2.281.53 246.00 0.14.77 233.39 0.00 0.00 0.00 0.00 2.200.00 9.00 356.53 2.281.53 246.00 0.14.93 246.46 0.00 0.00 0.00 0.00 2.200.00 9.00 356.53 2.281.71 294.41 1.76.77 293.39 0.00 0.00 0.00 0.00 0.00 2.200.00 9.00 356.53 2.287.84 292.85 1.77.77 293.39 0.00 0.00 0.00 0.00 0.00 0.00 3.85.53 2.287.38 38.59 2.20.00 0.00 0.00 0.00 0.00 3.283.4				740.15	33.21	-2.14	35.27	2.00	2.00	0.00
900.00 9.00 356.53 896.31 58.63 -3.566 58.74 0.00 0.00 0.00 1.000.00 9.00 356.53 1.993.84 89.86 -5.45 90.02 0.00 0.00 0.00 0.00 1.200.00 9.00 356.53 1.993.84 89.86 -5.45 90.02 0.00 0.00 0.00 0.00 1.200.00 9.00 356.53 1.193.84 89.86 -5.45 90.02 0.00 0.00 0.00 0.00 1.202.67 9.00 356.53 1.215.00 109.01 -6.62 109.21 0.00 0.00 0.00 0.00 1.202.67 9.00 356.53 1.215.00 109.01 -6.62 109.21 0.00 0.00 0.00 0.00 1.202.67 9.00 356.53 1.215.00 109.01 -6.62 109.21 0.00 0.00 0.00 0.00 1.200 0.00 0.				707 54	43.01	-2 61	43.00	0.00	0.00	0.00
1,000.00 9.00 366.53 1,038.84 89.86 5.46 90.02 0.00 0.00 0.00 1.200.00 1.200.00 9.00 366.53 1,038.84 89.86 5.46 90.02 0.00 0.00 0.00 0.00 1.200.00 9.00 366.53 1,215.00 109.01 4.662 109.21 0.00 0.00 0.00 0.00 1.202.67 9.00 356.53 1,215.00 109.01 4.662 109.21 0.00 0.00 0.00 0.00 0.00 1.202.67 9.00 356.53 1,215.00 109.01 109.01 109.01 109.01 0.662 109.21 0.00 0.00 0.00 0.00 1.400.00 9.00 356.53 1,390.15 136.70 8.30 136.95 0.00 0.00 0.00 0.00 1.400.00 9.00 356.53 1,380.15 136.70 8.30 136.95 0.00 0.00 0.00 0.00 1.500.00 9.00 356.53 1,486.92 152.32 9.24 152.60 0.00 0.00 0.00 0.00 1.500.00 9.00 356.53 1,486.00 153.44 9.31 155.72 0.00 0.00 0.00 0.00 1.500.00 9.00 356.53 1,587.69 167.93 -10.19 168.24 0.00 0.00 0.00 1.700.00 1.700.00 9.00 356.53 1,587.69 167.93 -10.19 168.24 0.00 0.00 0.00 0.00 1.800.00 9.00 356.53 1,587.69 167.93 -10.19 168.24 0.00 0.00 0.00 0.00 1.800.00 9.00 356.53 1,785.22 199.16 -12.09 199.53 0.00 0.00 0.00 1.976.95 9.00 356.53 1,883.99 214.77 -13.03 215.17 0.00 0.00 0.00 1.976.95 9.00 356.53 1,883.99 214.77 -13.03 215.17 0.00 0.00 0.00 0.00 1.976.95 9.00 356.53 1,980.00 226.79 -13.76 227.21 0.00 0.00 0.00 0.00 2.200.00 9.00 356.53 1,980.00 226.79 -13.76 227.21 0.00 0.00 0.00 2.200.00 9.00 356.53 2,289.07 277.23 -16.83 277.74 0.00 0.00 0.00 2.200.00 9.00 356.53 2,289.07 277.23 -16.83 277.74 0.00 0.00 0.00 2.200.00 9.00 356.53 2,289.07 277.23 -16.83 277.74 0.00 0.00 0.00 0.00 2.410.00 9.00 356.53 2,287.81 292.44 17.77 293.39 0.00 0.00 0.00 0.00 2.400.00 9.00 356.53 2,287.81 292.44 17.77 293.39 0.00 0.00 0.00 0.00 2.400.00 9.00 356.53 2,287.81 292.44 17.77 293.39 0.00 0.00 0.00 0.00 2.300.00 9.00 356.53 2,287.81 294.41 17.87 294.95 0.00 0.00 0.00 0.00 2.400.00 9.00 356.53 2,287.81 294.41 17.87 294.95 0.00 0.00 0.00 0.00 2.505.91 9.00 356.53 2,287.81 294.41 17.87 294.95 0.00 0.00 0.00 0.00 2.505.91 9.00 356.53 2,288.31 3.589.90 2.20 2.20 2.20 0.00 0.00 2.505.91 9.00 356.53 2.278.81 308.60 -18.72 338.79 2.00 2.00 0.00 0.00 2.505.91 9.00 356.53 2.278.31 335.597 21.86 360.87 0.00 0.00 0.00 0.00 3.505.91 9										
1,100.00 9.00 366.53 1,109.384 89.86 -5.45 90.02 0.00 0.00 0.00 0.00 1,222.67 9.00 356.53 1,109.15 105.47 -6.40 105.67 0.00 0.00 0.00 0.00 1,222.67 9.00 356.53 1,1215.00 109.01 -6.62 109.21 0.00 0.00 0.00 0.00 1,222.67 9.00 356.53 1,291.38 121.09 -7.35 121.31 0.00 0.00 0.00 0.00 1.400.00 9.00 356.53 1,390.15 136.70 -8.30 136.95 0.00 0.00 0.00 1.507.17 9.00 356.53 1,488.92 152.32 -9.24 152.60 0.00 0.00 0.00 1.507.17 9.00 356.53 1,488.92 152.32 -9.24 152.60 0.00 0.00 0.00 0.00 1.507.17 9.00 356.53 1,488.92 152.32 -9.24 152.60 0.00 0.00 0.00 0.00 1.507.07 9.00 356.53 1,488.92 152.32 -9.24 152.60 0.00 0.00 0.00 0.00 1.507.07 9.00 356.53 1,488.92 152.32 -9.24 152.60 0.00 0.00 0.00 0.00 1.507.07 9.00 356.53 1,488.92 152.32 -9.24 152.60 0.00 0.00 0.00 0.00 1.507.07 9.00 356.53 1,488.92 152.32 -9.24 152.60 0.00 0.00 0.00 0.00 1.507.07 9.00 356.53 1,488.92 152.32 -9.24 152.60 0.00 0.00 0.00 0.00 1.507.07 9.00 356.53 1,488.92 152.32 -9.24 152.60 0.00 0.00 0.00 0.00 1.507.07 9.00 356.53 1,587.69 167.93 -10.19 168.24 0.00 0.00 0.00 0.00 1.700.00 9.00 356.53 1,883.99 214.77 -13.03 19.50 0.00 0.00 0.00 1.900.00 9.00 356.53 1,883.99 214.77 -13.03 125.70 0.00 0.00 0.00 1.900.00 9.00 356.53 1,883.99 214.77 -13.03 125.71 0.00 0.00 0.00 0.00 1.976.99 9.00 356.53 1,883.99 214.77 -13.03 125.71 0.00 0.00 0.00 0.00 1.976.99 9.00 356.53 1,883.99 244.77 -13.03 125.71 0.00 0.00 0.00 0.00 1.976.99 9.00 356.53 1,883.99 244.77 -13.03 125.71 0.00 0.00 0.00 0.00 1.976.90 9.00 356.53 1,883.99 244.77 -13.03 125.71 0.00 0.00 0.00 0.00 1.976.90 9.00 356.53 1,883.99 124.77 -13.03 125.71 0.00 0.00 0.00 0.00 0.20 0.00 0.00 0.0										
1,200.00 9.00 356.53 1,192.61 105.47 -6.40 105.67 0.00 0.00 0.00 0.00 1,222.67 9.00 356.53 1,215.00 109.01 -6.62 109.21 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0										
1,222,67 9,00 356,53 1,215,00 109,01 -6,62 109,21 0,00 0,00 0,00				,						
GREEN RIVER										
1,300.00 9.00 366.53 1,291.38 121.09 -7.35 121.31 0.00 0.00 0.00 1,400.00 9.00 366.53 1,390.15 136.70 8.30 136.95 0.00 0.00 0.00 0.00 1,507.17 9.00 356.53 1,496.00 153.44 -9.31 153.72 0.00 0.00 0.00 0.00 1,507.17 9.00 356.53 1,496.00 153.44 -9.31 153.72 0.00 0.00 0.00 0.00 1,507.17 9.00 356.53 1,496.00 153.44 -9.31 153.72 0.00 0.00 0.00 0.00 1,507.17 9.00 356.53 1,587.69 167.93 -10.19 168.24 0.00 0.00 0.00 1,700.00 9.00 356.53 1,686.46 183.55 -11.14 183.88 0.00 0.00 0.00 1,900 0.00 1,900 0.00 1,900 0.00 1,900 0.00 1,900 0.00 1,900 0.00 1,900 0.00 1,900 0.00 1,900 0.00 1,900 0.00 1,900 0.00 1,900 0.00 0.00 1,976.95 9.00 356.53 1,960.00 1,24.77 -13.03 215.17 0.00 0.00 0.00 0.00 1,976.95 9.00 356.53 1,960.00 226.79 -13.76 227.21 0.00 0.00 0.00 0.00 1,976.95 9.00 356.53 1,980.00 226.79 -13.76 227.21 0.00 0.00 0.00 0.00 1,976.95 9.00 356.53 1,980.00 226.79 -13.76 227.21 0.00 0.00 0.00 0.00 2,100 0.00 9.00 366.53 2,180.30 261.62 -15.88 262.10 0.00 0.00 0.00 0.00 2,300.00 9.00 356.53 2,180.30 261.62 -15.88 262.10 0.00 0.00 0.00 0.00 2,300.00 9.00 356.53 2,180.30 261.62 -15.88 262.10 0.00 0.00 0.00 0.00 2,410.00 9.00 356.53 2,377.84 292.85 -17.77 293.39 0.00 0.00 0.00 0.00 2,410.00 9.00 356.53 2,377.84 292.85 -17.77 293.39 0.00 0.00 0.00 0.00 2,410.00 9.00 356.53 2,377.84 292.85 -17.77 293.39 0.00 0.00 0.00 0.00 2,410.00 9.00 356.53 2,377.84 292.85 -17.77 293.39 0.00 0.00 0.00 0.00 2,605.91 9.00 356.53 2,575.38 324.08 -19.67 324.67 0.00 0.00 0.00 0.00 2,605.91 9.00 356.53 2,575.38 324.08 -19.67 324.67 0.00 0.00 0.00 0.00 2,605.91 9.00 356.53 2,575.38 325.00 -19.72 325.60 0.00 0.00 0.00 0.00 3,055.91 0.00 0.00 3,035.53 2,773.79 348.80 -21.17 394.55 2.00 -2.00 0.00 0.00 3,055.91 0.00 0.00 3,035.53 2,973.45 350.21 -21.86 360.87 0.00 0.00 0.00 0.00 3,000 0.00 0.00 3,000 0.00 0.			000.00	1,210.00	100.01	0.02	100.21	0.00	0.00	0.00
1,400 00 9.00 356.53 1,390.15 136.70 -8.30 136.95 0.00 0.00 0.00 1,507.17 9.00 356.53 1,486.92 152.32 -9.24 152.60 0.00 0.00 0.00 0.00 1,507.17 9.00 356.53 1,496.00 153.44 -8.31 153.72 0.00 0.00 0.00 0.00 1,507.17 9.00 356.53 1,587.69 167.93 -10.19 168.24 0.00 0.00 0.00 1,700.00 9.00 356.53 1,587.69 167.93 -10.19 168.24 0.00 0.00 0.00 1,700.00 9.00 356.53 1,785.22 199.16 -12.09 199.53 0.00 0.00 0.00 1,900.00 9.00 356.53 1,883.99 214.77 -13.03 215.17 0.00 0.00 0.00 1,976.95 9.00 356.53 1,960.00 226.79 -13.76 227.21 0.00 0.00 0.00 0.00 1,976.95 9.00 356.53 1,982.76 230.39 -13.98 230.81 0.00 0.00 0.00 0.00 2,100.00 9.00 356.53 2,081.53 246.00 -14.93 246.46 0.00 0.00 0.00 2,200.00 9.00 356.53 2,180.30 261.62 -15.88 262.10 0.00 0.00 0.00 2,200.00 9.00 356.53 2,387.71 294.41 -17.87 294.95 0.00 0.00 0.00 0.00 2,400.00 9.00 356.53 2,377.84 292.85 -17.77 293.39 0.00 0.00 0.00 0.00 2,410.00 9.00 356.53 2,377.84 292.85 -17.77 293.99 0.00 0.00 0.00 0.00 2,605.91 9.00 356.53 2,575.38 324.08 -19.67 324.67 0.00 0.00 0.00 0.00 2,605.91 9.00 356.53 2,575.38 324.08 -19.67 324.67 0.00 0.00 0.00 0.00 2,605.91 9.00 356.53 2,575.38 324.08 -19.67 324.67 0.00 0.00 0.00 0.00 2,605.91 9.00 356.53 2,575.38 324.08 -19.67 324.67 0.00 0.00 0.00 0.00 2,605.91 9.00 356.53 2,575.38 324.08 -19.67 324.67 0.00										
1,500.00 9.00 356.53 1,489.82 152.32 -9.24 152.60 0.00 0.00 0.00 0.00				,						
1,507.17 9.00 356.53 1,496.00 153.44 -9.31 153.72 0.00 0.00 0.00										
BIRDSNEST				,						
1,600.00 9.00 356.53 1,587.69 167.93 -10.19 168.24 0.00 0.00 0.00 0.00 1,700.00 9.00 356.53 1,686.46 183.55 -11.14 183.88 0.00 0.00 0.00 0.00 1,800.00 9.00 356.53 1,785.22 199.16 -12.09 199.53 0.00 0.00 0.00 0.00 1,900.00 9.00 356.53 1,883.99 214.77 -13.03 215.17 0.00 0.00 0.00 0.00 1,976.95 9.00 356.53 1,960.00 226.79 -13.76 227.21 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0		9.00	350.53	1,496.00	155.44	-9.51	155.72	0.00	0.00	0.00
1,700.00 9.00 356.53 1,686.46 183.55 -11.14 183.88 0.00 0.00 0.00 1,800.00 9.00 356.53 1,785.22 199.16 -12.09 199.53 0.00 0.00 0.00 0.00 1,900.00 9.00 356.53 1,883.99 214.77 -13.03 215.17 0.00 0.00 0.00 0.00 1,976.95 9.00 356.53 1,883.99 214.77 -13.03 215.17 0.00 0.00 0.00 0.00 0.00 MAHOGANY 2,000.00 9.00 356.53 1,982.76 230.39 -13.98 230.81 0.00 0.00 0.00 0.00 2,100.00 9.00 356.53 2,881.53 246.00 -14.93 246.46 0.00 0.00 0.00 0.00 2,200.00 9.00 356.53 2,180.30 261.62 -15.88 262.10 0.00 0.00 0.00 0.00 2,300.00 9.00 356.53 2,279.07 277.23 -16.83 277.74 0.00 0.00 0.00 0.00 2,410.00 9.00 356.53 2,377.84 292.85 -17.77 293.39 0.00 0.00 0.00 0.00 2,410.00 9.00 356.53 2,377.84 292.85 -17.77 293.39 0.00 0.00 0.00 0.00 2,410.00 9.00 356.53 2,378.71 294.41 -17.87 294.95 0.00 0.00 0.00 0.00 85/8" 2,500.00 9.00 356.53 2,476.61 308.46 -18.72 309.03 0.00 0.00 0.00 0.00 2,605.91 9.00 356.53 2,575.38 324.08 -19.67 324.67 0.00 0.00 0.00 0.00 2,605.91 9.00 356.53 2,575.38 324.08 -19.67 324.67 0.00 0.00 0.00 0.00 2,605.91 9.00 356.53 2,575.38 324.08 -19.67 324.67 0.00 0.00 0.00 0.00 2,605.91 9.00 356.53 2,575.38 324.08 -19.67 324.67 0.00 0.00 0.00 0.00 2,605.91 9.00 356.53 2,575.38 324.08 -19.67 324.67 0.00 0.00 0.00 0.00 2,605.91 9.00 356.53 2,575.38 324.08 -19.67 324.67 0.00 0.00 0.00 0.00 2,805.91 9.00 356.53 2,575.38 324.08 -19.67 324.67 0.00 0.00 0.00 0.00 2,805.91 9.00 356.53 2,575.38 338.79 2.00 2.00 0.00 0.00 3,505.91 9.00 356.53 2,575.38 338.79 2.00 2.00 0.00 0.00 0.00 0.00 0.00 0.0		9.00	356 53	1 597 60	167.03	10.10	169 24	0.00	0.00	0.00
1,800.00 9.00 356.53 1,785.22 199.16 -12.09 199.53 0.00 0.00 0.00 1,900.00 9.00 356.53 1,883.99 214.77 -13.03 215.17 0.00 0.00 0.00 0.00 1,900.00 9.00 356.53 1,883.99 214.77 -13.03 227.21 0.00 0.00 0.00 0.00 0.00 MAHOGANY 2,000.00 9.00 356.53 1,982.76 230.39 -13.98 230.81 0.00 0.00 0.00 0.00 2,200.00 9.00 356.53 2,081.53 246.00 -14.93 246.46 0.00 0.00 0.00 0.00 2,200.00 9.00 356.53 2,180.30 261.62 15.88 262.10 0.00 0.00 0.00 2,300.00 9.00 356.53 2,279.07 277.23 -16.83 277.74 0.00 0.00 0.00 0.00 2,400.00 9.00 356.53 2,377.84 292.85 -17.77 293.39 0.00 0.00 0.00 0.00 2,410.00 9.00 356.53 2,377.84 292.85 -17.77 293.39 0.00 0.00 0.00 0.00 2,410.00 9.00 356.53 2,377.84 292.85 -17.77 294.95 0.00 0.00 0.00 0.00 85/8" 2,500.00 9.00 356.53 2,476.61 308.46 -18.72 309.03 0.00 0.00 0.00 0.00 2,600.00 9.00 356.53 2,575.38 324.08 -19.67 324.67 0.00 0.00 0.00 0.00 2,600.00 9.00 356.53 2,575.38 324.08 -19.67 324.67 0.00 0.00 0.00 0.00 2,600.00 9.00 356.53 2,581.21 325.00 -19.72 325.60 0.00 0.00 0.00 0.00 0.00 0.00 0.00										
1,900.00 9.00 356.53 1,883.99 214.77 -13.03 215.17 0.00 0.00 0.00 0.00 1,976.95 9.00 356.53 1,960.00 226.79 -13.76 227.21 0.00 0.00 0.00 0.00 0.00 MAHOGANY 2,000.00 9.00 356.53 1,982.76 230.39 -13.98 230.81 0.00 0.00 0.00 0.00 2,100.00 9.00 356.53 2,881.53 246.00 -14.93 246.46 0.00 0.00 0.00 0.00 2,200.00 9.00 356.53 2,180.30 261.62 -15.88 262.10 0.00 0.00 0.00 0.00 2,300.00 9.00 356.53 2,279.07 277.23 -16.83 277.74 0.00 0.00 0.00 0.00 2,400.00 9.00 356.53 2,377.84 292.85 -17.77 293.39 0.00 0.00 0.00 0.00 2,410.00 9.00 356.53 2,387.71 294.41 -17.87 294.95 0.00 0.00 0.00 0.00 85/8" 2,500.00 9.00 356.53 2,476.61 308.46 -18.72 309.03 0.00 0.00 0.00 0.00 2,605.91 9.00 356.53 2,575.38 324.08 -19.67 324.67 0.00 0.00 0.00 0.00 2,605.91 9.00 356.53 2,575.38 324.08 -19.67 324.67 0.00 0.00 0.00 0.00 2,605.91 9.00 356.53 2,575.38 324.08 -19.67 324.67 0.00 0.00 0.00 0.00 0.00 2,605.91 9.00 356.53 2,575.38 324.08 -19.67 324.67 0.00 0.00 0.00 0.00 0.00 2,605.91 9.00 356.53 2,575.38 324.08 -19.67 324.67 0.00 0.00 0.00 0.00 0.00 0.00 0.00 0										
1,976.95										
MAHOGANY										
2,000.00 9.00 356.53 1,982.76 230.39 -13.98 230.81 0.00 0.00 0.00 2,100.00 9.00 356.53 2,081.53 246.00 -14.93 246.46 0.00 0.00 0.00 2,200.00 9.00 356.53 2,180.30 261.62 -15.88 262.10 0.00 0.00 0.00 2,300.00 9.00 356.53 2,279.07 277.23 -16.83 277.74 0.00 0.00 0.00 2,400.00 9.00 356.53 2,377.84 292.85 -17.77 293.39 0.00 0.00 0.00 2,410.00 9.00 356.53 2,387.71 294.41 -17.87 294.95 0.00 0.00 0.00 2,500.00 9.00 356.53 2,476.61 308.46 -18.72 309.03 0.00 0.00 0.00 2,600.00 9.00 356.53 2,575.38 324.08 -19.67 324.67 0.00 0.00 0.00			330.33	1,900.00	220.79	-13.70	221.21	0.00	0.00	0.00
2,100.00 9.00 356.53 2,180.30 261.62 -15.88 262.10 0.00 0.00 0.00 2,200.00 9.00 356.53 2,180.30 261.62 -15.88 262.10 0.00 0.00 0.00 0.00 2,300.00 9.00 356.53 2,279.07 277.23 -16.83 277.74 0.00 0.00 0.00 0.00 2,400.00 9.00 356.53 2,377.84 292.85 -17.77 293.39 0.00 0.00 0.00 0.00 2,410.00 9.00 356.53 2,387.71 294.41 -17.87 294.95 0.00 0.00 0.00 0.00 85/8" 2,500.00 9.00 356.53 2,476.61 308.46 -18.72 309.03 0.00 0.00 0.00 2,600.00 9.00 356.53 2,581.21 325.00 -19.72 325.60 0.00 0.00 0.00 0.00 0.00 2,605.91 9.00 356.53 2,581.21 325.00 -19.72 325.60 0.00 0.00 0.00 0.00 0.00 0.00 0.00			356 53	1 982 76	230 39	-13 98	230.81	0.00	0.00	0.00
2,200.00 9.00 356.53 2,180.30 261.62 -15.88 262.10 0.00 0.00 0.00 0.00 2,300.00 9.00 356.53 2,279.07 277.23 -16.83 277.74 0.00 0.00 0.00 0.00 2,400.00 9.00 356.53 2,377.84 292.85 -17.77 293.39 0.00 0.00 0.00 0.00 0.00 2,410.00 9.00 356.53 2,387.71 294.41 -17.87 294.95 0.00 0.00 0.00 0.00 85/8" 2,500.00 9.00 356.53 2,476.61 308.46 -18.72 309.03 0.00 0.00 0.00 0.00 2,600.00 9.00 356.53 2,575.38 324.08 -19.67 324.67 0.00 0.00 0.00 0.00 2,600.91 9.00 356.53 2,581.21 325.00 -19.72 325.60 0.00 0.00 0.00 0.00 0.00 0.00 0.00										
2,300.00 9.00 356.53 2,279.07 277.23 -16.83 277.74 0.00 0.00 0.00 2,400.00 9.00 366.53 2,377.84 292.85 -17.77 293.39 0.00 0.00 0.00 2,410.00 9.00 356.53 2,387.71 294.41 -17.87 294.95 0.00 0.00 0.00 8 5/8" 2,500.00 9.00 356.53 2,476.61 308.46 -18.72 309.03 0.00 0.00 0.00 2,600.00 9.00 356.53 2,575.38 324.08 -19.67 324.67 0.00 0.00 0.00 2,605.91 9.00 356.53 2,581.21 325.00 -19.72 325.60 0.00 0.00 0.00 2,700.00 7.12 356.53 2,674.37 338.17 -20.52 338.79 2.00 -2.00 0.00 2,800.00 5.12 356.53 2,873.53 355.97 -21.60 356.63 2.00 <				,						
2,400.00 9.00 356.53 2,377.84 292.85 -17.77 293.39 0.00 0.00 0.00 2,410.00 9.00 356.53 2,387.71 294.41 -17.87 294.95 0.00 0.00 0.00 8 5/8" 2,500.00 9.00 356.53 2,476.61 308.46 -18.72 309.03 0.00 0.00 0.00 2,600.00 9.00 356.53 2,575.38 324.08 -19.67 324.67 0.00 0.00 0.00 2,605.91 9.00 356.53 2,581.21 325.00 -19.72 325.60 0.00 0.00 0.00 Start Drop -2.00 2,700.00 7.12 356.53 2,674.37 338.17 -20.52 338.79 2.00 -2.00 0.00 2,800.00 5.12 356.53 2,773.79 348.80 -21.17 349.45 2.00 -2.00 0.00 3,000.00 3.12 356.53 2,873.53 355.97	,									
2,410.00 9.00 356.53 2,387.71 294.41 -17.87 294.95 0.00 0.00 0.00 8 5/8" 2,500.00 9.00 356.53 2,476.61 308.46 -18.72 309.03 0.00 0.00 0.00 2,600.00 9.00 356.53 2,575.38 324.08 -19.67 324.67 0.00 0.00 0.00 2,605.91 9.00 356.53 2,581.21 325.00 -19.72 325.60 0.00 0.00 0.00 Start Drop -2.00 2,700.00 7.12 356.53 2,674.37 338.17 -20.52 338.79 2.00 -2.00 0.00 2,800.00 5.12 356.53 2,873.53 355.97 -21.60 356.63 2.00 -2.00 0.00 3,000.00 1.12 356.53 2,973.46 359.66 -21.83 360.32 2.00 -2.00 0.00 3,055.91 0.00 0.00 3,029.36 360.21 -21.86<										
8 5/8" 2,500.00 9.00 356.53 2,476.61 308.46 -18.72 309.03 0.00 0.00 0.00 2,600.00 9.00 356.53 2,575.38 324.08 -19.67 324.67 0.00 0.00 0.00 2,605.91 9.00 356.53 2,581.21 325.00 -19.72 325.60 0.00 0.00 0.00 Start Drop -2.00 2,700.00 7.12 356.53 2,674.37 338.17 -20.52 338.79 2.00 -2.00 0.00 2,800.00 5.12 356.53 2,873.53 355.97 -21.60 356.63 2.00 -2.00 0.00 3,000.00 3.12 356.53 2,873.53 355.97 -21.60 356.63 2.00 -2.00 0.00 3,000.00 1.12 356.53 2,973.46 359.66 -21.83 360.32 2.00 -2.00 0.00 3,055.91 0.00 0.00 3,029.36 360.21 -21.86 360.87 0.00 0.00 0.00 3,200.00										
2,500.00 9.00 356.53 2,476.61 308.46 -18.72 309.03 0.00 0.00 0.00 2,600.00 9.00 356.53 2,575.38 324.08 -19.67 324.67 0.00 0.00 0.00 2,605.91 9.00 356.53 2,581.21 325.00 -19.72 325.60 0.00 0.00 0.00 Start Drop -2.00 2,700.00 7.12 356.53 2,674.37 338.17 -20.52 338.79 2.00 -2.00 0.00 2,800.00 5.12 356.53 2,873.53 355.97 -21.60 356.63 2.00 -2.00 0.00 3,000.00 3.12 356.53 2,873.53 355.97 -21.60 356.63 2.00 -2.00 0.00 3,000.00 1.12 356.53 2,973.46 359.66 -21.83 360.32 2.00 -2.00 0.00 3,055.91 0.00 0.00 3,029.36 360.21 -21.86 360.87 0.00 0.00 0.00 3,200.00 0.00 0.00 3,73.4	,	0.00	000.00	2,001			2000	0.00	0.00	0.00
2,600.00 9.00 356.53 2,575.38 324.08 -19.67 324.67 0.00 0.00 0.00 2,605.91 9.00 356.53 2,581.21 325.00 -19.72 325.60 0.00 0.00 0.00 Start Drop -2.00 2,700.00 7.12 356.53 2,674.37 338.17 -20.52 338.79 2.00 -2.00 0.00 2,800.00 5.12 356.53 2,773.79 348.80 -21.17 349.45 2.00 -2.00 0.00 2,900.00 3.12 356.53 2,873.53 355.97 -21.60 356.63 2.00 -2.00 0.00 3,000.00 1.12 356.53 2,973.46 359.66 -21.83 360.32 2.00 -2.00 0.00 3,055.91 0.00 0.00 3,029.36 360.21 -21.86 360.87 2.00 -2.00 0.00 3,200.00 0.00 0.00 3,173.45 360.21 -21.86 360.87 0.00 0.00 0.00 3,300.00 0.00 0.00 3,273.4		0.00	050.50	0.470.04	000.10	10.70	000.00	2.22	2.25	2.22
2,605.91 9.00 356.53 2,581.21 325.00 -19.72 325.60 0.00 0.00 0.00 Start Drop -2.00 2,700.00 7.12 356.53 2,674.37 338.17 -20.52 338.79 2.00 -2.00 0.00 2,800.00 5.12 356.53 2,773.79 348.80 -21.17 349.45 2.00 -2.00 0.00 2,900.00 3.12 356.53 2,873.53 355.97 -21.60 356.63 2.00 -2.00 0.00 3,000.00 1.12 356.53 2,973.46 359.66 -21.83 360.32 2.00 -2.00 0.00 3,055.91 0.00 0.00 3,029.36 360.21 -21.86 360.87 2.00 -2.00 0.00 Start 6979.64 hold at 3055.91 MD 3,100.00 0.00 3,073.45 360.21 -21.86 360.87 0.00 0.00 0.00 3,200.00 0.00 0.00 3,273.45 360.21	,									
Start Drop -2.00 2,700.00 7.12 356.53 2,674.37 338.17 -20.52 338.79 2.00 -2.00 0.00 2,800.00 5.12 356.53 2,773.79 348.80 -21.17 349.45 2.00 -2.00 0.00 2,900.00 3.12 356.53 2,873.53 355.97 -21.60 356.63 2.00 -2.00 0.00 3,000.00 1.12 356.53 2,973.46 359.66 -21.83 360.32 2.00 -2.00 0.00 3,055.91 0.00 0.00 3,029.36 360.21 -21.86 360.87 2.00 -2.00 0.00 Start 6979.64 hold at 3055.91 MD 3,100.00 0.00 3,073.45 360.21 -21.86 360.87 0.00 0.00 0.00 3,200.00 0.00 3,173.45 360.21 -21.86 360.87 0.00 0.00 0.00 3,300.00 0.00 0.00 3,273.45 360.21 -21.86										
2,700.00 7.12 356.53 2,674.37 338.17 -20.52 338.79 2.00 -2.00 0.00 2,800.00 5.12 356.53 2,773.79 348.80 -21.17 349.45 2.00 -2.00 0.00 2,900.00 3.12 356.53 2,873.53 355.97 -21.60 356.63 2.00 -2.00 0.00 3,000.00 1.12 356.53 2,973.46 359.66 -21.83 360.32 2.00 -2.00 0.00 3,055.91 0.00 0.00 3,029.36 360.21 -21.86 360.87 2.00 -2.00 0.00 Start 6979.64 hold at 3055.91 MD 3,100.00 0.00 0.00 3,073.45 360.21 -21.86 360.87 0.00 0.00 0.00 3,200.00 0.00 0.00 3,173.45 360.21 -21.86 360.87 0.00 0.00 0.00 3,300.00 0.00 0.00 3,273.45 360.21 -21.86 360.87 0.00 0.00 0.00 3,400.00 0.00 0.00			550.55	2,001.21	323.00	-13.12	525.00	0.00	0.00	0.00
2,800.00 5.12 356.53 2,773.79 348.80 -21.17 349.45 2.00 -2.00 0.00 2,900.00 3.12 356.53 2,873.53 355.97 -21.60 356.63 2.00 -2.00 0.00 3,000.00 1.12 356.53 2,973.46 359.66 -21.83 360.32 2.00 -2.00 0.00 3,055.91 0.00 0.00 3,029.36 360.21 -21.86 360.87 2.00 -2.00 0.00 Start 6979.64 hold at 3055.91 MD 3,100.00 0.00 0.00 3,073.45 360.21 -21.86 360.87 0.00 0.00 0.00 3,200.00 0.00 0.00 3,173.45 360.21 -21.86 360.87 0.00 0.00 0.00 3,300.00 0.00 0.00 3,273.45 360.21 -21.86 360.87 0.00 0.00 0.00 3,400.00 0.00 0.00 3,373.45 360.21 -21.86 360.87 0.00 0.00 0.00 3,500.00 0.00 0.00 <t< td=""><td>•</td><td></td><td>356 53</td><td>2 674 37</td><td>338 17</td><td>-20 52</td><td>338 79</td><td>2 00</td><td>-2 00</td><td>0.00</td></t<>	•		356 53	2 674 37	338 17	-20 52	338 79	2 00	-2 00	0.00
2,900.00 3.12 356.53 2,873.53 355.97 -21.60 356.63 2.00 -2.00 0.00 3,000.00 1.12 356.53 2,973.46 359.66 -21.83 360.32 2.00 -2.00 0.00 3,055.91 0.00 0.00 3,029.36 360.21 -21.86 360.87 2.00 -2.00 0.00 Start 6979.64 hold at 3055.91 MD 3,100.00 0.00 0.00 3,073.45 360.21 -21.86 360.87 0.00 0.00 0.00 3,200.00 0.00 0.00 3,173.45 360.21 -21.86 360.87 0.00 0.00 0.00 3,300.00 0.00 0.00 3,273.45 360.21 -21.86 360.87 0.00 0.00 0.00 3,400.00 0.00 0.00 3,373.45 360.21 -21.86 360.87 0.00 0.00 0.00 3,500.00 0.00 0.00 3,473.45 360.21 -21.86 360.87 0.00 0.00 0.00	,			,						
3,000.00 1.12 356.53 2,973.46 359.66 -21.83 360.32 2.00 -2.00 0.00 3,055.91 0.00 0.00 3,029.36 360.21 -21.86 360.87 2.00 -2.00 0.00 Start 6979.64 hold at 3055.91 MD 3,100.00 0.00 0.00 3,073.45 360.21 -21.86 360.87 0.00 0.00 0.00 3,200.00 0.00 0.00 3,173.45 360.21 -21.86 360.87 0.00 0.00 0.00 3,300.00 0.00 0.00 3,273.45 360.21 -21.86 360.87 0.00 0.00 0.00 3,400.00 0.00 0.00 3,373.45 360.21 -21.86 360.87 0.00 0.00 0.00 3,500.00 0.00 0.00 3,473.45 360.21 -21.86 360.87 0.00 0.00 0.00										
3,055.91 0.00 0.00 3,029.36 360.21 -21.86 360.87 2.00 -2.00 0.00 Start 6979.64 hold at 3055.91 MD 3,100.00 0.00 0.00 3,073.45 360.21 -21.86 360.87 0.00 0.00 0.00 0.00 3,200.00 0.00 0.00 3,173.45 360.21 -21.86 360.87 0.00 0.00 0.00 0.00 0.00 3,300.00 0.00	,									
Start 6979.64 hold at 3055.91 MD 3,100.00 0.00 0.00 3,073.45 360.21 -21.86 360.87 0.00 0.00 0.00 0.00 3,200.00 0.00 0.00 3,173.45 360.21 -21.86 360.87 0.00 0.00 0.00 0.00 3,300.00 0.00 0.00 3,273.45 360.21 -21.86 360.87 0.00 0.00 0.00 3,400.00 0.00 0.00 3,373.45 360.21 -21.86 360.87 0.00 0.00 0.00 3,500.00 0.00 0.00 3,473.45 360.21 -21.86 360.87 0.00 0.00 0.00										
3,100.00 0.00 0.00 3,073.45 360.21 -21.86 360.87 0.00 0.00 0.00 0.00 3,200.00 0.00 0.00 3,173.45 360.21 -21.86 360.87 0.00 0.00 0.00 0.00 3,300.00 0.00 0.00 3,273.45 360.21 -21.86 360.87 0.00 0.00 0.00 3,400.00 0.00 0.00 3,373.45 360.21 -21.86 360.87 0.00 0.00 0.00 3,500.00 0.00 0.00 3,473.45 360.21 -21.86 360.87 0.00 0.00 0.00				5,525.55	550.21	21.00	550.07	2.00	2.00	0.00
3,200.00 0.00 0.00 3,173.45 360.21 -21.86 360.87 0.00 0.00 0.00 3,300.00 0.00 0.00 3,273.45 360.21 -21.86 360.87 0.00 0.00 0.00 3,400.00 0.00 0.00 3,373.45 360.21 -21.86 360.87 0.00 0.00 0.00 3,500.00 0.00 0.00 3,473.45 360.21 -21.86 360.87 0.00 0.00 0.00				3.073.45	360.21	-21.86	360.87	0.00	0.00	0.00
3,300.00 0.00 0.00 3,273.45 360.21 -21.86 360.87 0.00 0.00 0.00 0.00 3,400.00 0.00 0.00 3,373.45 360.21 -21.86 360.87 0.00 0.00 0.00 0.00 3,500.00 0.00 0.00 3,473.45 360.21 -21.86 360.87 0.00 0.00 0.00	,			,						
3,400.00 0.00 0.00 3,373.45 360.21 -21.86 360.87 0.00 0.00 0.00 0.00 3,500.00 0.00 0.00 3,473.45 360.21 -21.86 360.87 0.00 0.00 0.00										
3,500.00 0.00 0.00 3,473.45 360.21 -21.86 360.87 0.00 0.00 0.00										
5,555.55 5.55 5.55 5,575.15 555. <u>E1.55 555.67 5.55 5.50 5.50</u>										
3,700.00 0.00 0.00 3,673.45 360.21 -21.86 360.87 0.00 0.00 0.00										



Planning Report



Database: Denver Sales

Company: US ROCKIES REGION PLANNING
Project: UTAH - UTM (feet), NAD27, Zone 12N

Site: NBU 1022-9J PAD

Well: NBU 1022-9J1CS

Wellbore: OH

Design: PLAN #1 PRELIMINARY

Local Co-ordinate Reference:

TVD Reference: MD Reference: North Reference:

Survey Calculation Method:

Well NBU 1022-9J1CS

GL 5208 & KB 4 @ 5212.00ft (ASSUMED) GL 5208 & KB 4 @ 5212.00ft (ASSUMED)

True

lanned Survey									
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
3,800.00	0.00	0.00	3,773.45	360.21	-21.86	360.87	0.00	0.00	0.00
3,900.00	0.00	0.00	3,873.45	360.21	-21.86	360.87	0.00	0.00	0.00
4,000.00	0.00	0.00	3,973.45	360.21	-21.86	360.87	0.00	0.00	0.00
4,100.00	0.00	0.00	4,073.45	360.21	-21.86	360.87	0.00	0.00	0.00
4,200.00	0.00	0.00	4,173.45	360.21	-21.86	360.87	0.00	0.00	0.00
4,300.00	0.00	0.00	4,273.45	360.21	-21.86	360.87	0.00	0.00	0.00
4,349.15	0.00	0.00	4,322.60	360.21	-21.86	360.87	0.00	0.00	0.00
WASATCH									
4,400.00	0.00	0.00	4,373.45	360.21	-21.86	360.87	0.00	0.00	0.00
4,500.00	0.00	0.00	4,473.45	360.21	-21.86	360.87	0.00	0.00	0.00
4,600.00	0.00	0.00	4,573.45	360.21	-21.86	360.87	0.00	0.00	0.00
4,700.00	0.00	0.00	4,673.45	360.21	-21.86	360.87	0.00	0.00	0.00
4,800.00	0.00	0.00	4,773.45	360.21	-21.86	360.87	0.00	0.00	0.00
4,900.00	0.00	0.00	4,873.45	360.21	-21.86	360.87	0.00	0.00	0.00
5,000.00	0.00	0.00	4,973.45	360.21	-21.86	360.87	0.00	0.00	0.00
5,100.00	0.00	0.00	5,073.45	360.21	-21.86	360.87	0.00	0.00	0.00
5,200.00 5,300.00	0.00 0.00	0.00 0.00	5,173.45 5,273.45	360.21 360.21	-21.86 -21.86	360.87 360.87	0.00 0.00	0.00 0.00	0.00 0.00
5,400.00	0.00	0.00	5,373.45	360.21	-21.86	360.87	0.00	0.00	0.00
5,500.00	0.00	0.00	5,373.45 5,473.45	360.21	-21.86	360.87	0.00	0.00	0.00
5,600.00	0.00	0.00	5,573.45	360.21	-21.86	360.87	0.00	0.00	0.00
5,700.00	0.00	0.00	5,673.45	360.21	-21.86	360.87	0.00	0.00	0.00
5,800.00	0.00	0.00	5,773.45	360.21	-21.86	360.87	0.00	0.00	0.00
5,900.00	0.00	0.00	5,873.45	360.21	-21.86	360.87	0.00	0.00	0.00
6,000.00	0.00	0.00	5,973.45	360.21	-21.86	360.87	0.00	0.00	0.00
6,100.00	0.00	0.00	6,073.45	360.21	-21.86	360.87	0.00	0.00	0.00
6,200.00	0.00	0.00	6,173.45	360.21	-21.86	360.87	0.00	0.00	0.00
6,300.00	0.00	0.00	6,273.45	360.21	-21.86	360.87	0.00	0.00	0.00
6,400.00	0.00	0.00	6,373.45	360.21	-21.86	360.87	0.00	0.00	0.00
6,500.00	0.00	0.00	6,473.45	360.21	-21.86	360.87	0.00	0.00	0.00
6,600.00	0.00	0.00	6,573.45	360.21	-21.86	360.87	0.00	0.00	0.00
6,700.00	0.00	0.00	6,673.45	360.21	-21.86	360.87	0.00	0.00	0.00
6,800.00	0.00	0.00	6,773.45	360.21	-21.86	360.87	0.00	0.00	0.00
6,828.55	0.00	0.00	6,802.00	360.21	-21.86	360.87	0.00	0.00	0.00
MESAVERD	E								
6,900.00	0.00	0.00	6,873.45	360.21	-21.86	360.87	0.00	0.00	0.00
7,000.00	0.00	0.00	6,973.45	360.21	-21.86	360.87	0.00	0.00	0.00
7,100.00	0.00	0.00	7,073.45	360.21	-21.86	360.87	0.00	0.00	0.00
7,200.00	0.00	0.00	7,173.45	360.21	-21.86	360.87	0.00	0.00	0.00
7,300.00	0.00	0.00	7,273.45	360.21	-21.86	360.87	0.00	0.00	0.00
7,400.00	0.00	0.00	7,373.45	360.21	-21.86	360.87	0.00	0.00	0.00
7,500.00	0.00	0.00	7,473.45	360.21	-21.86	360.87	0.00	0.00	0.00
7,600.00	0.00	0.00	7,573.45	360.21	-21.86	360.87	0.00	0.00	0.00
7,700.00	0.00	0.00	7,573.45 7,673.45	360.21	-21.86	360.87	0.00	0.00	0.00
7,700.00	0.00	0.00	7,073.45	360.21	-21.86	360.87	0.00	0.00	0.00
7,900.00	0.00	0.00	7,873.45	360.21	-21.86	360.87	0.00	0.00	0.00
8,000.00	0.00	0.00	7,973.45	360.21	-21.86	360.87	0.00	0.00	0.00
8,100.00	0.00	0.00	8,073.45	360.21	-21.86	360.87	0.00	0.00	0.00
8,200.00	0.00	0.00	8,173.45	360.21	-21.86	360.87	0.00	0.00	0.00
8,300.00 8,400.00	0.00 0.00	0.00 0.00	8,273.45 8,373.45	360.21 360.21	-21.86 -21.86	360.87 360.87	0.00 0.00	0.00 0.00	0.00 0.00
8,400.00 8,500.00	0.00	0.00	8,373.45 8,473.45	360.21	-21.86 -21.86	360.87 360.87	0.00	0.00	0.00
			,						
8,600.00	0.00	0.00	8,573.45	360.21	-21.86	360.87	0.00	0.00	0.00
8,700.00	0.00	0.00	8,673.45	360.21	-21.86	360.87	0.00	0.00	0.00



Planning Report



Database: Denver Sales

Company: US ROCKIES REGION PLANNING
Project: UTAH - UTM (feet), NAD27, Zone 12N

 Site:
 NBU 1022-9J PAD

 Well:
 NBU 1022-9J1CS

Wellbore: OH

Design: PLAN #1 PRELIMINARY

Local Co-ordinate Reference:

TVD Reference:
MD Reference:
North Reference:

Survey Calculation Method:

Well NBU 1022-9J1CS

GL 5208 & KB 4 @ 5212.00ft (ASSUMED) GL 5208 & KB 4 @ 5212.00ft (ASSUMED)

True

Measured Depth	Inclination	Azimuth	Vertical Depth	+N/-S	+E/-W	Vertical Section	Dogleg Rate	Build Rate	Turn Rate
(ft)	(°)	(°)	(ft)	(ft)	(ft)	(ft)	(°/100usft)	(°/100usft)	(°/100usft)
8,800.00 8,900.00 8,906.55	0.00 0.00 0.00	0.00 0.00 0.00	8,773.45 8,873.45 8,880.00	360.21 360.21 360.21	-21.86 -21.86 -21.86	360.87 360.87 360.87	0.00 0.00 0.00	0.00 0.00 0.00	0.00 0.00 0.00
SEGO - SEG	O_NBU 1022-9J	1CS							
8,987.55	0.00	0.00	8,961.00	360.21	-21.86	360.87	0.00	0.00	0.00
CASTLEGAT	ΓE								
9,000.00 9,100.00 9,200.00 9,300.00	0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00	8,973.45 9,073.45 9,173.45 9,273.45	360.21 360.21 360.21 360.21	-21.86 -21.86 -21.86 -21.86	360.87 360.87 360.87 360.87	0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00
9,400.00 9,435.55	0.00 0.00	0.00 0.00	9,373.45 9,409.00	360.21 360.21	-21.86 -21.86	360.87 360.87	0.00 0.00	0.00 0.00	0.00 0.00
BLACKHAW									
9,500.00 9,600.00 9,700.00	0.00 0.00 0.00	0.00 0.00 0.00	9,473.45 9,573.45 9,673.45	360.21 360.21 360.21	-21.86 -21.86 -21.86	360.87 360.87 360.87	0.00 0.00 0.00	0.00 0.00 0.00	0.00 0.00 0.00
9,800.00 9,900.00 10,000.00 10,035.55	0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00	9,773.45 9,873.45 9,973.45 10,009.00	360.21 360.21 360.21 360.21	-21.86 -21.86 -21.86 -21.86	360.87 360.87 360.87 360.87	0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00	0.00 0.00 0.00 0.00

Design Targets									
Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (usft)	Easting (usft)	Latitude	Longitude
SEGO_NBU 1022-9J1C - plan hits target cent - Circle (radius 25.00		0.00	8,880.00	360.21	-21.86	14,516,216.39	2,077,234.48	39.9625270	-109.4411470
PBHL_NBU 1022-9J1C\$ - plan hits target cent - Circle (radius 100.0		0.00	10,009.00	360.21	-21.86	14,516,216.39	2,077,234.48	39.9625270	-109.4411470

Casing Points							
	Measured	Vertical			Casing	Hole	
	Depth	Depth			Diameter	Diameter	
	(ft)	(ft)		Name	(in)	(in)	
	2,410.00	2,387.71	8 5/8"		8.625	11.000	



Planning Report



Database: Denver Sales

Company: US ROCKIES REGION PLANNING
Project: UTAH - UTM (feet), NAD27, Zone 12N

 Site:
 NBU 1022-9J PAD

 Well:
 NBU 1022-9J1CS

Wellbore: OH

Design: PLAN #1 PRELIMINARY

Local Co-ordinate Reference:

TVD Reference: MD Reference: North Reference:

Survey Calculation Method:

Well NBU 1022-9J1CS

GL 5208 & KB 4 @ 5212.00ft (ASSUMED) GL 5208 & KB 4 @ 5212.00ft (ASSUMED)

True

ormations							
	Measured Depth (ft)	Vertical Depth (ft)	Name	Lithology	Dip (°)	Dip Direction (°)	
	1,222.67	1,215.00	GREEN RIVER				
	1,507.17	1,496.00	BIRDSNEST				
	1,976.95	1,960.00	MAHOGANY				
	4,349.15	4,322.60	WASATCH				
	6,828.55	6,802.00	MESAVERDE				
	8,906.55	8,880.00	SEGO				
	8,987.55	8,961.00	CASTLEGATE				
	9,435.55	9,409.00	BLACKHAWK				

Plan Annotations				
Measured	Vertical	Local Coor	dinates	
Depth	Depth	+N/-S	+E/-W	
(ft)	(ft)	(ft)	(ft)	Comment
300.00	300.00	0.00	0.00	Start Build 2.00
750.00	748.15	35.21	-2.14	Start 1855.90 hold at 750.00 MD
2,605.91	2,581.21	325.00	-19.72	Start Drop -2.00
3,055.91	3,029.36	360.21	-21.86	Start 6979.64 hold at 3055.91 MD
10,035.55	10,009.00	360.21	-21.86	TD at 10035.55

Surface Use Plan of Operations 1 of 6

NBU 1022-9G4CS/1022-9H3AS/1022-9H4CS/1022-9I1BS/1022-9I1DS/ 1022-9J1CS/NBU1022-9J1BS Kerr-McGee Oil Gas Onshore, L.P.

Kerr-McGee Oil & Gas Onshore, L.P.

NBU 1022-9J PAD

NBU 1022-9G4CS		
1917 FSL / 1784 FEL	NWSE	Lot
2359 FNL / 1825 FEL	SWNE	Lot
NBU 1022-9H3AS		
1926 FSL / 1766 FEL	NWSE	Lot
2219 FNL / 671 FEL	SENE	Lot
NBU 1022-9H4CS		
1935 FSL / 1748 FEL	NWSE	Lot
2613 FNL / 492 FEL	SENE	Lot
NBU 1022-911BS		
1931 FSL / 1757 FEL	NWSE	Lot
2331 FSL / 493 FEL	NESE	Lot
NBU 1022-911DS		
1922 FSL / 1775 FEL	NWSE	Lot
1980 FSL / 301 FEL	NESE	Lot
NBU 1022-9J1CS		
1913 FSL / 1793 FEL	NWSE	Lot
2273 FSL / 1814 FEL	NWSE	Lot
NBU 1022-9J1BS		
1908 FSL / 1802 FEL	NWSE	Lot
2576 FSL / 1794 FEL	NWSE	Lot
	1917 FSL / 1784 FEL 2359 FNL / 1825 FEL NBU 1022-9H3AS 1926 FSL / 1766 FEL 2219 FNL / 671 FEL NBU 1022-9H4CS 1935 FSL / 1748 FEL 2613 FNL / 492 FEL NBU 1022-911BS 1931 FSL / 1757 FEL 2331 FSL / 493 FEL NBU 1022-911DS 1922 FSL / 1775 FEL 1980 FSL / 301 FEL NBU 1022-9J1CS 1913 FSL / 1793 FEL 2273 FSL / 1814 FEL	1917 FSL / 1784 FEL 2359 FNL / 1825 FEL NBU 1022-9H3AS 1926 FSL / 1766 FEL 2219 FNL / 671 FEL NBU 1022-9H4CS 1935 FSL / 1748 FEL 2613 FNL / 492 FEL NBU 1022-911BS 1931 FSL / 1757 FEL 2331 FSL / 1757 FEL 2331 FSL / 493 FEL NBU 1022-911DS 1922 FSL / 1775 FEL 1980 FSL / 301 FEL NBU 1022-9J1CS 1913 FSL / 1793 FEL 2273 FSL / 1814 FEL NWSE NBU 1022-9J1BS 1908 FSL / 1802 FEL NWSE

This Surface Use Plan of Operations (SUPO) or 13-point plan provides site-specific information for the above-referenced wells.

In accordance with Utah Oil & Gas Conservation Rule R649-3-11 pertaining to Directional Drilling, these wells will be directionally drilled. Refer to Topo Map A for directions to the location and Topo Maps A and B for location of access roads within a 2-mile radius.

An on-site meeting was held on October 23,2013. Present were:

- · Tyler Cox and Jessi Brunson BLM;
- Mitch Batty Timberline Engineering & Land Surveying, Inc.; and
- · Cara Mahler, Kenny Warren, Casey McKee, Chantill Recker, Doreen Green, and Howdy Brown - Kerr-McGee

A. Existing Roads:

NBU 1022-9G4CS/1022-9H3AS/1022-9H4CS/1022-9I1BS/1022-9I1DS/ 1022-9J1CS/NBU1022-9J1BS Kerr-McGee Oil Gas Onshore, L.P. Surface Use Plan of Operations 2 of 6

Please refer to the Standard Operating Practices on file at the BLM Vernal Field Office dated October 31, 2012.

Please refer to Topo B for existing roads.

RECEIVED: March 04, 2015

NBU 1022-9G4CS/1022-9H3AS/1022-9H4CS/1022-9I1BS/1022-9I1DS/ 1022-9J1CS/NBU1022-9J1BS Kerr-McGee Oil Gas Onshore, L.P. Surface Use Plan of Operations 3 of 6

B. New or Reconstructed Access Roads:

Please refer to the Standard Operating Practices on file at the BLM Vernal Field Office dated October 31, 2012.

No new access road is proposed

C. Location of Existing Wells:

Please refer to Topo C for exiting wells.

D. Location of Existing and/or Proposed Facilities:

Please refer to the Standard Operating Practices on file at the BLM Vernal Field Office dated October 31, 2012.

This pad will expand the existing pad for the NBU 1022-9J, which is a producing gas well according to Utah Division of Oil, Gas and Mining (UDOGM) records on January 9, 2014. Gathering (pipeline) infrastructure will be utilized to collect and transport gas and fluids from the wells which are owned and operated by Kerr McGee Oil and Gas Onshore LP (Kerr-McGee).

GAS GATHERING

Please refer to Exhibit A and Topo D2- Pad and Pipeline Detail.

The total gas gathering pipeline distance from the meter to the tie in point is ± 290 ' and ± 785 of proposed pipeline re-route the individual segments are broken up as follows:

The following segments are "onlease", no ROW needed.

- ±180' (0.03 miles) Section 9 T10S R22E (NW/4 SE/4) On-lease UTU01196-D, BLM surface, New 10" buried gas gathering pipeline from the meter to the edge of the pad. Please refer to Topo D2 Pad and Pipeline Detail.
- ±110' (0.02 miles) Section 9 T10S R22E (NW/4 SE/4) On-lease UTU01196-D, BLM surface, New 10" buried gas gathering pipeline from the edge of the pad traversing northerly to an existing 16" gas pipeline. Please refer to Topo D2 -Pad and Pipeline Detail and Exhibit A Line No. 2.
- ±645' (0.12 miles) Section 9 T10S R22E (NW/4 SE/4) On-lease UTU01196-D, BLM surface, New 4" surface pipeline re-route around easterly edge of the pad. Please refer to Topo D2 Pad and Pipeline Detail.
- ±75' (0.01 miles) Section 9 T10S R22E (NW/4 SE/4) On-lease UTU01196-D, BLM surface, New 8" surface expansion loop re-route on existing pipeline west of the pad. Please refer to Topo D2 Pad and Pipeline Detail and Exhibit A Line No. 12.
- ± 65 ' (0.01 miles) Section 9 T10S R22E (NW/4 SE/4) On-lease UTU01196-D, BLM surface, New 12" surface expansion loop re-route on existing pipeline west of the pad. Please refer to Topo D2 Pad and Pipeline Detail.

LIQUID GATHERING

Please refer to Exhibit B and Topo D2- Pad and Pipeline Detail.

The total liquid gathering pipeline distance from the separator to the tie in point is ± 290 ' and the individual segments are broken up as follows:

NBU 1022-9G4CS/1022-9H3AS/1022-9H4CS/1022-9I1BS/1022-9I1DS/ 1022-9J1CS/NBU1022-9J1BS Kerr-McGee Oil Gas Onshore, L.P. Surface Use Plan of Operations 4 of 6

The following segments are "onlease", no ROW needed.

- ±180' (0.03 miles) Section 9 T10S R22E (NW/4 SE/4) On-lease UTU01196-D, BLM surface, New 6" buried liquid gathering pipeline from the separator to the edge of the pad. Please refer to Topo D2 Pad and Pipeline Detail.
- $\pm 110^{\circ}$ (0.02 miles) Section 9 T10S R22E (NW/4 SE/4) On-lease UTU01196-D, BLM surface, New 6" buried liquid gathering pipeline from the edge of the pad traversing northerly to an existing 6" liquid pipeline. Please refer to Topo D2 Pad and Pipeline Detail and Exhibit B Line No. 2.

Pipeline Gathering Construction

Please refer to the Standard Operating Practices on file at the BLM Vernal Field Office dated October 31, 2012.

The Anadarko Completions Transportation System (ACTS) information:

Please refer to the Standard Operating Practices on file at the BLM Vernal Field Office dated October 31, 2012.

Please refer to Exhibit C for ACTS Lines

E. Location and Types of Water Supply:

Please refer to the Standard Operating Practices on file at the BLM Vernal Field Office dated October 31, 2012.

Water will be hauled to location over the roads marked on Maps A and B.

F. Construction Materials:

Please refer to the Standard Operating Practices on file at the BLM Vernal Field Office dated October 31, 2012.

G. Methods for Handling Waste:

Please refer to the Standard Operating Practices on file at the BLM Vernal Field Office dated October 31, 2012.

Materials Management

Please refer to the Standard Operating Practices on file at the BLM Vernal Field Office dated October 31, 2012.

H. Ancillary Facilities:

No additional ancillary facilities are planned for this location.

I. Well Site Layout:

Please refer to the Standard Operating Practices on file at the BLM Vernal Field Office dated October 31, 2012.

NBU 1022-9G4CS/1022-9H3AS/1022-9H4CS/1022-9I1BS/1022-9I1DS/ 1022-9J1CS/NBU1022-9J1BS

Surface Use Plan of Operations 5 of 6

Kerr-McGee Oil Gas Onshore, L.P.

J. Plans for Surface Reclamation:

Please refer to the Standard Operating Practices on file at the BLM Vernal Field Office dated October 31, 2012.

Interim Reclamation

Please refer to the Standard Operating Practices on file at the BLM Vernal Field Office dated October 31, 2012.

Final Reclamation

Please refer to the Standard Operating Practices on file at the BLM Vernal Field Office dated October 31, 2012.

Measures Common to Interim and Final Reclamation

Please refer to the Standard Operating Practices on file at the BLM Vernal Field Office dated October 31, 2012.

Weed Control

Please refer to the Standard Operating Practices on file at the BLM Vernal Field Office dated October 31, 2012.

Monitoring

Please refer to the Standard Operating Practices on file at the BLM Vernal Field Office dated October 31, 2012.

K. Surface/Mineral Ownership:

United States of America Bureau of Land Management 170 South 500 East Vernal, UT 84078 (435)781-4400

L. Other Information:

Cultural and Paleontological Resources

Please refer to the Standard Operating Practices on file at the BLM Vernal Field Office dated October 31, 2012.

Resource Reports:

A Class I literature survey was completed on August 7, 2013 by Montgomery Archaeological Consultants, Inc (MOAC). For additional details please refer to report MOAC 13-208.

A paleontological reconnaissance survey was completed on July 23, 2013 by SWCA Environmental Consultants. For additional details please refer to report UT13-14314-136.

Biological field survey was completed on July 27, 2013 by Grasslands Consulting, Inc (GCI). For additional details please refer to report GCI-909.

NBU 1022-9G4CS/1022-9H3AS/1022-9H4CS/1022-9I1BS/1022-9I1DS/ 1022-9J1CS/NBU1022-9J1BS Kerr-McGee Oil Gas Onshore, L.P. Surface Use Plan of Operations 6 of 6

Proposed Action Annual Emissions Tables:

Please refer to the Appendix in the Standard Operating Practices on file at the BLM Vernal Field Office dated October 31, 2012.

M. Lessee's or Operators' Representative & Certification:

Joel Malefyt Regulatory Analyst II Kerr-McGee Oil & Gas Onshore LP PO Box 173779 Denver, CO 80217-3779 (720) 929-6828 Tommy Thompson General Manager, Drilling Kerr-McGee Oil & Gas Onshore LP PO Box 173779 Denver, CO 80217-3779 (720) 929-6724

Certification: All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved Plan of Operations, and any applicable Notice to Lessees.

The Operator will be fully responsible for the actions of its subcontractors. A complete copy of the approved "Application for Permit to Drill" will be furnished to the field representative(s) to ensure compliance and shall be on location during all construction and drilling operations.

Kerr-McGee Oil & Gas Onshore LP is considered to be the operator of the subject well. Kerr-McGee Oil & Gas Onshore LP agrees to be responsible under terms and conditions of the lease for the operations conducted upon leased lands.

Bond coverage pursuant to 43 CFR 3104 for lease activities is being provided by Bureau of Land Management Nationwide Bond WYB000291.

I hereby certify that I, or persons under my supervision, have inspected the proposed drill site and access route, that I am familiar with the conditions that currently exist; that I have full knowledge of the State and Federal laws applicable to this operation; that the statements made in this plan are, to the best of my knowledge, true and correct; and the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.

	January 15, 2014
Joel Malefyt	Date

Kerr-McGee Oil & Gas Onshore L.P., wholly owned subsidiary of Anadarko Petroleum Corporation, Standard Operating Practice Agreement for the Greater Natural Buttes Field

Drilling Program

All lease and/or unit operations will be conducted in such a manner that full compliance is made with applicable laws, regulations, Onshore Oil and Gas Orders, and the approved plan of operation. As Operator, KMG is fully responsible for actions of subcontractors. A copy of these Standard Operating Practices will be furnished to the field representatives to insure compliance.

Bureau of Land Management Notification Requirements:

Location Constructions: At least 48 hours prior to construction of location and access roads including notification, if applicable, to other surface management agencies, such as Ute Tribe Energy and Mineral Department, State of Utah, or private surface owner(s).

Location Completion: Prior to moving on the drilling rig

Spud Notice: At least 24 hours prior to spudding the well.

Casing String and Cementing: At least 24 hours prior to running casing and cementing all casing.

Blow Out Preventer & Related Equipment Tests: At least 24 hours prior to initiating pressure tests.

First Production Notice: Within 5 days after a new well begins production; or, within 5 days of when production resumes after a well has been off production for more than 90 days.

Details of the on-site inspection, including date, time, weather conditions, and individuals present, will be submitted with the site-specific Application for Permit to Drill (APD).

1. Estimated Tops of Important Geologic Markers:

Formation and depths will be submitted with site-specific APDs.

2. Estimated Depths of Anticipated Water, Oil, Gas, or Mineral Formations:

Formation and depths will be submitted with site-specific APDs.

3. Pressure Control Equipment:

Pressure Control Equipment Schematic is attached as appendix F. Any variance will be included in the site-specific APDs.

4. Proposed Casing & Cementing Program:

Proposed casing and cementing will be submitted with site-specific APDs.

5. Drilling Fluids Program:

Proposed drilling fluids will be submitted with site-specific APDs.

6. Evaluation Program:

Evaluation program will be submitted with site-specific APDs.

7. Abnormal Conditions:

Any abnormal condition will be submitted with site specific APDs.

8. Anticipated Starting Dates:

Drilling is planned to commence within the administrative period of an approved application.

9. Variances:

KMG respectfully requests a variance to several requirements associated with air drilling outlined in OSO 2:

Variance for air drilling

Air rig is only used by KMG to construct a stable surface casing hole through a historically difficult lost circulation zone. A conventional rotary rig follows the air rig and is used to drill and construct the majority of the wellbore.

KMG typically utilizes an air rig for drilling the surface casing hole, an interval from the surface to surface casing depths, which varies in depth from 1,700 to 3,200 MD. The air rig drilling operation does not drill through productive or over pressured formations in KMG field, but does penetrate the Uinta and Green River Formations. The purpose of the air drilling operation is to overcome the severe loss circulation zone in the Green River known as the Bird's Nest while creating a stable hole for the surface casing. The surface casing hole is generally drilled to approximately 500 feet below the Bird's Nest.

Before the surface air rig is mobilized, a rathole rig is utilized to set and cement conductor pipe through a competent surface formation. Generally, the conductor is set at 40 feet. In some cases, conductor may be set deeper in areas that the surface formation is not found competent. This rig

also drills the rat and mouse holes in preparation for the surface casing and production string drilling operations.

The air rig is then mobilized to drill the surface casing hole by drilling a 12 1/4 inch hole for the first 200 feet, then will drill an 11inch hole to just above the Bird's Nest Interval. with an air hammer. The hammer is then tripped and replaced with an 11 inch tri-cone bit. The tri-cone bit is used to drill to the surface casing point, approximately 500 feet below the loss circulation zone (Bird's Nest). The 8-5/8 inch surface casing is then run and cemented in place, thereby isolating the lost circulation zone.

Variance for BOPE Requirements

The air rig operation utilizes a properly lubricated and maintained air bowl diverter system which diverts the drilling returns to a six-inch blooie line. The air bowl is the only piece of BOPE equipment which is installed during drilling operations and is sufficient to contain the air returns associated with this drilling operation. As was discussed earlier, the drilling of the surface hole does not encounter any over pressured or productive zones, and as a result standard BOPE equipment should not be required. In addition, standard drilling practices do not support the use of BOPE on 40 feet of conductor pipe.

Variance for Mud Material Requirements

OSO 2 also states that sufficient quantities of mud materials shall be maintained or readily accessible for the purpose of assuring adequate well control. Once again, the surface hole drilling operations does not encounter over pressured or productive intervals, and as a result there is not a need to control pressure in the surface hole with a mud system. Instead of mud, the air rigs utilize water from the reserve pit for well control, if necessary. A skid pump, which is located near the reserve pit, will supply the water to the well bore.

Variance for Special Drilling Operation (surface equipment placement)

OSO 2 requires specific safety distances or setbacks for the placement of associated standard air drilling equipment, wellbore, and reserve pits. The air rigs used to drill the surface holes are not typical of an air rig used to drill a producing hole in other parts of the US. These are smaller in nature and designed to fit a KMG location.

Typically the blooie line discharge point is required to be 100 feet from the well bore. In the case of a KMG well, the reserve pit is only 45 feet from the rig and is used for the drill cuttings. The blooie line, which transports the drill cuttings from the well to the reserve pit, subsequently discharges only 45 feet from the well bore.

Typically the air rig compressors are required to be located in the opposite direction from the blooie line and a minimum of 100 feet from the well bore. At the KMG locations, the air rig compressors are approximately 40 feet from the well bore and approximately 60 feet from the blooie line discharge due to the unique air rig design. The air compressors are located on the rig (1250 cfm) and on a standby trailer (1170 cfm). A booster sits between the two compressors and

boosts the output from 350 psi to 2000 psi. The design does put the booster and standby compressor opposite from the blooie line.

Lastly, OSO 2 addresses the need for an automatic igniter or continuous pilot light on the blooie line. The air rig does not utilize an igniter as the surface hole drilling operation does not encounter productive formations.

Variance for FIT Requirements

KMG also respectfully requests a variance to OSO 2, Section III, Part Bi, for the pressure integrity test (PIT, also known as a formation integrity test (FIT)). These wells are not exploratory wells and are being drilled in an area where the formation integrity is well known.

10. Other Information:

Drilling Program will be submitted with site-specific APDs.

SURFACE USE PROGRAM

A. Existing Roads:

Existing roads consist of county and improved/unimproved access roads (two-tracks). In accordance with OSO 1, KMG will improve or maintain existing roads in a condition that is the same as or better than before operations began. New or reconstructed proposed access roads are discussed in Section B.

The existing roads will be maintained in a safe and usable condition. Maintenance for existing roads will continue until final abandonment and reclamation of well pads and/or other facilities, as applicable. Road maintenance will include, but is not limited to, blading, ditching, and/or culvert installation and cleanout. To ensure safe operating conditions, gravel surfacing may be performed where excessive rutting or erosion may occur. Dust control may be performed as necessary to ensure safe operating conditions.

Roads, gathering lines and electrical distribution lines may occupy common disturbance corridors where possible. Where available, roadways may be used as the staging area and working space for installation of gathering lines. All disturbances located in the same corridor may overlap each other to the maximum extent possible, while maintaining safe and sound construction and installation practices. Unless otherwise approved or requested in site specific documents, in no case will the maximum disturbance widths of the access road and utility corridors exceed the widths specified in Part D of this document.

Within individual APDs, please refer to Topo B, for existing roads.

B. New or Reconstructed Access Roads:

All new or reconstructed roads will be located, designed, and maintained to meet the standards of the BLM's Surface Operating Standards for Oil and Gas Exploration and Development, 4th Edition (Gold Book) (USDI and USDA, 2007). The BLM Manual Section 9113 (1985) will be considered in consultation with the BLM in the design, construction, improvement and maintenance of all new or reconstructed roads. If a new road would cross a water of the United States, KMG will adhere to all applicable US Army Corps of Engineers requirements in cooperation with the Utah Division of Water Rights.

New well pads or pad expansions may require construction of a new access road and/or decommissioning of an older road. Plans, routes, and distances for new roads and road improvements are provided in design packages, exhibits and maps for a project. Project-specific maps are submitted to depict the locations of existing, proposed, and/or decommissioned and include the locations for supporting structures, including, but not limited to, culverts, bridges, low water crossings, range infrastructure, and haul routes, per OSO 1. Designs for cuts and fills, including spoils source and storage areas, are provided with the road designs, as necessary.

Where safety objectives can be met KMG may use unimproved and/or two-track roads for lease operations and to lessen total disturbance. Road designs will be based on the road safety requirements, traffic characteristics, environmental conditions, and the vehicles the road is intended to carry. Generally, newly constructed unpaved lease roads will be crowned and ditched with the running surfaces of the roads approximately 12-18 feet wide and a total road corridor width not to exceed 45 feet, except where noted in the road design for a specific project. Maximum grade will generally not exceed 8%. Borrow ditches will be back sloped 3:1 or less. Construction BMPs will be employed to control onsite and offsite erosion.

Where topography would direct storm water runoff to an access road or well pad, drainage ditches or other common drainage control facilities may be constructed to divert surface water runoff. Drainage features, including culverts, may be constructed or installed prior to commencing other operations, including drilling for facilities placement. Riprap will be placed at the inlet and outlet at the culvert(s). Drainage features will meet the standards of the BLM's Surface Operating Standards for Oil and Gas Exploration and Development, 4th Edition (Gold Book) (USDI and USDA, 2007).

Prior to construction, new access road(s) will be staked according to the requirements of OSO 1. Construction activities will not be conducted using frozen or saturated materials or during periods when significant watershed damage (e.g. rutting, extensive sheet soil erosion, formation of rills/gullies, etc.) is likely to occur. Vegetative debris will not be placed in or under fill embankments.

New road maintenance will include, but is not limited to, blading, ditching, culvert installation and cleanout, gravel surfacing where excessive rutting or erosion may occur and dust control, as necessary to ensure safe operating conditions. All vehicular traffic, personnel movement and construction/restoration operations will be confined to the approved area and to existing roadways and/or access routes.

Snow removal will be conducted on an as-needed basis to accommodate safe travel. Snow removal will occur as necessary throughout the year, as will necessary drainage ditch construction. Removed snow may be stored on permitted well pads to reduce hauling distances and/or at the aerial extent of approved disturbance boundaries to facilitate snow removal for the remainder of the season.

If a county road crossing or encroachment permit is needed, it will be obtained prior to construction.

For individual APDs, refer to Topo B.

C. Location of Existing Wells:

For individual APDs, refer to Topo C

D. Location of Existing and/or Proposed Facilities:

The following will apply if the well is productive: Gathering (pipeline) infrastructure will be utilized to collect and transport gas and fluids from the wells which are owned and operated by Kerr McGee Oil and Gas Onshore LP (KMG). Should the well(s) prove productive, production facilities will be installed on the disturbed portion of each well pad.

A berm may be constructed completely around production components (typically excluding dehy's and/or separators) that contain fluids (i.e. production tanks, produced liquids tanks). The berms will be constructed to hold the capacity of the largest tank and have sufficient freeboard to accommodate a 25 year rainfall event. This includes pumping units. Aboveground structures constructed or installed onsite for 6 months or longer, will be painted a flat, non-reflective, earth-tone color chosen at the onsite in coordination with the BLM (typically Shadow Gray). A production facility layout is provided as part of a project- specific APD, ROW or NOS submission.

Gas Gathering

The gas gathering pipeline is made of steel line pipe, surface is bare pipe and buried is of coated with fusion bonded epoxy coating (or equivalent). The individual segments will be denoted in site-specific APDs.

Liquid Gathering

The individual segments will be denoted in site-specific APDs.

Pipeline Gathering Construction

Gas gathering pipeline(s,) gas lift, or liquids pipelines may be constructed to lie on the surface or be buried. The road and/or well pad may be utilized for construction activities and staging when the pipeline is adjacent to the road or well pad. The area of disturbance during construction from

the edge of road or well pad and for surface and buried pipelines including cross country will typically be 45' temporary disturbance. In addition, KMG requests a permanent 30'disturbance width that will be maintained for the portion adjacent to the road as well as cross country lines. The need for the 30' of permanent disturbance width is for maintenance and repairs.

Above-ground installation will generally not require clearing of vegetation or blading of the surface, except where safety considerations necessitate earthwork. If installation cannot occur on the exact location, pipe may be constructed parallel and adjacent to a road and lifted from the road to the pipeline route. In other cases where a pipeline route is not parallel and adjacent to a road (cross-country between sites), it will be welded/fused in place at a well pad, access road, or designated work area and pulled between connection locations with a suitable piece of equipment. Buried pipelines will generally be installed parallel and adjacent to existing and/or newly constructed roads and within the permitted disturbance corridor. Buried pipelines may vary from 2" (typically fuel gas lines) to 24" (typically transportation lines) in diameter, but 6" to 16 "is typical for a buried gas line. The diameter of liquids pipelines may vary from 2" to 12", but 6"is the typical diameter. Gas lift lines may vary from 2" to 12" diameter, but 6" diameter pipes are generally used for gas lift. If two or more pipelines are present (gas gathering, gas lift, and fluids), they will share a common trench where possible.

When installing a buried pipeline, typically topsoil will be removed, windrowed and placed on the non-working side of the route for later reclamation. Because working room is limited, the spoil may be spread out across the working side and construction will take place on the spoil. The working side of the corridor will be used for pipe stringing, bending, welding and equipment travel. Small areas on the working side displaying ruts or uneven ground will be groomed to facilitate the safe passage of equipment. After the pipelines are installed, spoil will be placed back into the trench, and the topsoil will be redistributed over the disturbed corridor prior to final reclamation. Typical depth of the trench will be 6', but depths may vary according to site-specific conditions (presence of bedrock, etc.). The proposed trench width for the pipeline would range from 18"-48".

The pipeline will be welded along the proposed route and lowered into place. Trenching equipment will cut through the soil or into the bedrock and create good backfill, eliminating the need to remove large rocks. The proposed buried pipeline will be visually and radio-graphically inspected and the entire pipeline will be pneumatically or hydrostatically tested before being placed into service. Routine vehicle traffic will be prevented from using pipeline routes as travel ways by posting signs at the route's intersection with an access road.

The liquid gathering lines will be made of polyethylene or a composite polyethylene/steel or polyethylene/fiberglass that is not subject to internal or external pipe corrosion. The content of the produced fluids to be transferred by the liquid gathering system will be approximately 92% produced water and 8% condensate. Trunk line valve connections for the water gathering system will be below ground but accessible from the surface in order to prevent freezing during winter time.

If pipelines or roads encounter a drainage that could be subject to flooding or surface water during extreme precipitation events, KMG will apply all applicable Army Corps mandates as

well as the BLM's Hydraulic Considerations for pipeline Crossings of Stream Channels (BLM Technical Note 423, April 2007). In addition, all stream and drainage crossings will be evaluated to determine the need for stream alteration permits from the State of Utah Division of Water Rights and if necessary, required permits will be secured. Similarly, where a road or pipeline crossing exists the pipe will be butt welded and buried to a depth between 24 and 48 inches or more. Dirt roads will be cut and restored to a condition equivalent to the existing condition. All Uintah County road encroachment and crossing permits, where applicable, will be obtained prior to crossing construction. In no case will pressure testing of pipelines result in discharge of liquids to the surface.

Pipeline signs will be installed along the route to indicate the pipeline proximity, ownership, and to provide emergency contact phone numbers. Above ground valves and lateral T's will be installed at various locations for production integrity and safety purposes.

Upon completion of the proposed buried pipeline, the entire area of disturbance will be reclaimed to the standards proposed in the Green River District Reclamation Guidelines. Please refer to section J for more details regarding final reclamation.

When no longer deemed necessary by the operator, KMG or its successor will consult with the BLM, Vernal Field Office before terminating of the use of the pipeline(s).

The Anadarko Completions Transportation System (ACTS) information:

For individual APDs, refer to Exhibit C for the proposed placement of the ACTS temporary lines.

KMG will use either a closed loop drilling system that will require one pit and one storage area to be constructed on the drilling pad or a traditional drilling operation with one pit. The storage area will be used to contain only the de-watered drill cuttings and will be lined and reclaimed according to traditional pit closure standards. The pit will be constructed to allow for completion operations. The completion pit is lined and will be used for the wells drilled on the pad or used as part of our ACTS system which is discussed in more detail below. Using the closed loop drilling system will allow KMG to decrease the amount of disturbance/footprint on location compared to a single large drilling/completion pit.

If KMG does not use a closed loop system, it will construct a drilling reserve pit to contain drill cuttings and for use in completion operations. Depending on the location of the pit, its relation to future drilling locations, the reserve/completion pit may be utilized for the completion of the wells on that pad and/or be used as part of our ACTS system. KMG will use ACTS to optimize the completion processes for multiple pads across the project area which may include up to a section of development. ACTS will facilitate management of completion fluids by utilizing existing reserve pits, or newly constructed completion pits, as well as temporary, surface-laid aluminum liquids transfer lines between pad locations. The pit will be refurbished as follows when a traditional drill pit is used, including mix and pile up drill cuttings with dry dirt, bury the original liner in the pit, walk bottom of pit with cat. KMG will reline the pit with a 30 mil liner and double felt padding. The refurbished or newly constructed pit will be the same size or

smaller as specified in the originally approved ROW/APD. The pit refurbish will be done in a normal procedure and there will be no modification to the pit. All four sides of the completions pit will be fenced in according to standard pit fencing procedures. Netting will be installed over all pits.

Any hydrocarbons collected will be treated and sold at approved sales facilities. A loading/ <u>unloading</u> rack <u>with drip containment</u> will also be installed where water trucks would unload and load to prevent damage caused from pulling hoses in and out of the pit.

ACTS will require temporarily laying multiple 6 inch aluminum water transfer lines on the surface between either existing or refurbished reserve pits. The temporary aluminum transfer lines will be utilized to transport completion fluid being injected and/or recovered during the completion process and will be laid adjacent to existing access roads or pipeline corridors. Upon conclusion of the completion operation, the liquids transfer lines will be flushed with fresh water and purged with compressed air. The contents of the transfer lines will be flushed into a water truck for delivery to another ACTS location or a reserve pit.

The volume of frac fluid transported through a water transfer line will vary, but volume is projected to be approximately 1.75 bbls per 50-foot joint. Although the maximum working pressure is 125 psig, the liquids transfer lines will be operated at a pressure of approximately 30 to 40 psig. KMG will keep the netted pit open for one year from first production of the first produced well on the pad. During this time the surrounding well location completion fluids may be recycled in this pit and utilized for other completion jobs in the area. After one year KMG will backfill the pit and reclaim. If the pit is not needed for an entire year it will be backfilled and reclaimed earlier. KMG understands that due to the temporary nature of this system, BLM considers this a casual use situation; therefore, no permanent ROW or temporary use plan will need to be issued by the BLM.

E. Location and Types of Water Supply:

Water for drilling and completion operations will be obtained from the following sources: JD Field Services:

Green River: 1087' FSL & 1020' FEL, Sec. 15 – T2N – R22E

RN Industries:

High Pressure: 705' FNL & 675' FWL, Sec. 1 – T6S – R22E

1057' FNL & 390' FWL, Sec. 1 – T6S – R22E 1239' FNL & 52' FEL, Sec. 6 – T6S – R23E

White River: 501' FNL & 1676' FEL, Sec. 9 – T8S – R20E

471' FNL & 1676' FEL, Sec. 9 – T8S – R20E 900' FNL & 550' FEL, Sec. 35 – T9S – R22E 200' FNL & 950' FEL, Sec. 2 – T10S – R22E 275' FSL & 2275' FEL, Sec. 2 – T10S – R22E 122' FSL & 1350' FEL, Sec. 11 – T10S – R22E 1670' FSL & 500' FEL, Sec. 12 – T10S – R22E

959' FNL & 705' FEL, Sec. 13 – T10S – R22E

600' FSL & 900' FEL, Sec. 13 – T10S – R22E

Water Plant: 481' FNL & 2176' FEL, Sec. 9 – T8S – R20E

471' FNL & 2176' FEL, Sec. 9 – T8S – R20E

Frog Pond: 4820' FNL & 1200' FWL, Sec. 33 – T8S – R20E

4850' FNL & 700' FWL, Sec. 33 – T8S – R20E

Blue Tanks: 200' FNL & 405' FEL, Sec. 32 – T4S – R3E

Buggsy's Water Source:

Green River: N 2090' & W 30' from E1/4 corner of Sec. 33 – T8S – R20E

Underground Water Well: N 1850' & W 425' from E1/4 corner of Sec. 33 – T8S – R20E

Water will be hauled to location over the roads marked in the individual APD's Maps A and B.

F. Construction Materials:

Construction operations will typically be completed with native materials found on location. Construction materials imported to the site (mineral material aggregate, soils or materials suitable for fill/surfacing) will be obtained from a nearby permitted source (described in site-specific documents). No construction materials will be removed from Federal lands without notifying the BLM. A proposed source location other than an on-location construction site will be designated either via a map or narrative within the project specific materials provided to the BLM.

G. Methods for Handling Waste:

All wastes subject to regulation will be handled in compliance with applicable laws to minimize the potential for leaks or spills to the environment. KMG maintains a Spill Control and Countermeasure Plan for each applicable location, which includes notification requirements, to the BLM and other appropriate agencies, for all reportable spills of oil, produced liquids, and hazardous materials.

Any accidental release, such as a leak or spill in excess of the reportable quantity, as established by 40 CFR Part 117.3, will be reported as per the requirements of Comprehensive Environmental Response, Compensation, and Liability Act, Section 102 B. If a release involves petroleum hydrocarbons or produced liquids, KMG will comply with the notification requirements of NTL-3A.

Drill cuttings and/or drilling fluids may be contained in a reserve/completion pit whether a closed loop system is or isn't utilized and cuttings may be buried in the pit(s) upon closure. Unless specifically approved by the BLM, no oil or other oil-based drilling additives,

chromium/metals-based, or saline muds will be used during drilling. Only fresh water (as specified above), biodegradable polymer soap, bentonite clay, and/or non-toxic additives will be used in the mud system.

If utilizing a closed loop system, drill cuttings and/or drilling fluids may be stored in above ground containers while on the location. All used drilling fluids may be hauled to Anadarko Petroleum Corporation's Mud Plant where it may be recycled for use at future well locations, hauled to a permitted disposal facility, or solidified for incorporation into the pad during interim reclamation practices. Drill cuttings from a closed loop system may be either hauled to an approved Utah Department of Oil, Gas and Mining Commercial Landfarm Disposal Facility or incorporated into the pad location during interim reclamation.

Pits will be constructed to eliminate the accumulation of surface precipitation runoff into the pit (via appropriate placement of subsoil storage areas and/or construction of berms, ditches, etc). Should unexpected liquid petroleum hydrocarbons (crude oil or condensate) be encountered during drilling, completions or well testing, liquid petroleum hydrocarbons will either be contained in test tanks on the well site or evacuated by vacuum trucks and transported to an approved disposal/sales facility. Netting will be placed over pits before any liquids are discharged into pit. Should hydrocarbons be released into a reserve/completion pit, they will be removed as soon as practical and before the netting is removed from the pit. Similarly, hydrocarbon removal will take place prior to the closure of the pit, unless authorization is provided for disposal via alternate pit closure methods (e.g. solidification).

The reserve and/or completion pit will be lined with a synthetic material 30 mil or thicker liner. The bottom and side walls of the pit will be void of any sharp rocks that could puncture the liner. The liner will be installed over smooth fill subgrade that is free of pockets, loose rocks, or other materials (i.e. sand, sifted dirt, bentonite, straw, etc.) that could damage the liner. After evaporation and when dry, the reserve pit liners will be cut off, ripped and/or folded back (as safety considerations allow) as near to the mud surface as possible and buried on location or hauled to a landfill prior to backfilling the pit with a minimum of five feet of soil material.

Where necessary and if conditions allow, produced liquids from newly completed wells may be temporarily disposed of into pits for a period not to exceed 90 days as per OSO 7. Subsequently, permanent approved produced water disposal methods will be employed in accordance with OSO 7 and/or as described in a Water Management Plan (WMP). Revisions to the water source or method of transportation will be subject to written approval from the BLM.

Any additional pits necessary for subsequent operations, such as temporary flare or workover pits, will be contained within the originally approved well pad and disturbance boundaries. Such temporary pits will be backfilled and reclaimed within 180 days of completion of work at a well location.

Pits containing drilling cuttings, mud, and/or completions fluids will be allowed to dry. Any free fluids remaining after one year from reaching total depth, date of completion, and/or determination of inactivity will be removed (as weather conditions allow) to an approved site and

the pit reclaimed. Installation and operation of any sprinklers, pumps, and equipment will ensure that water spray or mist does not drift.

No garbage or non-exempt substances as defined by Resource Conservation and Recovery Act (RCRA) subtitle C will be placed in the reserve pit. All refuse (trash and other solid waste including cans, paper, cable, etc.) generated during construction, drilling, completion, and well testing activities will be contained in an enclosed receptacle, removed from the drill locations promptly, and transported to an approved disposal facility. Immediately after removal of the drilling rig, all debris and other waste materials not contained within trash receptacles will be collected and removed from the well location.

For the protection of livestock and wildlife, all open pits (excluding flare pits) will be fenced or netted to prevent wildlife or livestock entry.

Maximum distance between fence posts shall be no greater than 16 feet. Siphons, catchments, and absorbent pads will be installed to keep hydrocarbons produced by the drilling rig or other equipment on location from entering the reserve pit. Hydrocarbons, contaminated pads, and/or soils will be disposed of in accordance with state and federal requirements.

Portable, self-contained chemical toilets and/or sewage processing facilities will be provided for human waste disposal. Upon completion of operations, or as required, the toilet holding tanks will be pumped and the contents disposed of in an approved sewage disposal facility. All applicable regulations pertaining to disposal of human and solid waste will be observed.

Materials Management

Hazardous materials above reportable quantities will not be produced by drilling or completing proposed wells or constructing the pipelines/facilities. The term "hazardous materials" as used here means: (1) any substance, pollutant, or containment listed as hazardous under the CERCLA of 1980, as amended 42 U.S.C. 9601 et seq., and the regulations issued under CERCLA; and (2) any hazardous waste as defined in RCRA of 1976, as amended. In addition, no extremely hazardous substance, as defined in 40 CFR 355, in threshold planning quantities, would be used, produced, stored, transported, or disposed of while producing any well.

Hazardous materials may be contained in some grease or lubricants, solvents, acids, paint, and herbicides, among others as defined above. KMG maintains a file, per 29 CFR 1910.1200 (g) containing current Material Safety Data Sheets (MSDS) for all chemicals, compounds, and/or substances that are used during the course of construction, drilling, completion, and production operations for this project. The transport, use, storage and handling of hazardous materials will follow procedures specified by federal and state regulations. Transportation of hazardous materials to the well location is regulated by the Department of Transportation (DOT) under 49 CFR, Parts 171-180. DOT regulations pertain to the packing, container handling, labeling, vehicle placarding, and other safety aspects.

Potentially hazardous materials used in the development or operation of wells will be kept in limited quantities on well sites and at the production facilities for short periods of time.

Chemicals meeting the criteria for being an acutely hazardous material/substance or meet the quantities criteria per BLM Instruction Memorandum No. 93-344 will not be used. Chemicals subject to reporting under Title III of the Superfund Amendments and Reauthorization Act (SARA) in quantities of 10,000 pounds or more may be produced and/or stored at production facilities (crude oil/condensate, produced water). They may also be kept in limited quantities on drilling sites (barite, diesel fuel, cement, cottonseed hulls etc.) for short periods of time during drilling or completion activities.

Any produced water separated from recoverable condensate during well operations will be contained in a water tank and will then be transported by pipeline and/or truck to one of the preapproved disposal sites:

RNI in Sec. 5 T9S R22E NBU #159 in Sec. 35 T9S R21E Ace Oilfield in Sec. 2 T6S R20E MC&MC in Sec. 12 T6S R19E Pipeline Facility in Sec. 36 T9S R20E Goat Posture Eveneration Pend in SW//

Goat Pasture Evaporation Pond in SW/4 Sec. 16 T10S R22E

Bonanza Evaporation Pond in Sec. 2 T10S R23E

Or to one of the following KMG active Salt Water Disposal (SWD) wells:

NBU 159 SWD in Sec. 35 T9S R21E CIGE 112D SWD in Sec. 19 T9S R21E CIGE 114 SWD in Sec. 34 T9S R21E NBU 921-34K SWD in Sec. 34 T9S R21E NBU 921-33F SWD in Sec. 34 T9S R21E

H. Ancillary Facilities:

If additional ancillary facilities are planned they will be depicted on site specific APDs.

I. Well Site Layout:

The location, orientation and aerial extent of each drill pad, reserve/completion/flare pit (for closed loop or non-closed loop operations), access road ingress/egress points, drilling rig, dikes/ditches, existing wells/infrastructure, proposed cuts and fills, and topsoil and spoil material stockpile locations are depicted on the exhibits for each project, where applicable.

Site-specific conditions may require slight deviation in actual equipment depending on whether a closed loop system is used. Surface distance may be less if using closed loop. But in either case, the area of disturbance will not exceed the maximum disturbance outlined in the attached exhibits of the APDs.

Each well will utilize either a centralized tank battery, centralized fluids management system, or have tanks installed on its pad. Production/Produced Liquid tanks will be constructed,

maintained, and operated to prevent unauthorized surface or subsurface discharges of liquids and to prevent livestock or wildlife entry. The tanks will be kept reasonably free from surface accumulations of liquid hydrocarbons. The tanks are not to be used for disposal of liquids from additional sources without prior approval of BLM.

J. Plans for Surface Reclamation:

The surface reclamation will be undertaken in two phases: interim and final. Interim reclamation is conducted following well completion and extends through the period of production. Interim reclamation is for the area of the well pad that is not required for production activities. Final reclamation is conducted following well plugging/conversion and/or facility abandonment processes.

Reclamation activities in both phases may include but is not limited to the re-contouring or re-configuration of topographic surfaces, restoration of drainage systems, segregation of spoils material, minimizing surface disturbance, re-evaluating backfill requirements, pit closure, topsoil redistribution, soil treatments, seeding and weed control.

Interim Reclamation

Interim reclamation may include pit evaporation, fluid removal, pit solidification, re-contouring, incorporation of cuttings, ripping, spreading top soil, seeding, and/or weed control. Interim reclamation will be performed in accordance with OSO 1, or written notification will be provided to the BLM for approval. Where feasible, drilling locations, reserve pits, or access routes not utilized for production operations will be re-contoured to a natural appearance.

Interim re-contouring involves bringing all construction material from cuts and fills back onto the well pad and site and reestablishing the natural contours where desirable and practical. Fill and stockpiled spoils no longer necessary to the operation will be spread on the cut slopes and covered with stockpiled topsoil. Stockpiled drill cuttings may also be incorporated into the spoils, recontoured, and covered with stockpiled topsoil. All stockpiled top soils will be used for interim reclamation where practical to maintain soil viability. Where possible, the land surface will be left "rough" after re-contouring to ensure that the maximum surface area will be available to support the reestablishment of vegetative cover.

A reserve pit, upon being allowed to dry, will be backfilled and compacted with cover materials that are void of any topsoil, vegetation, large stones, rocks or foreign objects. Soils that are moisture laden, saturated, or partially/completely frozen will not be used for backfill or cover. The pit area will be mounded to allow for settling and to promote positive surface drainage away from the pit. Disposal of pit fluids and linings is discussed in Section G.

Final Reclamation

Final reclamation will be performed for unproductive wells and after the end of the life of a productive well. As soon as practical after the conclusion of drilling and testing operations, unproductive drill holes will be plugged and abandoned (P&A). Site and road reclamation will commence following plugging. In no case will reclamation at non-producing locations be initiated later than six (6) months from the date a well is plugged. A joint inspection of the disturbed area to be reclaimed may be requested by KMG. The primary purpose of this inspection will be to review the existing conditions, or agree upon a revised final reclamation and abandonment plan. The BLM will be notified prior to commencement of reclamation operations. A Notice of Intent to Abandon will be filed for final recommendations regarding surface reclamation.

After plugging, all wellhead equipment that is no longer needed will be removed, and the well site will be reclaimed. Final contouring will blend with and follow as close as practical the natural terrain and contours of the original site and surrounding areas. After re-contouring the site and prior to replacing topsoil, final grading and site preparation will be conducted over the entire surface of the well site and access road. The area will be ripped to a depth no greater than 6 inches on 18 to 24-inch centers and the surface soil material will be uniformly pitted with longitudinal depressions perpendicular to the natural flow of water where practical. Following site preparation, topsoil will be spread on the location and prepared for seeding.

Reclamation of roads will be performed at the discretion of the BLM. All unnecessary surface equipment and structures (e.g. cattle guards) and water control structures (e.g. culverts, drainage pipes) not needed to facilitate successful reclamation will be removed during final reclamation. Roads that will be reclaimed will be ripped to a depth of 6 to 24 inches where practical, recontoured to approximate the original contour of the ground and seeded in accordance with the seeding specifications of the BLM.

Upon successfully completing reclamation of a P&A location, a Final Abandonment Notice will be submitted to the BLM.

Measures Common to Interim and Final Reclamation

Soil tillage will be conducted using a disk in areas needing additional seedbed preparation following site preparation. This will provide primary soil tillage to a depth no greater than 6 inches. Prior to reseeding, compacted areas will be scarified by ripping or chiseling to loosen compacted soils, promote water infiltration, and improve soil aeration and root penetration.

Seeding will occur during optimal soil conditions and will typically be accomplished through the use of a no-till rangeland style seed drill with a "picker box." Additionally an imprinter seeder may be used. An imprinter seeder creates divots to roughen the surface and collect moisture to aid in seed germination. Seed mixes appropriate to the native plant community as determined and specified for each project location based on the site specific soils will be used for revegetation. The seed mixes will be selected from a list provided by or approved by the BLM, or a specific seed mix will be proposed by KMG to the BLM and used after its approval. The selected specific seed mix for each well location and road segment will be utilized while performing interim and final reclamation for each project. All seed will be certified and tags will be

maintained by KMG. Every effort will be made to obtain "cheat grass free seed" and noxious weed free seed.

Seed Mix to be used for Well Site, Access Road, and Pipeline (as applicable):

Bonanza Area Mix	Pure Live Seed lbs/acre
Crested Wheat (Hycrest)	1.5
Bottlebrush Squirreltail	1.3
Western Wheatgrass (Arriba)	1
Thick Spike Wheatgrass	1.5
Indian Ricegrass	1
Fourwing Saltbush	2
Shadscale	2
Forage Kochia	0.25
Rocky Mountain Bee Plant	0.5
Total	10.75

Natural Buttes Area Mix Option 1:	Pure Live Seed lbs/acre	
Indian Ricegrass (Nezpar)	3	
Thick Spike Wheatgrass	2	
Sandberg bluegrass	0.5	
Bottlebrush squirreltail	1	
Crested wheatgrass (Hycrest)	1	
Winterfat	0.25	
Shadscale	1.5	
Four-wing saltbush	0.75	
Forage Kochia	0.25	
Total	10.25	

Natural Buttes Area Mix Option 2: Pure Live Seed lbs/acre

Galleta Grass	0.5
Great Basin Wildrye	0.5
Thickspike Wheatgrass	2.5
Indian Ricegrass (Nezpar)	1
Crested Wheatgrass	1
Siberian Wheatgrass	1
Bottlebrush Squirreltail	1
Munro Globemallow	0.1
Palmer Penstemon	0.1
Rocky Mtn beeplant	0.5
Western yarrow	0.1
Shadscale	0.5
Forage Kochia	0.5
T-4-1	0.2

Total 9.3

Natural Buttes Area Mix Option 3:	Pure Live Seed lbs/acro	
Galleta Grass	2	
Sandberg bluegrass	0.5	
Shadscale	0.5	
Bluebunch (secar)	2	
Indian Ricegrass (Nezpar)	2	
Western Wheatgrass (Arriba)	2	
Palmer penstemon	0.25	
Munro Globemallow	0.15	
Black Sage	0.25	
Winterfat	0.25	
Forage Kochia	0.25	
Total	10.15	

Additional soil amendments and/or stabilization may be required on sites with poor soils and/or excessive erosion potential. Where severe erosion can become a problem and/or the use of machinery is not practical, seed will be hand broadcast and raked with twice the specified amount of seed. Slopes will be stabilized using materials specifically designed to prevent erosion on steep slopes and hold seed in place so vegetation can become permanently established. These materials will include, but are not limited to: erosion control blankets, hydro-mulch, and/or bonded fiber matrix at a rate to achieve a minimum of 80 percent soil coverage. Soil amendments such as "Sustain" (an organic fertilizer that will be applied at the rate 1,800 – 2,100 lbs/acre with seed) may also be dry broadcast or applied with hydro-seeding equipment.

Weed Control

All weed management will be done in accordance with the Vernal BLM Surface Disturbance Weed Policy. Noxious weeds will be controlled, as applicable, on project areas. Monitoring and management of noxious and/or invasive weeds of concern will be completed annually until the project is deemed successfully reclaimed by the surface management agency and/or owner according to the Anadarko Integrated Weed Management Plan. Noxious weed infestations will be mapped using a GPS unit and submitted to the BLM with information required in the Vernal BLM Surface Disturbance Weed Policy. If herbicide is to be applied it will be done according to an approved Pesticide Use Proposal (PUP), inclusive of applicable locations. All pesticide applications will be recorded using a Pesticide Application Record (PAR) and will be submitted along with a Pesticide Use Report (PUR) annually prior to Dec. 31.

Monitoring

Monitoring of reclaimed project areas will be completed annually during the growing season and actions to ensure reclamation success will be taken as needed. During the first two growing seasons an ocular methodology will be used to determine the success of the reclamation activities. During the 3rd growing season a 100 point line intercept (quantitative) methodology will be used to obtain basal cover. The goal is to have the reclaimed area reach 30% basal cover when compared to the reference site. If after three growing seasons the area has not reached 30% basal cover, additional reclamation activities may be necessary. Monitoring will continue until the reclaimed area reaches 75% basal cover of desirable vegetation when compared to the reference site. (Green River District Reclamation Guidelines).

All monitoring reports will be submitted electronically to the Vernal BLM in the form of a geodatabase no later than March 1st of the calendar year following the data collection.

K. Surface/Mineral Ownership:

Depicted on site specific APDs.

L. Other Information:

Cultural and Paleontological Resources

All personnel are strictly prohibited from collecting artifacts, any paleontological specimens or fossils, and from disturbing any significant cultural resources in the area. If artifacts, fossils, or any culturally sensitive materials are exposed or identified in the area of construction, all construction operations that would affect the newly discovered resource will cease, and KMG will provide immediate notification to the BLM or appropriate SMA.

Resource Reports

Appropriate archaeological and paleontological reconnaissance surveys and biological field surveys will be completed and provide to the BLM for individual APDs.

Proposed Action Annual Emissions Tables:

Appendix A through G contains the emission table per pad based on well count.

M. Lessee's or Operators' Representative & Certification:

Depicted on site specific APDs.

Appendix A:

Proposed Action Annual Emissions Tables: 4 Well Pad

Table 1: Proposed Action Annual Emissions (tons/year) ¹			
Pollutant	Development	Production	Total
NOx	3.8	1.2	5
CO	2.2	1.08	3.28
VOC	0.1	6.8	6.9
SO ₂	0.005	0.01	0.02
PM ₁₀	1.7	0.11	1.81
PM _{2.5}	0.4	0.05	0.45
Benzene	2.20E-03	0.12	0.12
Toluene	1.60E-03	0.2	0.2
Ethylbenzene	3.40E-04	0.01	0.01
Xylene	1.10E-03	0.09	0.09
n-Hexane	1.70E-04	0.51	0.51
Formaldehyde	1.30E-02	1.30E-04	1.31E-02

¹ Emissions include 1 producing well and associated operations traffic during the year in which the project is developed

Table 2: Proposed Action versus 2012 WRAP Phase III Emissions Inventory Comparison

Species	Proposed Action Production Emissions (ton/yr)	WRAP Phase III 2012 Uintah Basin Emission Inventory ^a (ton/yr)	Percentage of Proposed Action to WRAP Phase III
NOx	5	16,547	0.03%
VOC	6.9	127,495	0.01%

^a http://www.wrapair.org/forums/ogwg/PhaseIII_Inventory.html

Appendix B:

Proposed Action Annual Emissions Tables: 5 Well Pad

Table 1: Proposed Action Annual Emissions (tons/year) ¹			
Pollutant	Development	Production	Total
NOx	3.8	1.5	5.3
CO	2.2	1.08	3.28
VOC	0.1	8.5	8.6
SO_2	0.005	0.01	0.02
PM_{10}	1.7	0.11	1.81
PM _{2.5}	0.4	0.05	0.45
Benzene	2.20E-03	0.12	0.12
Toluene	1.60E-03	0.2	0.2
Ethylbenzene	3.40E-04	0.01	0.01
Xylene	1.10E-03	0.09	0.09
n-Hexane	1.70E-04	0.51	0.51
Formaldehyde	1.30E-02	1.30E-04	1.31E-02

¹ Emissions include 1 producing well and associated operations traffic during the year in which the project is developed

Table 2: Proposed Action versus 2012 WRAP Phase III Emissions Inventory Comparison

Species	Proposed Action Production Emissions (ton/yr)	WRAP Phase III 2012 Uintah Basin Emission Inventory ^a (ton/yr)	Percentage of Proposed Action to WRAP Phase III
NOx	5.3	16,547	0.03%
VOC	8.6	127,495	0.01%

^a http://www.wrapair.org/forums/ogwg/PhaseIII_Inventory.html

Appendix C:

Proposed Action Annual Emissions Tables: 6 Well Pad

Table 1: Proposed Action Annual Emissions (tons/year) ¹			
Pollutant	Development	Production	Total
NOx	3.8	1.8	5.6
CO	2.2	1.08	3.28
VOC	0.1	10.2	10.3
SO ₂	0.005	0.01	0.02
PM ₁₀	1.7	0.11	1.81
PM _{2.5}	0.4	0.05	0.45
Benzene	2.20E-03	0.12	0.12
Toluene	1.60E-03	0.2	0.2
Ethylbenzene	3.40E-04	0.01	0.01
Xylene	1.10E-03	0.09	0.09
n-Hexane	1.70E-04	0.51	0.51
Formaldehyde	1.30E-02	1.30E-04	1.31E-02

 $^{^{1}}$ Emissions include 1 producing well and associated operations traffic during the year in which the project is developed

Table 2: Proposed Action versus 2012 WRAP Phase III Emissions Inventory Comparison			
Species Proposed Action Production Emissions (ton/yr) WRAP Phase III 2012 Uintah Basin Emission Inventory ^a (ton/yr) WRAP Phase III			
NOx	5.6	16,547	0.03%
VOC	10.3	127,495	0.01%

^a http://www.wrapair.org/forums/ogwg/PhaseIII_Inventory.html

Uintah Basin
Data

Appendix D:

Proposed Action Annual Emissions Tables: 7 Well Pad

Table 1: Proposed Action Annual Emissions (tons/year) ¹			
Pollutant	Development	Production	Total
NOx	3.8	2.1	5.9
CO	2.2	1.08	3.28
VOC	0.1	11.9	12
SO ₂	0.005	0.01	0.02
PM_{10}	1.7	0.11	1.81
PM _{2.5}	0.4	0.05	0.45
Benzene	2.20E-03	0.12	0.12
Toluene	1.60E-03	0.2	0.2
Ethylbenzene	3.40E-04	0.01	0.01
Xylene	1.10E-03	0.09	0.09
n-Hexane	1.70E-04	0.51	0.51
Formaldehyde	1.30E-02	1.30E-04	1.31E-02

¹ Emissions include 1 producing well and associated operations traffic during the year in which the project is developed

Table 2: Proposed Action versus 2012 WRAP Phase III Emissions Inventory Comparison				
Species	Proposed Action Production Emissions (ton/yr) WRAP Phase III 2012 Uintah Basin Emission Inventory ^a (ton/yr) WRAP Proposed Action to WRAP Phase III			
NOx	5.9	16,547	0.03%	
VOC	12	127,495	0.01%	

 $[^]a\ http://www.wrapair.org/forums/ogwg/PhaseIII_Inventory.html$

Uintah Basin Data

Appendix E:

Proposed Action Annual Emissions Tables: 8 Well Pad

Table 1: Proposed Action Annual Emissions (tons/year)¹

Pollutant	Development	Production	Total
NOx	3.8	2.4	6.2
СО	2.2	1.08	3.28
VOC	0.1	13.6	13.7
SO ₂	0.005	0.01	0.02
PM ₁₀	1.7	0.11	1.81
PM _{2.5}	0.4	0.05	0.45
Benzene	2.20E-03	0.12	0.12
Toluene	1.60E-03	0.2	0.2
Ethylbenzene	3.40E-04	0.01	0.01
Xylene	1.10E-03	0.09	0.09
n-Hexane	1.70E-04	0.51	0.51
Formaldehyde	1.30E-02	1.30E-04	1.31E-02

¹ Emissions include 1 producing well and associated operations traffic during the year in which the project is developed

Table 2: Proposed Action versus 2012 WRAP Phase III Emissions Inventory Comparison			
Species	Proposed Action Production Emissions (ton/yr)	WRAP Phase III 2012 Uintah Basin Emission Inventory ^a (ton/yr)	Percentage of Proposed Action to WRAP Phase III
NOx	6.2	16,547	0.03%
VOC	13.7	127,495	0.01%

^a http://www.wrapair.org/forums/ogwg/PhaseIII_Inventory.html

Appendix F:

Proposed Action Annual Emissions Tables: 10 Well Pad

Table 1: Proposed Action Annual Emissions (tons/year) ¹			
Pollutant	Development	Production	Total
NOx	3.8	3	6.8
CO	2.2	1.08	3.28
VOC	0.1	17	17.1
SO_2	0.005	0.01	0.02

PM_{10}	1.7	0.11	1.81
PM _{2.5}	0.4	0.05	0.45
Benzene	2.20E-03	0.12	0.12
Toluene	1.60E-03	0.2	0.2
Ethylbenzene	3.40E-04	0.01	0.01
Xylene	1.10E-03	0.09	0.09
n-Hexane	1.70E-04	0.51	0.51
Formaldehyde	1.30E-02	1.30E-04	1.31E-02

¹ Emissions include 1 producing well and associated operations traffic during the year in which the project is developed

Table 2: Proposed Action versus 2012 WRAP Phase III Emissions Inventory Comparison			
Species	rcies Proposed Action Production Emissions (ton/yr)		Percentage of Proposed Action to WRAP Phase III
NOx	6.8	16,547	0.03%
VOC	17.1	127,495	0.01%

 $[^]a\ http://www.wrapair.org/forums/ogwg/PhaseIII_Inventory.html$

Appendix G:

Proposed Action Annual Emissions Tables: 12 Well Pad

Table 1: Proposed Action Annual Emissions (tons/year) ¹			
Pollutant	Development	Production	Total
NOx	3.8	3.6	7.4
CO	2.2	1.08	3.28
VOC	0.1	20.4	20.5
SO ₂	0.005	0.01	0.02
PM_{10}	1.7	0.11	1.81
PM _{2.5}	0.4	0.05	0.45

Benzene	2.20E-03	0.12	0.12
Toluene	1.60E-03	0.2	0.2
Ethylbenzene	3.40E-04	0.01	0.01
Xylene	1.10E-03	0.09	0.09
n-Hexane	1.70E-04	0.51	0.51
Formaldehyde	1.30E-02	1.30E-04	1.31E-02

¹ Emissions include 1 producing well and associated operations traffic during the year in which the project is developed

Table 2: Propo	Table 2: Proposed Action versus 2012 WRAP Phase III Emissions Inventory Comparison			
Species	Proposed Action Production Emissions (ton/yr)	WRAP Phase III 2012 Uintah Basin Emission Inventory ^a (ton/yr)	Percentage of Proposed Action to WRAP Phase III	
NOx	7.4	16,547	0.03%	
VOC	20.5	127,495	0.01%	

^a http://www.wrapair.org/forums/ogwg/PhaseIII_Inventory.html

Appendix G:


Proposed Action Annual Emissions Tables: 15 Well Pad

Table 1: Proposed Action Annual Emissions (tons/year) ¹			
Pollutant	Development	Production	Total
NOx	3.8	4.5	8.3
CO	2.2	1.08	3.28
VOC	0.1	25.5	25.6
SO ₂	0.005	0.01	0.02
PM ₁₀	1.7	0.11	1.81
PM _{2.5}	0.4	0.05	0.45
Benzene	2.20E-03	0.12	0.12
Toluene	1.60E-03	0.2	0.2
Ethylbenzene	3.40E-04	0.01	0.01
Xylene	1.10E-03	0.09	0.09
n-Hexane	1.70E-04	0.51	0.51
Formaldehyde	1.30E-02	1.30E-04	1.31E-02

¹ Emissions include 1 producing well and associated operations traffic during the year in which the project is developed

Table 2: Proposed Action versus 2012 WRAP Phase III Emissions Inventory Comparison			
Species	Proposed Action Production Emissions (ton/yr)	WRAP Phase III 2012 Uintah Basin Emission Inventory ^a (ton/yr)	Percentage of Proposed Action to WRAP Phase III
NOx	8.3	16,547	0.03%
VOC	25.6	127,495	0.01%

^a http://www.wrapair.org/forums/ogwg/PhaseIII_Inventory.html



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office 440 West 200 South, Suite 500 Salt Lake City, UT 84101

IN REPLY REFER TO: 3160 (UT - 922)

March 9, 2015

Memorandum

To: Assistant Field Office Manager Minerals,

Vernal Field Office

Michael Coulthard, Petroleum Engineer From:

Subject: 2015 Plan of Development Natural Buttes Unit

Uintah County, Utah.

Pursuant to email between Diana Mason, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management, the following wells are planned for calendar year 2015 within the Natural Buttes Unit, Uintah County, Utah.

API # WELL NAME LOCATION

(Proposed PZ WASATCH-MESA VERDE)

PAD NBU 1022-9J

43-047-55266 NBU 1022-9J1CS Sec 09 T10S R22E 1913 FSL 1793 FEL BHL Sec 09 T10S R22E 2273 FSL 1814 FEL

43-047-55267 NBU 1022-9J1BS Sec 09 T10S R22E 1908 FSL 1802 FEL BHL Sec 09 T10S R22E 2576 FSL 1794 FEL

This office has no objection to permitting the wells at this time.

Michael Coulthard

Digitally signed by Michael Coulthard

DN: cn=Michael Coulthard, o=Bureau of Land Management, ou=Division of Minerals, email=mcoultha@blm.gov, c=US

Date: 2015.03.09 09:23:57 -0600'


bcc: File - Natural Buttes Unit

Division of Oil Gas and Mining

Central Files Agr. Sec. Chron Fluid Chron

MCoulthard:mc:3-9-15

RECEIVED: March 10, 2015



API Well Number: 4304 755 5 60 COTAGO UTM (feet), NAD27, Zone 12N

Scientific Drilling

Site: NBU 1022-9J PAD Well: NBU 1022-9J1CS

Wellbore: OH


Design: PLAN #1 PRELIMINARY






Azimuths to True North Magnetic North: 10.67°

> Magnetic Field Strength: 51834.3snT Dip Angle: 65.73° Date: 3/2/2015 Model: BGGM2013





API Well Number: 4304 755 5 60 COTAGO UTM (feet), NAD27, Zone 12N

Scientific Drilling

Site: NBU 1022-9J PAD Well: NBU 1022-9J1BS

Wellbore: OH

Design: PLAN #1 PRELIMINARY




T M

Azimuths to True North Magnetic North: 10.70°

> Magnetic Field Strength: 51818.4snT Dip Angle: 65.74° Date: 3/2/2015 Model: BGGM2014





WORKSHEET APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 3/4/2015 API NO. ASSIGNED: 43047552660000

WELL NAME: NBU 1022-9J1CS

OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P. (N2995) PHONE NUMBER: 720 929-6828

CONTACT: Joel Malefyt

PROPOSED LOCATION: NWSE 09 100S 220E **Permit Tech Review:**

> **SURFACE: 1913 FSL 1793 FEL Engineering Review:**

> **BOTTOM: 2273 FSL 1814 FEL Geology Review:**

COUNTY: UINTAH

LATITUDE: 39.96136 LONGITUDE: -109.44176 **UTM SURF EASTINGS: 633088.00** NORTHINGS: 4424631.00

FIELD NAME: NATURAL BUTTES LEASE TYPE: 1 - Federal

LEASE NUMBER: UTU 01196-D PROPOSED PRODUCING FORMATION(S): WASATCH-MESA VERDE

SURFACE OWNER: 1 - Federal **COALBED METHANE: NO**

RECEIVED AND/OR REVIEWED: LOCATION AND SITING:

✓ PLAT R649-2-3.

Unit: NATURAL BUTTES Bond: FEDERAL - WYB000291

Potash R649-3-2. General

Oil Shale 190-5

Oil Shale 190-3 R649-3-3. Exception

Oil Shale 190-13 **Drilling Unit**

Board Cause No: Cause 173-14 Water Permit: 43-8496

Effective Date: 12/2/1999 **RDCC Review:**

Siting: Suspends General Siting Fee Surface Agreement

✓ Intent to Commingle R649-3-11. Directional Drill

Commingling Approved

Comments: Presite Completed

Stipulations:

3 - Commingling - ddoucet 4 - Federal Approval - dmason 15 - Directional - dmason 17 - Oil Shale 190-5(b) - dmason



State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

Permit To Drill

Well Name: NBU 1022-9J1CS
API Well Number: 43047552660000
Lease Number: UTU 01196-D
Surface Owner: FEDERAL
Approval Date: 3/12/2015

Issued to:

KERR-MCGEE OIL & GAS ONSHORE, L.P., P.O. Box 173779, Denver, CO 80217

Authority:

Pursuant to Utah Code Ann. 40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of Cause 173-14. The expected producing formation or pool is the WASATCH-MESA VERDE Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

Duration:

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

Commingle:

In accordance with Board Cause No. 173-14, commingling of the production from the Wasatch formation and the Mesaverde formation in this well is allowed.

General:

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

Conditions of Approval:

State approval of this well does not supercede the required federal approval, which must be obtained prior to drilling.

In accordance with Utah Admin. R.649-3-11, Directional Drilling, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.

In accordance with the Order in Cause No. 190-5(b) dated October 28, 1982, the operator shall comply with the requirements of Rules R649-3-31 and R649-3-27 pertaining to Designated Oil Shale Areas. Additionally, the operators shall ensure that the surface and or production casing is properly cemented over the entire oil

shale section as defined by Rule R649-3-31. The Operator shall report the actual depth the oil shale is encountered to the division.

Notification Requirements:

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

• Within 24 hours following the spudding of the well - contact Carol Daniels at 801-538-5284

(please leave a voicemail message if not available)

submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website

at http://oilgas.ogm.utah.gov

Reporting Requirements:

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) due within 5 days of spudding the well
- Monthly Status Report (Form 9) due by 5th day of the following calendar month
 - Requests to Change Plans (Form 9) due prior to implementation
 - Written Notice of Emergency Changes (Form 9) due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) due prior to implementation
 - Report of Water Encountered (Form 7) due within 30 days after completion
- Well Completion Report (Form 8) due within 30 days after completion or plugging

Approved By:

For John Rogers Associate Director, Oil & Gas Form 3160-3 (August 2007)

RECEIVED

UNITED STATES DEPARTMENT OF THE INTERMAR 0 5 2015 **BUREAU OF LAND MANAGEMENT**

FORM APPROVED OMB No. 1004-0136 Expires July 31, 2010

DIM

Lease Serial No. UTU01196D

APPLICATION FOR PERMIT	Deny protestal U	6. If Indian, Allottee or Tribe	e Name
1a. Type of Work:		7. If Unit or CA Agreement, UTU63047A	Name and No.
1b. Type of Well: ☐ Oil Well ☐ Gas Well ☐ Otl	ner Single Zone Multiple Zone	Lease Name and Well No. NBU 1022-9J1CS	
2. Name of Operator Contact: KERR-MCGEE OIL & GAS ONSHORMail: JOEL M	JOEL MALEFYT ALEFYT@ANADARKO.COM	9. API Well No. 430475521	ماه
3a. Address P.O. BOX 173779 DENVER, CO 80202-3779	3b. Phone No. (include area code) Ph: 720-929-6828 Fx: 720-929-7828	10. Field and Pool, or Explor NATURAL BUTTES	atory
4. Location of Well (Report location clearly and in accorded	nce with any State requirements.*)	11. Sec., T., R., M., or Blk. a	nd Survey or Area
At surface NWSE 1913FSL 1793FWL	39.961504 N Lat, 109.441752 W Lon	Sec 9 T10S R22E Me	er SLB
At proposed prod. zone NWSE 2273FSL 1814FEL	39.962493 N Lat, 109.441830 W Lon		
14. Distance in miles and direction from nearest town or post 48.7 MILES SOUTH OF VERNAL, UT	Office*	12. County or Parish UINTAH	13. State UT
15. Distance from proposed location to nearest property or lease line, ft. (Also to nearest drig. unit line, if any)	16. No. of Acres in Lease	17. Spacing Unit dedicated to	this well
830	320.00		
18. Distance from proposed location to nearest well, drilling,	19. Proposed Depth	20. BLM/BIA Bond No. on f	île
completed, applied for, on this lease, ft. 290	10035 MD 10009 TVD	WYB000291	· .
21. Elevations (Show whether DF, KB, RT, GL, etc. 5208 GL	22. Approximate date work will start 05/01/2015	23. Estimated duration 60-90 DAYS	
	24. Attachments		:
The following, completed in accordance with the requirements o	f Onshore Oil and Gas Order No. 1, shall be attached to t	his form:	
 Well plat certified by a registered surveyor. A Drilling Plan. A Surface Use Plan (if the location is on National Forest Syst SUPO shall be filed with the appropriate Forest Service Off 	Item 20 above). 5. Operator certification	ns unless covered by an existing ormation and/or plans as may be	· · · ·
25. Signature (Electronic Submission)	Name (Printed/Typed) JOEL MALEFYT Ph: 720-929-6828		Date 03/04/2015
Title REGULATORY ANALYST			
Approved by (Signature)	Name (Printed/Typed) Jerry Kend	zka	Date MAY 0 4 2015
Title Lands & Mineral Resources	VERNAL FIELD OFFICE		
Application approval does not warrant or certify the applicant ho operations thereon. Conditions of approval, if any, are attached.		ase which would entitle the appl TIONS OF APPROVA	
			

Title 18 U.S.C. Section 1001 and Title 43 U.S.C. Section 1212, make it a crime for any person knowingly and willfully to make to any department or agency of the United States any false, fictitious or fraudulent statements or representations as to any matter within its jurisdiction.

Additional Operator Remarks (see next page)

MAY 12 2015

Electronic Submission #293851 verified by the BLM Well Information System

For KERR-MCGEE OIL & GAS ONSHORE, sent to the Vernal

Committed to AFMSS for processing by STEVE HIRSCHI on 03/05/2015 (PIV. OF OIL GAS & MININC NOTICE OF APPROVAL



UNITED STATES DEPARTMENT OF THE INTERIOR **BUREAU OF LAND MANAGEMENT** VERNAL FIELD OFFICE 170 South 500 East

VERNAL, UT 84078

(435) 781-4400



CONDITIONS OF APPROVAL FOR APPLICATION FOR PERMIT TO DRILL

Company: Well No:

KERR MCGEE OIL & GAS ONSHORE

NBU 1022-9J1CS

API No: 43-047-55266 Location:

NWSE, Sec. 9, T10S, R22E

UTU-01196D

Lease No: Agreement:

OFFICE NUMBER:

(435) 781-4400

OFFICE FAX NUMBER:

(435) 781-3420

A COPY OF THESE CONDITIONS SHALL BE FURNISHED TO YOUR FIELD REPRESENTATIVE TO INSURE COMPLIANCE

All lease and/or unit operations are to be conducted in such a manner that full compliance is made with the applicable laws, regulations (43 CFR Part 3160), and this approved Application for Permit to Drill including Surface and Downhole Conditions of Approval. The operator is considered fully responsible for the actions of his subcontractors. A copy of the approved APD must be on location during construction, drilling, and completion operations. This permit is approved for a two (2) year period, or until lease expiration, whichever occurs first. An additional extension, up to two (2) years, may be applied for by sundry notice prior to expiration.

NOTIFICATION REQUIREMENTS

Location Construction (Notify Environmental Scientist)	-	Forty-Eight (48) hours prior to construction of location and access roads.
Location Completion (Notify Environmental Scientist)	-	Prior to moving on the drilling rig.
Spud Notice (Notify Petroleum Engineer)	-	Twenty-Four (24) hours prior to spudding the well.
Casing String & Cementing (Notify Supv. Petroleum Tech.)	-	Twenty-Four (24) hours prior to running casing and cementing all casing strings to: blm_ut_vn_opreport@blm.gov
BOP & Related Equipment Tests (Notify Supv. Petroleum Tech.)	-	Twenty-Four (24) hours prior to initiating pressure tests.
First Production Notice (Notify Petroleum Engineer)	-	Within Five (5) business days after new well begins or production resumes after well has been off production for more than ninety (90) days.

Page 2 of 8 Well: NBU 1022-9J1CS 4/30/2015

SURFACE USE PROGRAM CONDITIONS OF APPROVAL (COAs)

- All new and replacement internal combustion gas field engines of less than or equal to 300 designrated horsepower must not emit more than 2 gms of NO_x per horsepower-hour. This requirement does not apply to gas field engines of less than or equal to 40 design-rated horsepower.
- All and replacement internal combustion gas field engines of greater than 300 design rated horsepower must not emit more than 1.0 gms of NO_x per horsepower-hour.
- If there is an active Gilsonite mining operation within 2 miles of the well location, operator shall notify the Gilsonite operator at least 48 hours prior to any blasting during construction.
- If paleontological materials are uncovered during construction, the operator is to immediately stop
 work and contact the Authorized Officer (AO). A determination will be made by the AO as to what
 mitigation may be necessary for the discovered paleontologic material before construction can
 continue.

NBU 1022-9J1BS and NBU 1022-9J1CS

- KMG will install bird exclusion netting over reserve pits containing water that are left open for more than 30 days to reduce possibility of exposure to hazardous chemicals (BLM 2012b).
- KMG will install bird-excluding devises that prevent the perching and entry of migratory birds on or into its new fired vessel exhaust stacks (BLM 2012b). An infiltration gallery will be constructed in a U.S. Fish and Wildlife Service (USFWS)-approved location. An infiltration gallery is basically a pit or trench dug within a floodplain to a depth below the water table. Water is drawn from the pit rather than from the river directly. If this is not possible, KMG will limit pumping within the river to off-channel locations that do not connect to the river during high spring flows.
- If water cannot be drawn using the measures below, and the pump head will be located in the river channel where larval fish are known to occur, the following measures will apply (BLM 2012b):
- KMG will avoid pumping from low-flow or no-flow areas as these habitats tend to concentrate larval fishes;
- KMG will avoid pumping to the greatest extent possible, during that period of the year when larval fish may be present (approximately April 1 to August 31);
- KMG will avoid pumping, to the greatest extent possible, during the midnight hours (10:00 pm to 2:00 am) as larval drift studies indicate that is a period of greatest daily activity. Dusk is the preferred pumping time as larval drift abundance is lowest.
- KMG will screen all pump intakes with 3/32-inch mesh material.
- Silt fencing will be used to protect cacti that are within 300 feet and downslope or downwind of surface disturbance. Fencing is intended to prevent sedimentation or dust deposition and will be evaluated for effectiveness by a qualified botanist.
- A qualified botanist will be on site to monitor surface-disturbing activities when cacti are within 300 feet of any surface disturbance.
- Dust abatement (consisting of water only) will occur during construction where plants are closer than 300 feet from surface-disturbing activities.
- Cacti within 300 feet of proposed surface disturbance will be flagged immediately prior to surface-disturbing activities and flags will be removed

Page 3 of 8 Well: NBU 1022-9J1CS 4/30/2015

immediately after surface-disturbing activities are completed. Leaving cacti flagged for as short a time as possible will minimize drawing attention to the cacti location and reduce potential for theft.

- Pipelines will be sited to maximize distance from adjacent cacti locations.
- Project personnel associated with construction activities will be instructed to drive at a speed limit of 15 miles per hour on unpaved roads and remain in existing roadway ROWs at all times.
- For permanent surface pipelines, KMG will adhere to existing cacti survey/buffer guidelines of 300 feet, or amended guidelines if developed by the BLM and USFWS. In areas where avoidance by 300 feet is not feasible and populations or individuals of *Sclerocactus wetlandicus* are within 50 feet of proposed project components, the following actions will be taken to minimize impacts:
- Prior to construction, flag individual cactus. Once pipe installation is complete, remove the flagging.
- Prior to construction, install protective fencing around the cacti if they are down gradient of the surface pipe. Once pipe installation is complete, remove the protective fencing.
- A qualified botanist will be present during construction to monitor surface line installation.
- As per discussions and email with the BLM on October 18, 2012, KMG will contribute to the Utah *Sclerocactus* mitigation fund to further study the effects of development on *Sclerocactus wetlandicus* in the Uinta Basin and the effectiveness of current mitigation measures. This contribution will be provided over the first 5 years of project development and in lieu of the required 3–year monitoring described in the Vernal BLM RMP for cacti found within 300 feet of planned surface disturbance that cannot be rerouted. This is consistent with the intent of the RMP for the effects of development to be effectively monitored within the Project Area and to better assess conservation measures to avoid or minimize these impacts in the future.
- The following considerations are required for those wells where KMG deems completion fluid recycling is appropriate based on new well density and topography:
- o Temporary lines associated with recycling of completion water will be sited in existing ROWs. The pressure in the lines is less than 50 pounds per square inch and the lines are constructed of rigid aluminum; therefore, virtually no movement will occur during operation.
- If surface water completion lines are placed within the footprint of a road disturbance where vegetation does not grow, Sclerocactus wetlandicus surveys will not be necessary.
- A qualified botanist will survey a 50-foot-wide corridor along roads where temporary lines are planned to ensure *Sclerocactus wetlandicus* is not present.
- o If cacti are present within the 50-foot-wide survey corridor and avoidance is necessary (to ensure the line is more than 50 feet away from identified cactus), the new alignment will, if possible, be such that the cacti are topographically higher than the re-aligned line so a potential spill from the line will not impact the identified cacti.
- o If it is not possible to re-align the surface lines to avoid individuals or populations of the *Sclerocactus wetlandicus* that are within 50 feet of surface disturbance, the following actions will be taken to minimize impacts:
- o Prior to construction, KMG will flag individual cacti. Once pipe installation is complete, remove the flagging.
- o Prior to construction, KMG will install protective fencing around the cacti if they are down gradient of the surface pipe. Once pipe installation

Page 4 of 8 Well: NBU 1022-9J1CS 4/30/2015

is complete, remove the protective fencing.

 A qualified botanist will be present during construction to monitor surface line installation.

In addition, through several discussions and meetings in December 2011 and January 2012, KMG/Anadarko committed to the following conservation measures in core conservation areas for Sclerocactus wetlandicus:

- KMG will continue to abide by mitigation measures outlined in the 2010 Programmatic Biological Opinion (BO) if any development is proposed in cactus core conservation areas.
- Avoidance of cactus by 300 feet will take priority in the expansion of pads within the cactus core conservation areas. When the 300-foot buffer cannot be avoided in pad expansion, KMG will notify the USFWS and work with the BLM to determine pad expansion that places a priority on avoiding cactus impacts.
- o KMG will follow existing ROWs and/or roads in constructing new buried pipelines within the cactus core conservation areas. For instance, where a new buried pipeline is unable to follow an existing ROW and/or road and exceeds 600 feet in length, KMG will work with the USFWS and the BLM to determine a route that places a priority on avoiding cactus impacts.
- KMG retains the right to perform necessary maintenance activities on all existing pipelines within the cactus core conservation areas. Maintenance activities on pipelines within cactus core conservation areas will avoid impacts to cactus, to the extent possible.
- o KMG will not create new pads in the cactus core conservation areas without formal Service consultation, with the exception of 15 quarter-quarter sections within the cactus core conservation areas where new pad construction will be allowed as a condition of this consultation, with the following conditions:
- o When topographically feasible, expansion of existing well pads will take priority in Level 1 cactus core conservation areas.
- Where feasible, new pads will be placed on or adjacent to existing disturbance (e.g. roads) in the cactus core conservation areas.
- o Where topographically feasible, drill mats or similar devices will be used for new well pad development in the cactus core conservation areas.
- o Due to the high value of Level 1 cactus core conservation areas, KMG will notify the Service and work with the BLM (and the BIA if on tribal surface) to determine new pad placement that places a priority on avoiding cactus impacts when in these areas.
- If feasible, new well pad development will not occur in cactus core conservation areas located in the northeast corner of the Project Area (e.g. the population located in T8S R23E and the northern portion of T9S R23E)
- KMG will fund a study in the amount of \$100,000 in addition to typical expenditures for pad reclamation, to evaluate the technical feasibility of re-planting the Uinta Basin hookless cactus during pad reclamation activities. KMG will be allowed to review and provide input to the study work plan prior to study implementation and will be given an opportunity to review study results prior to submittal of results for publication. KMG will exercise no control over final study design or study results submitted for publication.

Page 5 of 8 Well: NBU 1022-9J1CS 4/30/2015

DOWNHOLE PROGRAM CONDITIONS OF APPROVAL (COAs)

SITE SPECIFIC DOWNHOLE COAs:

NBU 1022-9J1BS NBU 1022-9J1CS

Well specific down-hole COA's:

- Cement for the 4.5 inch casing shall be brought up to a minimum of 200 feet above the surface casing shoe.
- A CBL shall be run from TD to TOC in the Production Casing.
- Variances shall be granted as requested in Section 9 of the Drilling Program of the SOP.

All provisions outlined in Onshore Oil & Gas Order #2 Drilling Operations shall be strictly adhered to. The following items are emphasized:

DRILLING/COMPLETION/PRODUCING OPERATING STANDARDS

- The spud date and time shall be reported orally to Vernal Field Office within 24 hours of spudding.
- Notify Vernal Field Office Supervisory Petroleum Engineering Technician at least 24 hours in advance of casing cementing operations and BOPE & casing pressure tests.
- All requirements listed in Onshore Order #2 III. E. Special Drilling Operations are applicable for air drilling of surface hole.
- Blowout prevention equipment (BOPE) shall remain in use until the well is completed or abandoned. Closing unit controls shall remain unobstructed and readily accessible at all times. Choke manifolds shall be located outside of the rig substructure.
- All BOPE components shall be inspected daily and those inspections shall be recorded in the daily drilling report. Components shall be operated and tested as required by Onshore Oil & Gas Order No. 2 to insure good mechanical working order. All BOPE pressure tests shall be performed by a test pump with a chart recorder and <u>NOT</u> by the rig pumps. Test shall be reported in the driller's log.
- BOP drills shall be initially conducted by each drilling crew within 24 hours of drilling out from under the surface casing and weekly thereafter as specified in Onshore Oil & Gas Order No. 2.
- Casing pressure tests are required before drilling out from under all casing strings set and cemented in place.
- No aggressive/fresh hard-banded drill pipe shall be used within casing.
- Cement baskets shall not be run on surface casing.

Page 6 of 8 Well: NBU 1022-9J1CS 4/30/2015

- The operator must report all shows of water or water-bearing sands to the BLM. If flowing water is
 encountered it must be sampled, analyzed, and a copy of the analyses submitted to the BLM Vernal
 Field Office.
- The operator must report encounters of all non oil & gas mineral resources (such as Gilsonite, tar sands, oil shale, trona, etc.) to the Vernal Field Office, in writing, within 5 working days of each encounter. Each report shall include the well name/number, well location, date and depth (from KB or GL) of encounter, vertical footage of the encounter and, the name of the person making the report (along with a telephone number) should the BLM need to obtain additional information.
- A complete set of angular deviation and directional surveys of a directional well will be submitted to the Vernal BLM office engineer within 30 days of the completion of the well.
- While actively drilling, chronologic drilling progress reports shall be filed directly with the BLM,
 Vernal Field Office on a weekly basis in sundry, letter format or e-mail to the Petroleum Engineers until the well is completed.
- A cement bond log (CBL) will be run from the production casing shoe to the top of cement and shall be utilized to determine the bond quality for the production casing. Submit a field copy of the CBL to this office.
- Please submit an electronic copy of all other logs run on this well by CD (compact disc).
 This submission will supersede the requirement for submittal of paper logs to the BLM.
- There shall be no deviation from the proposed drilling, completion, and/or workover program as approved. Safe drilling and operating practices must be observed. Any changes in operation must have prior approval from the BLM Vernal Field Office.

Page 7 of 8 Well: NBU 1022-9J1CS 4/30/2015

OPERATING REQUIREMENT REMINDERS:

- All wells, whether drilling, producing, suspended, or abandoned, shall be identified in accordance with 43 CFR 3162.6. There shall be a sign or marker with the name of the operator, lease serial number, well number, and surveyed description of the well.
- For information regarding production reporting, contact the Office of Natural Resources Revenue (ONRR) at www.ONRR.gov.
- Should the well be successfully completed for production, the BLM Vernal Field office must be
 notified when it is placed in a producing status. Such notification will be by written communication
 and must be received in this office by not later than the fifth business day following the date on
 which the well is placed on production. The notification shall provide, as a minimum, the following
 informational items:
 - o Operator name, address, and telephone number.
 - Well name and number.
 - o Well location (1/4/4, Sec., Twn, Rng, and P.M.).
 - Date well was placed in a producing status (date of first production for which royalty will be paid).
 - The nature of the well's production, (i.e., crude oil, or crude oil and casing head gas, or natural gas and entrained liquid hydrocarbons).
 - The Federal or Indian lease prefix and number on which the well is located; otherwise the non-Federal or non-Indian land category, i.e., State or private.
 - Unit agreement and/or participating area name and number, if applicable.
 - o Communitization agreement number, if applicable.
- Any venting or flaring of gas shall be done in accordance with Notice to Lessees (NTL) 4A and needs prior approval from the BLM Vernal Field Office.
- All undesirable events (fires, accidents, blowouts, spills, discharges) as specified in NTL 3A will be reported to the BLM, Vernal Field Office. Major events, as defined in NTL3A, shall be reported verbally within 24 hours, followed by a written report within 15 days. "Other than Major Events" will be reported in writing within 15 days. "Minor Events" will be reported on the Monthly Report of Operations and Production.
- Whether the well is completed as a dry hole or as a producer, "Well Completion and Recompletion Report and Log" (BLM Form 3160-4) shall be submitted not later than 30 days after completion of the well or after completion of operations being performed, in accordance with 43 CFR 3162.4-1. Two copies of all logs run, core descriptions, and all other surveys or data obtained and compiled during the drilling, workover, and/or completion operations, shall be filed on BLM Form 3160-4. Submit with the well completion report a geologic report including, at a minimum, formation tops, and a summary and conclusions. Also include deviation surveys, sample descriptions, strip logs, core data, drill stem test data, and results of production tests if performed. Samples (cuttings, fluid,

Page 8 of 8 Well: NBU 1022-9J1CS 4/30/2015

and/or gas) shall be submitted only when requested by the BLM, Vernal Field Office.

- All off-lease storage, off-lease measurement, or commingling on-lease or off-lease, shall have prior written approval from the BLM Vernal Field Office.
- Oil and gas meters shall be calibrated in place prior to any deliveries. The BLM Vernal Field Office
 Petroleum Engineers will be provided with a date and time for the initial meter calibration and all
 future meter proving schedules. A copy of the meter calibration reports shall be submitted to the
 BLM Vernal Field Office. All measurement facilities will conform to the API standards for liquid
 hydrocarbons and the AGA standards for natural gas measurement. All measurement points shall
 be identified as the point of sale or allocation for royalty purposes.
- A schematic facilities diagram as required by Onshore Oil & Gas Order No. 3 shall be submitted to the BLM Vernal Field Office within 30 days of installation or first production, whichever occurs first. All site security regulations as specified in Onshore Oil & Gas Order No. 3 shall be adhered to. All product lines entering and leaving hydrocarbon storage tanks will be effectively sealed in accordance with Onshore Oil & Gas Order No. 3.
- Any additional construction, reconstruction, or alterations of facilities, including roads, gathering
 lines, batteries, etc., which will result in the disturbance of new ground, shall require the filing of a
 suitable plan and need prior approval of the BLM Vernal Field Office. Emergency approval may be
 obtained orally, but such approval does not waive the written report requirement.
- No location shall be constructed or moved, no well shall be plugged, and no drilling or workover
 equipment shall be removed from a well to be placed in a suspended status without prior approval
 of the BLM Vernal Field Office. If operations are to be suspended for more than 30 days, prior
 approval of the BLM Vernal Field Office shall be obtained and notification given before resumption
 of operations.
- Pursuant to Onshore Oil & Gas Order No. 7, this is authorization for pit disposal of water produced from this well for a period of 90 days from the date of initial production. A permanent disposal method must be approved by this office and in operation prior to the end of this 90-day period. In order to meet this deadline, an application for the proposed permanent disposal method shall be submitted along with any necessary water analyses, as soon as possible, but no later than 45 days after the date of first production. Any method of disposal which has not been approved prior to the end of the authorized 90-day period will be considered as an Incident of Noncompliance and will be grounds for issuing a shut-in order until an acceptable manner for disposing of said water is provided and approved by this office.
- Unless the plugging is to take place immediately upon receipt of oral approval, the Field Office
 Petroleum Engineers must be notified at least 24 hours in advance of the plugging of the well, in
 order that a representative may witness plugging operations. If a well is suspended or abandoned,
 all pits must be fenced immediately until they are backfilled. The "Subsequent Report of
 Abandonment" (Form BLM 3160-5) must be submitted within 30 days after the actual plugging of
 the well bore, showing location of plugs, amount of cement in each, and amount of casing left in
 hole, and the current status of the surface restoration.

	STATE OF UTAH			FORM 9		
ι	DEPARTMENT OF NATURAL RESOUF DIVISION OF OIL, GAS, AND M			5.LEASE DESIGNATION AND SERIAL NUMBER: UTU 01196-D		
SUNDR	RY NOTICES AND REPORTS	S ON V	WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:		
	posals to drill new wells, significantl reenter plugged wells, or to drill horiz n for such proposals.			7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES		
1. TYPE OF WELL Gas Well				8. WELL NAME and NUMBER: NBU 1022-9J1CS		
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ON	ISHORE, L.P.		9. API NUMBER: 43047552660000			
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th	h Street, Suite 600, Denver, CO, 802	NE NUMBER: 720 929-6	9. FIELD and POOL or WILDCAT: 110ATURAL BUTTES			
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1913 FSL 1793 FEL			COUNTY: UINTAH			
QTR/QTR, SECTION, TOWNSH	HIP, RANGE, MERIDIAN: 09 Township: 10.0S Range: 22.0E Mei	eridian: S	3	STATE: UTAH		
11. CHECI	K APPROPRIATE BOXES TO INDICA	ATE NA	TURE OF NOTICE, REPOR	T, OR OTHER DATA		
TYPE OF SUBMISSION			TYPE OF ACTION			
	ACIDIZE		TER CASING	CASING REPAIR		
NOTICE OF INTENT Approximate date work will start:	CHANGE TO PREVIOUS PLANS	☐ c⊦	ANGE TUBING	CHANGE WELL NAME		
	CHANGE WELL STATUS	□ cc	DMMINGLE PRODUCING FORMATIONS	CONVERT WELL TYPE		
SUBSEQUENT REPORT Date of Work Completion:	DEEPEN	☐ FR	ACTURE TREAT	NEW CONSTRUCTION		
	OPERATOR CHANGE	PL	UG AND ABANDON	PLUG BACK		
✓ SPUD REPORT	PRODUCTION START OR RESUME	☐ RE	CLAMATION OF WELL SITE	RECOMPLETE DIFFERENT FORMATION		
Date of Spud: 6/11/2015	REPERFORATE CURRENT FORMATION	☐ sii	DETRACK TO REPAIR WELL	TEMPORARY ABANDON		
0/11/2013	TUBING REPAIR		NT OR FLARE	WATER DISPOSAL		
DRILLING REPORT Report Date:	WATER SHUTOFF		TA STATUS EXTENSION	APD EXTENSION		
Report Bate.		_ v.				
	WILDCAT WELL DETERMINATION	01	THER	OTHER:		
Spud well 06/11/20 ² X .250 wall co	COMPLETED OPERATIONS. Clearly show 15 @ 10:00. Drill 24" cond nductor pipe, cement with 9 spud date and surface ca	ductor 90 sa	hole to 40', run 14" cks ready mix.	Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY June 15, 2015		
NAME (PLEASE PRINT) Doreen Green	PHONE NUM 435 781-9758		TITLE Regulatory Analyst II			
SIGNATURE N/A			DATE 6/15/2015			

	STATE OF UTAH		FORM 9			
ı	DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING	3	5.LEASE DESIGNATION AND SERIAL NUMBER: UTU 01196-D			
SUNDR	Y NOTICES AND REPORTS ON	WELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:			
	posals to drill new wells, significantly dee reenter plugged wells, or to drill horizontal n for such proposals.		7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES			
1. TYPE OF WELL Gas Well			8. WELL NAME and NUMBER: NBU 1022-9J1CS			
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ON	9. API NUMBER: 43047552660000					
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th	9. FIELD and POOL or WILDCAT: 100ATURAL BUTTES					
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1913 FSL 1793 FEL		COUNTY: UINTAH				
QTR/QTR, SECTION, TOWNSH	HP, RANGE, MERIDIAN: 09 Township: 10.0S Range: 22.0E Meridian:	s	STATE: UTAH			
11. CHECI	K APPROPRIATE BOXES TO INDICATE N	IATURE OF NOTICE, REPOR	T, OR OTHER DATA			
TYPE OF SUBMISSION		TYPE OF ACTION				
	CHANGE TO PREVIOUS PLANS CHANGE WELL STATUS DEEPEN OPERATOR CHANGE PRODUCTION START OR RESUME REPERFORATE CURRENT FORMATION TUBING REPAIR		CASING REPAIR CHANGE WELL NAME CONVERT WELL TYPE NEW CONSTRUCTION PLUG BACK RECOMPLETE DIFFERENT FORMATION TEMPORARY ABANDON WATER DISPOSAL APD EXTENSION OTHER: Epths, volumes, etc. Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY September 29, 2015			
NAME (PLEASE PRINT)	PHONE NUMBER	TITLE				
Jennifer Thomas SIGNATURE	720 929-6808	Regulatory Specialist DATE				
N/A		9/29/2015				

	STATE OF UTAH			FORM 9			
ı	DEPARTMENT OF NATURAL RESOUR DIVISION OF OIL, GAS, AND MI			5.LEASE DESIGNATION AND SERIAL NUMBER: UTU 01196-D			
SUNDR	RY NOTICES AND REPORTS	ON W	ELLS	6. IF INDIAN, ALLOTTEE OR TRIBE NAME:			
	posals to drill new wells, significantly reenter plugged wells, or to drill horiz n for such proposals.			7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES			
1. TYPE OF WELL Gas Well				8. WELL NAME and NUMBER: NBU 1022-9J1CS			
2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ON	ISHORE, L.P.		9. API NUMBER: 43047552660000				
3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18th	9. FIELD and POOL or WILDCAT: 5NATERAL BUTTES						
4. LOCATION OF WELL FOOTAGES AT SURFACE: 1913 FSL 1793 FEL		COUNTY: UINTAH					
QTR/QTR, SECTION, TOWNSH	HIP, RANGE, MERIDIAN: 09 Township: 10.0S Range: 22.0E Mer	ridian: S		STATE: UTAH			
11. CHECI	K APPROPRIATE BOXES TO INDICA	ATE NAT	URE OF NOTICE, REPOR	T, OR OTHER DATA			
TYPE OF SUBMISSION			TYPE OF ACTION				
	ACIDIZE	ALTE	R CASING	CASING REPAIR			
NOTICE OF INTENT Approximate date work will start:	CHANGE TO PREVIOUS PLANS	CHAN	NGE TUBING	CHANGE WELL NAME			
Approximate date work will start.	CHANGE WELL STATUS	□ сом	MINGLE PRODUCING FORMATIONS	CONVERT WELL TYPE			
SUBSEQUENT REPORT Date of Work Completion:	DEEPEN	FRAC	CTURE TREAT	NEW CONSTRUCTION			
12/9/2015	OPERATOR CHANGE	PLUG	G AND ABANDON	PLUG BACK			
SPUD REPORT	✓ PRODUCTION START OR RESUME	RECL	AMATION OF WELL SITE	RECOMPLETE DIFFERENT FORMATION			
Date of Spud:	REPERFORATE CURRENT FORMATION	SIDE	TRACK TO REPAIR WELL	TEMPORARY ABANDON			
	TUBING REPAIR	VENT	OR FLARE	WATER DISPOSAL			
DRILLING REPORT Report Date:	WATER SHUTOFF		STATUS EXTENSION	APD EXTENSION			
Report Bate.							
	WILDCAT WELL DETERMINATION	OTHE	=R 	OTHER:			
The NBU 1022-9J	COMPLETED OPERATIONS. Clearly show ITCS well was placed on propletion. Producing from the	roducti	on on 12/9/2015	Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY December 10, 2015			
NAME (PLEASE PRINT) Jennifer Thomas	PHONE NUM 720 929-6808		I TLE Regulatory Specialist				
SIGNATURE N/A			ATE 2/9/2015				

Form 3160-4 (August 2007)			UNITED STATES DEPARTMENT OF THE INTERIOR BUREAU OF LAND MANAGEMENT											OM	IB No. 1	PROVED 004-0137 y 31, 2010		
	WELL (COMPL	ETION C	R RE	CO	MPLE	TIO	N RE	PO	RT	AND L	.OG				ase Serial TU01196		
1a. Type of	Well	Oil Well	⊠ Gas ^v	Well	□ I	Ory	□ Ot	her							6. If	Indian, Al	lottee o	r Tribe Name
b. Type of	f Completion	_	lew Well er	□ Wo		_] Dec	epen		Plug	Back	☐ Di	ff. Re	esvr.	7. Uı	nit or CA A	Agreem _A	ent Name and No.
2. Name of KFRR-I	Operator MCGEE OIL	AND G	AS ONSH ©	RWFail:.	Jennit	Contac fer Tho									8. Le	ase Name BU 1022-	and We	
	P.O. BOX DENVER,	173779			-			3a.	Phon	e No	. (include	e area c	ode)			PI Well No		43-047-55266
4. Location	Location of Well (Report location clearly and in accordance with Federal requirements)* 10. Field and Pool, or Exploratory																	
At surfa	ce NWSE	1913FS	L 1793FEL	39.961	504 I	N Lat, 1	09.4	41752	W Lo	on						ATURAL Sec. T. R		ES Block and Survey
At top p	rod interval r	eported b	elow NWS	SE 228	1FSL	_ 1799F	EL								OI	r Area Se	c 9 T1	0S R22E Mer SLB
At total	depth NW	SE 2279	FSL 1808FI	EL 39.9	96249	93 N La	t, 109	9.4418	30 W	/ Lor	1				12. C	County or I INTAH	Parish	13. State UT
14. Date Sp 06/11/2	oudded 2015			ate T.D. /25/20		hed				D & .	Complet A 🔯 9/2015	ed Ready	to Pr	od.	17. E		(DF, KI 21 KB	B, RT, GL)*
18. Total D	epth:	MD TVD	8902 8885		19.	Plug Ba	ck T.	D.:	MI TV			342 326		20. Dep	oth Brid	dge Plug S		MD TVD
21. Type El RADIAL	lectric & Oth L CEMENT	er Mecha GAMMA	nical Logs R RAY CCL	un (Sub	mit co	opy of e	ach)					W	as D	ell cored ST run? ional Su		No No	☐ Yes	s (Submit analysis) s (Submit analysis) s (Submit analysis)
23. Casing ar	nd Liner Reco	ord (Repo	ort all strings	set in v	vell)								necti	ionai ba	ivey.		Z 10.	(Submit analysis)
Hole Size	Size/G	rade	Wt. (#/ft.)	To (Ml	•	Botto (MI		Stage D	Ceme Depth	enter		of Sks. & of Ceme		Slurry (BB		Cement	Top*	Amount Pulled
24.000		000 STL	36.7		0		40						90					
11.000 7.875		525 J-55 500 I-80	28.0 11.6		13 13	_	2456 3890						825 798				992	
7.075	4.	300 1-00	11.0		10		0000						730				332	
24. Tubing	Record			<u> </u>		<u> </u>												
	Depth Set (N	ID) P	acker Depth	(MD)	Si	ze	Depth	n Set (N	MD)	P	acker De	pth (MI	D)	Size	De	pth Set (M	(D)	Packer Depth (MD)
2.375		8562					100	D. C		$oxed{oxed}$								
25. Producii	ormation		Тор	Т	Ro.	ttom	26.	Perfora			ra Interval		Т	Size	\Box	lo. Holes	Т	Perf. Status
A)	MESAVE	RDE		6809		8902		1	CHOI	ateu	7958 T	O 8756	3	0.4	_		OPE	
В)																		
<u>C)</u>													-		_		-	
D)	acture, Treat	ment Cer	ment Squeeze	Ftc														
	Depth Interva	-	nent Squeeze	, Etc.						Ar	nount and	d Type o	of Ma	aterial				
			756 PUMP 5	6294 B	BLS S	SLICKWA	ATER,	, 18 BB	LS 15	5% H	CL ACID,	115090	LBS	30/50 N	IESH S	AND		
28. Producti	ion - Interval	A																
Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL		Gas MCF		/ater BL		Oil Gra Corr. A			as ravity		Producti	on Method		
12/09/2015	12/23/2015	24	- Coddction	4.0	- 1	817.0	- 1	447.0		COII. F	AF I		iavity			FLO	WS FRO	OM WELL
Choke Size 20/64	Tbg. Press. Flwg. 498 SI	Csg. Press. 1242.0	24 Hr. Rate	Oil BBL 4		Gas Water Gas:Oil Well Status MCF BBL Ratio 817 447 PGW												
	tion - Interva	<u> </u>				317		171										
Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL		Gas MCF												
Choke Size	Tbg. Press. Flwg.	Csg. Press.	24 Hr. Rate	Oil BBL		Gas MCF		/ater BL		Gas:Oi Ratio	1	W	/ell Sta	itus				

⁽See Instructions and spaces for additional data on reverse side)
ELECTRONIC SUBMISSION #327852 VERIFIED BY THE BLM WELL INFORMATION SYSTEM

** OPERATOR-SUBMITTED ** OPERATOR-SUBMITTED **

Sundı	ry Numk	oer:	68916	API We	ell N	Jumber:	4304	75526	6000	0		
28h Pro/	duction - Inter	rval C										
Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravit Corr. API		Gas Gravity	Production Method	od	
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio		Well Statu	s		
28c. Proc	duction - Inter	val D										
Date First Produced	Test Date	Hours Tested	Test Production	Oil BBL	Gas MCF	Water BBL	Oil Gravit Corr. API		Gas Gravity	Production Method		
Choke Size	Tbg. Press. Flwg. SI	Csg. Press.	24 Hr. Rate	Oil BBL	Gas MCF	Water BBL	Gas:Oil Ratio		Well Statu	s		
29. Dispo	osition of Gas TURED	(Sold, used	d for fuel, ven	ted, etc.)	1				ı			
	nary of Porou	s Zones (I	nclude Aquif	ers):					3	1. Formation (Log)	Markers	
tests,	all important including dep ecoveries.	t zones of joth interva	porosity and o l tested, cushi	contents ther ion used, tim	eof: Core e tool ope	d intervals and en, flowing and	all drill-st shut-in pr	em ressures				
	Formation		Тор	Bottom		Description	ns, Conte	nts, etc.		Namo	e	Top Meas. Deptl
32. Addi	tional remarks	s (include)	plugging proc	cedure):						GREEN RIVER BIRDS NEST MAHOGANY M. WASATCH MESAVERDE		1147 1475 1946 4309 6809
1. El	e enclosed att lectrical/Mech undry Notice f	anical Log		•		2. Geologic 6. Core Ana	•		3. DS 7 Oth	ST Report ner:	4. Direction	onal Survey
		-	Elect	tronic Subm For KERR	ission #3	omplete and cor 27852 Verified E OIL AND GA	l by the B AS ONSH	LM Well l IORE, sen	Information to the V	nilable records (see a on System. ernal Y SPECIALIST III	attached instruct	ions):
name	e(please print) <u>JEININIF</u>	LN IHOWA	io				THE KEG	<u>ULATUR</u>	1 OF LOIALIOT III		
Signa	ature	(Electro	nic Submiss	sion)]	Date <u>01/06</u>	6/2016			
Title 18 I	U.S.C. Section	n 1001 and	Title 43 U.S	.C. Section 1	212, mak	xe it a crime for	any perso	on knowing	ly and wil	Ifully to make to an	y department or	agency
of the Ur	nted States an	y false, fic	cutious or frac	aulent statem	ents or re	epresentations a	s to any n	natter withi	n its jurisc	liction.		

				U	S ROC	KIES R	EGION	
			(Opera	ition S	umma	ary Report	
Well: NBU 1022	2-9J1CS BLACK						Spud date: 6/24	4/2015
Project: UTAH-L	JINTAH		Site: NBU	1022-9J	PAD		·	Rig name no.: PROPETRO 12/12, ENSIGN 145/145
Event: DRILLIN	G		Start date	· 6/24/20	15			End date: 9/26/2015
	KB @5,221.00usft (a	bove Mean S		13/E/0/1793/0/0				
Level)		201004 0	-					
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD from (usft)	Operation
6/11/2015	10:00 - 11:00	1.00	DRLCON	2	Α	Р		DRILL 24" CONDUCTOR HOLE TO 40'
	11:00 - 12:00	1.00	DCSGCON	12	E	Р		SET 14" CONDUCTOR CASING AND CEMENT WITH 90 SX CEMENT
6/23/2015	21:00 - 0:00	3.00	MIRU	01	В	Р	49	PRE JOB SAFETY MEETING WITH JD TRUCKING, STALLION CREW. MOVE CAMPS IN & RIG UP. 1 BED TRUCKS, 2 HAUL TRUCKS, 1 TRUCK PUSHER, 1 SWAMPER, 1 ROUSTABOUT.
6/24/2015	0:00 - 5:30	5.50	MIRU	01	В	Р	49	PRE JOB SAFETY MEETING WITH JD TRUCKING,STALLION CREW, PROPETRO RIG CREW. RIG UP CAMPS, MOVE AND RIG UP, TANK FARM, MUD PITS, MUD PUMP, ZECO SOLIDS CONTROL. 2 BED TRUCKS, 2 HAUL TRUCKS, 1 TRUCK PUSHER, 1 SWAMPER, 1 ROUSTABOUT.
	5:30 - 6:00	0.50	MIRU	23	0	Р	49	PRE TOUR SAFETY MEETING
	6:00 - 14:00	8.00	MIRU	01	В	P	49	CONTINUE TO RIG UP, MOVE AND RIG UP, TANK FARM, MUD PITS, MUD PUMP, ZECO SOLIDS CONTROL. 2 BED TRUCKS, 2 HAUL TRUCKS, 1 TRUCK PUSHER, 1 SWAMPER, 1 ROUSTABOUT. RELEASE TRUCKS @ 10:00 6/24/2015 FILL PITS, SET MATTING BOARD, SET RIG IN PLACE ON NBU 1022-9J1BS WELL 1 OF 7, JSA, RIG UP FLOW AND MUD LINES, REVIEW DIRECTIONAL PLANS AND PLATS AND VERIFY LAT/LONGS, VERIFY DIRECTIONAL DRILLERS PLAN IS THE MOST RECENT AND APPROVED VERSION REFERENCE WELLBORE DIAGRAMS FOR EXACT CASING DESIGN AND GENERAL OVERVIEW OF WELLBORE PRIOR TO SPUD.
	14:00 - 17:30	3.50	MIRU	01	В	Р	49	FINISH RIG UP, PRE SPUD INSPECTION,
	17:30 - 18:00	0.50	MIRU	23	0	Р	49	PRE TOUR SAFETY MEETING
	18:00 - 19:30	1.50	MIRU	06	Α	Р	49	PICK UP NOV 1.83 DEGREE BENT MOTOR (RUN # 1) .17 REV/GAL PICK UP 12.25" DRILL BIT. PICK UP ROTATING HEAD.
	19:30 - 21:30	2.00	DRLSUR	02	В	Р	49	DRILL 12:25" HOLE F/ 40' T/ 210@ 85'PH) WEIGHT ON BIT 25 K STROKES PER MINUTE = 120 GALLONS PER MINUTE = 491 PRESSURE ON/OFF (BOTTOM) 560/460 ROTARY RPM 55 MOTOR RPM 83 TOTAL RPM 138 UP/DOWN/ ROTATE 25/25/25 K. DRAG 0 K. CIRCULATE CLOSED LOOP SYSTEM WITH 8.5# WATER. RUNNING VOLUME THROUGH 2 CENTRIFUGE DE WATERING RUNNING VOLUME OVER BOTH SHAKERS NO HOLE ISSUES

1/6/2016 9:48:29AM 1

Sundry Number: 68916 API Well Number: 43047552660000 **US ROCKIES REGION Operation Summary Report** Well: NBU 1022-9J1CS BLACK Spud date: 6/24/2015 Project: UTAH-UINTAH Site: NBU 1022-9J PAD Rig name no.: PROPETRO 12/12, ENSIGN 145/145 **Event: DRILLING** End date: 9/26/2015 Start date: 6/24/2015 UWI: NW/SE/0/10/S/22/E/9/0/0/26/PM/S/1913/E/0/1793/0/0 Active datum: RKB @5,221.00usft (above Mean Sea P/U Date Time Duration Phase Code Sub MD from Operation Start-End (hr) Code (usft) 21:30 - 0:00 2.50 DRLSUR 06 Ρ 219 PRE JOB SAFETY MEETING, CIRC 15 MINUTES Α TRIP OUT OF HOLE LAY DOWN BHA # (12 1/4" BIT) P/U BHA #2 TRIP IN HOLE, MAKE UP REED-NOV 11", 8" DIRECTIONAL ASSEMBLY, SCIBE MOTOR, INSTALL EM TOOL AND TRIP IN HOLE. 6/25/2015 0:00 - 0:30 RIG SERVICE & CHECK FITTING 0.50 **DRLSUR** 07 Α Р 219 0:30 - 1:00 0.50 DRLSUR 06 Α Ρ 219 INSTALL ROTATING HEAD RUBBER 1:00 - 5:30 Р 4.50 DRI SUR 02 D 219 DRILL 11" SURFACE HOLE F/210' T/ 610' (400'@ 89'PH) WEIGHT ON BIT 15-20 K STROKES PER MINUTE=120 GALLONS PER MINUTE=491 PRESSURE ON/OFF(BOTTOM) 800 / 490 **ROTARY RPM 55** MOTOR RPM 83 TOTAL RPM 138 UP/DOWN/ ROT 25/25/25 K. DRAG 0K DIRECTIONAL PLAN CURRENTLY 2.39' ft HIGH, 0.52' ft LEFT SLIDE 386 ft @ 2.75Hrs CIRCULATE CLOSED LOOP SYSTEM WITH 8.5# WATER RUNNING VOLUME THROUGH 2 CENTRIFUGES DEWATERING. RUNNING VOLUME OVER BOTH SHAKERS NO HOLE ISSUES 5:30 - 6:00 0.50 619 PRE TOUR SAFETY MEETING DRI SUR 23 0 Р 6:00 - 12:00 6.00 **DRLSUR** 02 D 619 DRILL 11" SURFACE HOLE F/610' T/ 1060' (450'@ 75'PH) WEIGHT ON BIT 15-20 K STROKES PER MINUTE = 120 GALLONS PER MINUTE = 491 PRESSURE ON/OFF(BOTTOM) 800 / 490 **ROTARY RPM 55** MOTOR RPM 83 **TOTAL RPM 138** UP/DOWN/ ROT 25/25/25 K. DRAG 0K DIRECTIONAL PLAN CURRENTLY 1.4 ft. high 6.7' ft right SLIDE 140 ft @ 1.5 Hrs CIRCULATE CLOSED LOOP SYSTEM WITH 8.5# WATER RUNNING VOLUME THROUGH 2 CENTRIFUGES DEWATERING. RUNNING VOLUME OVER BOTH SHAKERS NO HOLE ISSUES

1/6/2016 9:48:29AM 2

Α

12:00 - 12:30

0.50

DRLSUR

RIG SERVICE

Sundry Number: 68916 API Well Number: 43047552660000 **US ROCKIES REGION Operation Summary Report** Spud date: 6/24/2015 Well: NBU 1022-9J1CS BLACK Project: UTAH-UINTAH Site: NBU 1022-9J PAD Rig name no.: PROPETRO 12/12, ENSIGN 145/145 **Event: DRILLING** End date: 9/26/2015 Start date: 6/24/2015 UWI: NW/SE/0/10/S/22/E/9/0/0/26/PM/S/1913/E/0/1793/0/0 Active datum: RKB @5,221.00usft (above Mean Sea P/U Date Time Duration Phase Code Sub MD from Operation Start-End (hr) Code (usft) 12:30 - 17:30 5.00 DRLSUR 02 D Ρ 1069 DRILL 11" SURFACE HOLE F/ 1060' TO 1360' (300'@ WEIGHT ON BIT 15-20 K STROKES PER MINUTE = 120 GALLONS PER MINUTE = 491 PRESSURE ON/OFF(BOTTOM) 1050 / 850 **ROTARY RPM 55 MOTOR RPM 83 TOTAL RPM 138** UP/DOWN/ ROT 68/55/64 K. DRAG 4K DIRECTIONAL PLAN CURRENTLY 3.3 ft. high 5.7' ft SLIDE 0 ft @ 0 Hrs CIRCULATE CLOSED LOOP SYSTEM WITH 8.5# WATER RUNNING VOLUME THROUGH 2 CENTRIFUGES DEWATERING. RUNNING VOLUME OVER BOTH SHAKERS NO HOLE ISSUES 17:30 - 18:00 0.50 DRLSUR 0 Ρ 1369 PRE TOUR SAFETY MEETING 18:00 - 0:00 6.00 D Р 1369 **DRLSUR** 02 DRILL 11" SURFACE HOLE F/ 1360' TO 1990' (630'@ 105'PH) WEIGHT ON BIT 15-20 K STROKES PER MINUTE = 120 GALLONS PER MINUTE = 491 PRESSURE ON/OFF(BOTTOM) 1172 PSI / 984 PSI **ROTARY RPM 55** MOTOR RPM 83 **TOTAL RPM 138** UP/DOWN/ ROT 79/62/72 K. DRAG 7K DIRECTIONAL PLAN CURRENTLY 2.5 ft. high 1.6' ft right SLIDE 152 ft @ 1.92 Hrs CIRCULATE CLOSED LOOP SYSTEM WITH 8.5# WATER RUNNING VOLUME THROUGH 2 CENTRIFUGES DEWATERING. RUNNING VOLUME OVER BOTH SHAKERS NO HOLE ISSUES

1/6/2016 9:48:29AM 3

AIR ON @ 1570' CFM 1755

Sundry Number: 68916 API Well Number: 43047552660000 US ROCKIES REGION **Operation Summary Report** Well: NBU 1022-9J1CS BLACK Spud date: 6/24/2015 Project: UTAH-UINTAH Site: NBU 1022-9J PAD Rig name no.: PROPETRO 12/12, ENSIGN 145/145 **Event: DRILLING** End date: 9/26/2015 Start date: 6/24/2015 UWI: NW/SE/0/10/S/22/E/9/0/0/26/PM/S/1913/E/0/1793/0/0 Active datum: RKB @5,221.00usft (above Mean Sea Date P/U Time Duration Phase Code MD from Operation Sub Start-End (hr) Code (usft) 6/26/2015 0:00 - 5:30 5.50 DRLSUR 02 Ρ 1999 D DRILL 11" SURFACE HOLE F/ 1990' TO 2320' (330'@ WEIGHT ON BIT 15-20 K STROKES PER MINUTE = 120 GALLONS PER MINUTE = 491 PRESSURE ON/OFF(BOTTOM) 1180 PSI / 990 PSI **ROTARY RPM 55 MOTOR RPM 83 TOTAL RPM 138** UP/DOWN/ ROT 88/65/74 K. DRAG 14K DIRECTIONAL PLAN CURRENTLY 0.5 ft. LOW 3.79' ft RIGHT SLIDE 50 ft @ 0.75 Hrs CIRCULATE CLOSED LOOP SYSTEM WITH 8.5# WATER RUNNING VOLUME THROUGH 2 CENTRIFUGES DEWATERING. RUNNING VOLUME OVER BOTH SHAKERS NO HOLE ISSUES AIR ON @ 1570' CFM 1755 CONFERENCE CALLS WITH TEAM ABOUT MAGNETIC INTERERANCE 5:30 - 6:00 0.50 **DRLSUR** 23 0 Р 2329 PRE TOUR SAFETY MEETING 6:00 - 8:00 2.00 D Р 2329 **DRLSUR** 02 DRILL 11" SURFACE HOLE F/ 2320' TO 2477' (157'@ WEIGHT ON BIT 15-20 K STROKES PER MINUTE = 120 GALLONS PER MINUTE = 491 PRESSURE ON/OFF(BOTTOM) 1140 PSI / 930 PSI **ROTARY RPM 55** MOTOR RPM 83 **TOTAL RPM 138** UP/DOWN/ ROT 86/72/78 K. DRAG 8K DIRECTIONAL PLAN ENDED 1.4 ft. low & 1.9 ft right SLIDE 60 ft @ 1.17 Hrs CIRCULATE CLOSED LOOP SYSTEM WITH 8.5# WATER RUNNING VOLUME THROUGH 2 CENTRIFUGES DEWATERING. RUNNING VOLUME OVER BOTH SHAKERS NO HOLE ISSUES AIR ON @ 1570' CFM 1755 TD @ 08:00 HRS ON 6-26-2015 8:00 - 10:00 2486 2.00 **CSGSUR** 05 С CIRCULATE AND CONDITION HOLE, VOLUME IS CLEAN COMING OVER SHAKERS, 600 BBLS H20 ON LOCATION FOR DRILLING 800 BBLS H20 ON LOCATION FOR CEMENT 10:00 - 15:30 5.50 **CSGSUR** 2486 06 Ρ TRIP OUT OF HOLE, LAY DOWN DRILL STRING, BHA, LAY DOWN DIRECTIONAL TOOLS, MOTOR, AND, BIT. RUN CHECK SHOT ON HOT SPOT COMING OUT TO VERIFIED V-TOTALS 2170', 1840' & 1090' 15:30 - 16:30 **CSGSUR** Ρ 2486 1.00 12 MOVE CAT WALK & PIPE RACKS, PJSM, R/U TO RUN 8 5/8" CSG

1/6/2016 9:48:29AM 4

Sundry	Number: 0	58916	APT We	ıl N	<u>lumbe</u>	r: 4	3047552	660000	
_				U	S ROC	KIES RI	EGION		
				Opera	tion S	umma	ary Report		
Well: NBU 1022	-9J1CS BLACK						Spud date: 6/2	4/2015	
Project: UTAH-U	JINTAH		Rig name no.: PROPETRO 12/12, ENSIGN 145/145						
Event: DRILLING	G		Start date	: 6/24/20	15			End date: 9/26/2015	
Active datum: RKB @5,221.00usft (above Mean Sea Level) UWI: NW/SE/0/10/S/22/E/9/0/0/26/PM/S/1913/E/0/1793/0/0									
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD from (usft)	Operation	
	16:30 - 17:30	1.00	CSGSUR	12	С	Р	2486	RUN 56 JOINTS OF 8-5/8" 28# J-55 LT&C CASING. RAN 1 CENTRALIZER ON FIRST THREE JOINTS, AND EVERY TWO JOINT FOR 2 JOINTS FOR A TOTAL OF 5 CENTRALIZERS. RUN CASING TO BOTTOM WITH NO PROBLEMS. LANDED FLOAT SHOE @ 2,446.98' SET TOP OF BAFFLE PLATE @ 2,401.06' (CLEAN PITS)	
	17:30 - 18:00	0.50	CSGSUR	23	0	Р	2486	PRE TOUR SAFETY MEETING	
	18:00 - 21:00	3.00	CSGSUR	12	С	Р	2486	FINISH RUNNING 56 JOINTS OF 8-5/8" 28# J-55 LT&C CASING. RAN 1 CENTRALIZER ON FIRST THREE JOINTS, AND EVERY TWO JOINT FOR 2 JOINTS FOR A TOTAL OF 5 CENTRALIZERS. RUN CASING TO BOTTOM WITH NO PROBLEMS. LANDED FLOAT SHOE @ 2,446.98' SET TOP OF BAFFLE PLATE @ 2,401.06' (CLEAN PITS)	

1/6/2016 9:48:29AM 5

Sundry Number: 68916 API Well Number: 43047552660000 **US ROCKIES REGION Operation Summary Report** Well: NBU 1022-9J1CS BLACK Spud date: 6/24/2015 Project: UTAH-UINTAH Site: NBU 1022-9J PAD Rig name no.: PROPETRO 12/12, ENSIGN 145/145 **Event: DRILLING** End date: 9/26/2015 Start date: 6/24/2015 UWI: NW/SE/0/10/S/22/E/9/0/0/26/PM/S/1913/E/0/1793/0/0 Active datum: RKB @5,221.00usft (above Mean Sea Date P/U Time Duration Phase Code Sub MD from Operation Start-End (hr) Code (usft) 21:00 - 0:00 3.00 **CSGSUR** 12 Ρ 2486 Ε 5PRE JOB SAFETY MEETING WITH PRO PETRO CEMENTERS. RIG UP AND INSTALL CEMENT HEAD, START CEMENT OPERATIONS. PRESSURE TEST LINES TO 2500 PSI. PUMP 30 BBLS H2O AND PUMP 20 BBLS OF 8.4# GEL WATER AHEAD. MIX AND PUMP (300 SX) 61.4 BBLS OF 15.8# 1.15 YP 5 GAL/SK PREMIUM CEMENT W/ 2% CALC. DROP PLUG ON FLY. DISPLACE W/ 151 BBLS OF H20. NO CIRC THROUGH OUT. FINAL LIFT OF 250 PSI AT 4 BBL/MIN. BUMP PLUG WITH 750 PSI FOR 5 MIN. FLOAT HELD. RIG DOWN CEMENT HEAD, PICKED UP LANDING JOINT, PULLED BUSHINGS, PULLED DIVERTER RUBBER, SET ELEVATORS, CASING LANDED ON CONDUCTOR, RUN 200' OF 1" PIPE DOWN BACK SIDE OF 8.5/8" CASING ANNULUS, R/D PROPETRO RIG. RELEASED RIG ON 6/27/2015 @ 00:00 HRS TOP JOB # 1: PUMP CEMENT DOWN ONE INCH PIPE WITH 100 SX PREMIUM CEMENT WITH 4% CACL2 & .25 LB/SX FLOCELE. 150# GR-3 20.4 BBLS OF SLURRY MIXED AT 15.8 PPG WITH YIELD OF 1.15 CF/SX. NO CEMENT TO SURFACE. TOP JOB # 2: PUMP CEMENT DOWN ONE INCH PIPE WITH 125 SX PREMIUM CEMENT WITH 4% CACL2 & .25 LB/SX FLOCELE. 150# GR-3 25.6 BBLS OF SLURRY MIXED AT 15.8 PPG WITH YIELD OF 1.15 CF/SX. NO CEMENT TO SURFACE. TOP JOB # 3: PUMP CEMENT DOWN ONE INCH PIPE WITH 150 SX PREMIUM CEMENT WITH 4% CACL2 & .25 LB/SX FLOCELE, 150# GR-3 30,72 BBLS OF SLURRY MIXED AT 15.8 PPG WITH YIELD OF 1.15 CF/SX. NO CEMENT TO SURFACE. TOP JOB # 4: PUMP CEMENT DOWN ONE INCH PIPE WITH 150 SX PREMIUM CEMENT WITH 4% CACL2 & .25 LB/SX FLOCELE. 150# GR-3, 30.72 BBLS OF SLURRY MIXED AT 15.8 PPG WITH YIELD OF 1.15 CF/SX. CEMENT TO SURFACE AND STAYING. RELEASE CEMENTERS @ 6/27/15 08:30 HRS. 9/22/2015 18:00 - 21:00 3.00 MIRU3 01 С Ρ 2486 SKID RIG TO NBU 1022-9G4CS 21:00 - 22:00 PRPSPD Ρ 2486 NIPPLE UP B.O.P'S & RIG UP ROTARY TOOLS 1.00 Α 22:00 - 0:00 Р 2.00 **CSGSUR** 2486 15 Α SAFETY MEETING WITH CREW, START TESTING BOP WITH B&C TESTERS TEST ANNULAR TO 250 PSI LOW/ 5 MIN 2500 PSI HIGH 10 MIN, PIPE & BLIND RAMS, FLOOR VALVES, IBOP, HCR VALVE, KILL LINE VALVES, TEST BOPS, CHOKE MANIFOLD TO 250 PSI LOW / 5 MIN - 5000 PSI HIGH / 10 MIN, HOLD ACCUMULATOR FUNCTION TEST, & TEST SURFACE CASING 1500 PSI FOR 30 MINS.

1/6/2016 9:48:29AM 6

Sundry Number: 68916 API Well Number: 43047552660000 **US ROCKIES REGION Operation Summary Report** Well: NBU 1022-9J1CS BLACK Spud date: 6/24/2015 Project: UTAH-UINTAH Site: NBU 1022-9J PAD Rig name no.: PROPETRO 12/12, ENSIGN 145/145 **Event: DRILLING** End date: 9/26/2015 Start date: 6/24/2015 UWI: NW/SE/0/10/S/22/E/9/0/0/26/PM/S/1913/E/0/1793/0/0 Active datum: RKB @5,221.00usft (above Mean Sea P/U Date Time Duration Phase Code Sub MD from Operation Start-End (hr) Code (usft) 0:00 - 2:00 9/23/2015 2.00 **CSGSUR** 15 Ρ 2486 Α FINISH TESTING BOP'S WITH B&C TESTERS TEST ANNULAR TO 250 PSI LOW/ 5 MIN 2500 PSI HIGH 10 MIN, PIPE & BLIND RAMS, FLOOR VALVES, IBOP, HCR VALVE, KILL LINE VALVES, TEST BOPS, CHOKE MANIFOLD TO 250 PSI LOW / 5 MIN - 5000 PSI HIGH / 10 MIN, HOLD ACCUMULATOR FUNCTION TEST, & TEST SURFACE CASING 1500 PSI FOR 30 2:00 - 2:30 0.50 **CSGSUR** 14 В 2486 SET WEAR BUSHING 2:30 - 3:00 Ρ 0.50 **CSGSUR** 07 2486 RIG SERVICE 3:00 - 4:30 1.50 **CSGSUR** Р 2486 06 Α HELD PJSM WITH RIG CREW AND TOTAL, PICKED UP THE MM55M BIT, HUNTING MUD MOTOR AND DIRECTIONAL BHA SCRIBED THE ASSEMBLY.(SURFACE TEST MUD MOTOR GOOD) 4:30 - 6:00 1.50 **CSGSUR** 06 Р 2486 TRIP IN 9 STANDS OF HWDP SET THE HYDRAULIC SLIPS IN PLACE 6:00 **DRLPRC** 2486 - 7:30 1.50 02 DRILL CEMENT AND SHOE TRACK, (FLOAT @ 2417' SHOE @ 2463') 7:30 - 16:00 8.50 DRLPRC Р 2486 02 D DIRECTIONAL DRILL F/ 2,486' - 4042' (1,556' / 6.2 HRS @ 250.9'/FPH) TOTAL BIT HRS. 6.2 WEIGHT ON BIT = 18/20 K STROKES PER MINUTE - 158 GALLONS PER MINUTE = 600 MUD MOTOR RPM =96 TOP DRIVE RPM = 50 TOTAL RPM = 146 FT/LBS TORQUE = 8.5 - 10.6K STPP = 2425 OFF BOTTOM = 2000 STRING WEIGHT UP/DOWN/ROTATING = 130 / 112 / 116 BIT POSISTION: 7.86' Low / .88' Left Slide 243' @ 16.16% Depth/24.53% Time = 1.59 Hrs - Rot 1,261 ' @ 83.84% Depth/ 75.47% Time MUD WEIGHT = 8.5 PPG VISCOSITY = 27 SECONDS HOLE IN GOOD CONDITION ZECO - DEWATERING CENTRIFUGE - RUNNING DE-SANDER - RUNNING DRILLING WITH GYPSUM SYSTEM MIXING HIGH

1/6/2016 9:48:29AM 7

Ρ

4042

16:00

- 16:30

0.50

DRLPRC

07

Α

RECEIVED: Jan. 06, 2016

VISCOSITY SWEEPS WITH CALCARB

LUBRICATE RIG AND TOP DRIVE

1/6/2016 9:48:29AM 8

RECEIVED: Jan. 06, 2016

VISCOSITY SWEEPS WITH CALCARB

Sundry Number: 68916 API Well Number: 43047552660000 **US ROCKIES REGION Operation Summary Report** Well: NBU 1022-9J1CS BLACK Spud date: 6/24/2015 Project: UTAH-UINTAH Site: NBU 1022-9J PAD Rig name no.: PROPETRO 12/12, ENSIGN 145/145 **Event: DRILLING** End date: 9/26/2015 Start date: 6/24/2015 UWI: NW/SE/0/10/S/22/E/9/0/0/26/PM/S/1913/E/0/1793/0/0 Active datum: RKB @5,221.00usft (above Mean Sea Date P/U Time Duration Phase Code MD from Operation Sub Start-End (hr) Code (usft) 2:30 - 16:00 13.50 DRLPRO 02 Ρ 5744 В VERTICAL DRILL F/ 5744' -7446' (1702' / 10.4 HRS @ 163.6'/FPH) TOTAL BIT HRS. 24.5 WEIGHT ON BIT = 18/20 K STROKES PER MINUTE - 158 GALLONS PER MINUTE = 600 MUD MOTOR RPM =96 TOP DRIVE RPM = 50 TOTAL RPM = 146 FT/LBS TORQUE = 9.5 - 11.8K STPP = 2750 OFF BOTTOM = 2497 STRING WEIGHT UP/DOWN/ROTATING = 195 / 141 / BIT POSISTION: 14.51' North/ 10.57' East Slide 87' @ 5.11% Depth/10.9% Time = 1.46 Hrs -Rot 1616 '@ 94.89% Depth/ 68.87% Time = 9.26Hrs MUD WEIGHT = 8.9 PPG VISCOSITY = 27 SECONDS HOLE IN GOOD CONDITION ZECO - DEWATERING CENTRIFUGE - RUNNING DE-SANDER - RUNNING DRILLING WITH GYPSUM SYSTEM MIXING HIGH VISCOSITY SWEEPS WITH CALCARB 7350' HAD A 25'FLARE ON BOTTOMS UP 2-10' FLARE WHILE DRILLING 16:00 - 16:30 0.50 **DRLPRO** 7446 07 RIG SERVICE 16:30 - 23:00 6.50 **DRLPRO** В Ρ 7446 02 VERTICAL DRILL F/ 7446' - 8110' (664' / 5.3 HRS @ 163.6'/FPH) TOTAL BIT HRS. 29.8 WEIGHT ON BIT = 18/20 K STROKES PER MINUTE - 158 GALLONS PER MINUTE = 600 MUD MOTOR RPM =96 TOP DRIVE RPM = 40/50 TOTAL RPM = 146 FT/LBS TORQUE = 9.5 - 11.8K STPP = 3133 OFF BOTTOM = 2800 STRING WEIGHT UP/DOWN/ROTATING = 202 / 143 / BIT POSISTION: 10.79' North/ 14.13' East Slide 73' @ 11.03% Depth/18.81% Time = .34 Hrs -Rot 354 ' @ 88.97% Depth/ 81.19% Time = 5.9Hrs MUD WEIGHT = 9.0 PPG VISCOSITY = 27 SECONDS HOLE IN GOOD CONDITION ZECO - CENTRIFUGE -RUNNING DE-SANDER - MIXING HIGH VISCOSITY SWEEPS WITH CALCARB INTERMITTENT 2-15' FLARES WHILE DRILLING AND 10-15' ON BOTTOMS UP 23:00 - 0:00 1.00 **DRLPRO** 05 G 8110 STOPPED @ 8110' TO DISPLACE THE ACTIVE SYSTEM WITH 11.4# MUD 8093' TVD

1/6/2016 9:48:29AM 9

Sundry Number: 68916 API Well Number: 43047552660000 **US ROCKIES REGION Operation Summary Report** Well: NBU 1022-9J1CS BLACK Spud date: 6/24/2015 Project: UTAH-UINTAH Site: NBU 1022-9J PAD Rig name no.: PROPETRO 12/12, ENSIGN 145/145 **Event: DRILLING** End date: 9/26/2015 Start date: 6/24/2015 UWI: NW/SE/0/10/S/22/E/9/0/0/26/PM/S/1913/E/0/1793/0/0 Active datum: RKB @5,221.00usft (above Mean Sea P/U Date Phase Time Duration Code Sub MD from Operation Start-End (hr) Code (usft) 9/25/2015 0:00 - 0:30 0.50 **DRLPRO** 05 Ρ 8110 G FINISHED DISPLACING THE ACTIVE SYSTEM W/ 11.4# MUD 0:30 - 12:00 11.50 DRLPRO 02 В Ρ 8110 VERTICAL DRILL F/ 8110' - 8,902' (792' / 9.1 HRS @ 87'/FPH) TOTAL BIT HRS. 38.9 WEIGHT ON BIT = 18/23 K STROKES PER MINUTE - 136 GALLONS PER MINUTE =520 MUD MOTOR RPM =83 TOP DRIVE RPM = 40/50 TOTAL RPM = 133 FT/LBS TORQUE = 10800 - 14900K STPP = 3412 OFF BOTTOM = 3158 STRING WEIGHT UP/DOWN/ROTATING = 202 / 143 / 162 BIT POSISTION: 5.42' North/ 36.89' East Slide 0.0' @ 0.0% Depth/0.0% Time = 0.0Hrs - Rot 792' @ 100% Depth/ 100% Time = 3.9Hrs/ Bit Hrs =38.9 / D&C Hrs = 5.75 MUD WEIGHT = 11.9 PPG VISCOSITY = 40 **SECONDS** HOLE IN GOOD CONDITION ZECO - CENTRIFUGE -DOWN DE-SANDER - CLEANING SAND TRAPS 12:00 - 13:00 1.00 **CSGPRO** 05 С 8902 PUMP 2 - 30BBL SWEEPS, FOLLOWED BY 2 **BOTTOMS UP** 13:00 - 13:30 0.50 Р 8902 **CSGPRO** 05 FLOW CHECK, "NO FLOW" 13:30 - 14:00 0.50 **CSGPRO** С Ρ 8902 05 CIRCULATE BOTTOMS UP TO MONITOR GAS AND VERIFY SAFE TRIP MARGIN WITH 11.9PPG MUD WEIGHT, NO GAS ON BOTTOMS UP 14:00 - 22:30 Ρ 8902 8.50 **CSGPRO** 06 Α TRIPPED OUT OF THE HOLE TO RUN PRODUCTION TIGHT SPOTS @ 5711, 5080', 4942', 4244', 3918',

1/6/2016 9:48:29AM 10

22:30 - 23:30

23:30 - 0:00

0:00 - 1:00

9/26/2015

1.00

0.50

1.00

CSGPRO

CSGPRO

CSGPRO

06

14

12

Α

В

Ρ

Ρ

Р

8902

8902

8902

LAID DOWN THE DIRECTIONAL BHA, MUD MOTOR

SAFETY MEETING AND RIG UP FRANKS CASING

AND PULLED THE MWD TOOL

PULLED THE WEAR BUSHING

CREW

Sundry Number: 68916 API Well Number: 43047552660000 **US ROCKIES REGION Operation Summary Report** Well: NBU 1022-9J1CS BLACK Spud date: 6/24/2015 Project: UTAH-UINTAH Site: NBU 1022-9J PAD Rig name no.: PROPETRO 12/12, ENSIGN 145/145 **Event: DRILLING** End date: 9/26/2015 Start date: 6/24/2015 UWI: NW/SE/0/10/S/22/E/9/0/0/26/PM/S/1913/E/0/1793/0/0 Active datum: RKB @5,221.00usft (above Mean Sea Date P/U Time Duration Phase Code Sub MD from Operation Start-End (hr) Code (usft) 1:00 - 12:30 11.50 **CSGPRO** 12 Ρ 8902 С SAFETY MEETING AND RUN CASING RAN A TOTAL OF 205 JTS OF CASING = (87 JTS. 4.5" / 11.6# / I-80 / LTC+ 2 MARKER JOINTS) + (115 JTS OF 4.5" / 11.6# / I-80 / DQX CASING + 1 CROSS OVER) LANDED @ 8889.68', SHOE @ 8888.18', FLOAT COLLAR @ 8842.38', MV MARKER @ 6790.68', PUP JT. @ 5002.78', CROSS OVER @ 4981.15 BRIDGE @ 3,777' AND HAD TO WASH LAST 2 JOINTS TO BOTTOM. LOTS OF CUTTING ON THE SHAKERS JTS. LEFT OUT 3-4.5" LTC 3-4.5" DQX 1- DQX CROSS OVER 12:30 - 13:30 1.00 **CSGPRO** 05 D Р 8902 CIRCULATE BOTTOMS UP, WHILE STAGING IN SCHLUMBERGER CEMENT TRUCKS 13:30 - 14:00 0.50 **CSGPRO** Р 8902 PJSM, RIG UP SCHLUMBERGER CEMENT EQUIPMENT 12 В 14:00 - 17:00 3.00 **CSGPRO** 12 Ε Ρ 8902 PRESSURE TEST TO 5000 PSI. PUMP 30 BBL. CHEMICAL WASH, . DROPPED THE BOTTOM PLUG AND PUMPED 175 BBLS (725 SX) OF CLASS G LEAD CEMENT, 12.8 PPG 1.36 YLD, 53.01 #/SK D035 + 0.10% BWOC D208 + 0.2% BWOC D065 +.20 % BWOC D046 + .25 #/SK D029 + 0.50% BWOC D079 + 0.49 % BWOC D800, 6.298 GL./SK FRESH WATER . FOLLOWED BY 258BBLS (1073 SX) OF 14.5#, 1.34 YLD. CLASS G POZ TAIL CEMENT + 35.01#/SK D035 + 20.10% BWOC D066 +0.05% BWOC D208 + 0.18 % BWOC D800 + 0.20 % BWOC D046 + 0.30 % BWOC B477 + 5.585 GL/SK FRESH WATER . SHUT DOWN AND DROP PLUG AND DISPLACE W/ 137.4 BBLS OF FRESH WATER. FULL RETURNS WITH 15 BBLS OF CEMENT RETURNED TO SURFACE. LIFT PSI OF 2640 / 3342 BUMP PLUG PSI. . PRESSURE HELD 5 MINS. FLOAT HELD. FLOW BACK 1.5 BBLS. EST. TOC FOR LEAD 13', EST TOC OF TAIL CEMENT 3834'. RIG DOWN CEMENTERS 17:00 - 17:30 0.50 **CSGPRO** 12 В Ρ 8902 PJSM, RIG DOWN SCHLUMBERGER CEMENTING **EQUIPMENT** 17:30 - 19:30 2.00 **CSGPRO** 21 Ε Ζ 8902 CAMERON WAS CALLED @ 14:00 HOURS WITH A 3 HOUR CALLOUT TO SET A PACK OFF. THE DISPATCH FORGOT TO CALL THE TECH UNTIL THEY WERE CALLED AGAIN TO CHECK ON THE HAND SINCE HE HAD NOT ARRIVED. WE CUT AND SLIPPED DRILLING LINE WHILE WAITING FOR THE FIELD TECH TO ARRIVE 19:30 - 20:00 0.50 **CSGPRO** Р 8902 В SET THE PACK OFF WITH CAMERON PERSONNEL RIG RELEASED @ 20:00 9/26/2015

1/6/2016 9:48:29AM 11

ANADARKO PETROLEUM CORP

UINTAH COUNTY, UTAH (NAD 27) NW SE SEC. 9 T10S R22E (NBU 1022-9J PAD) NBU 1022-9J1CS PRODUCTION - JOB #2015-113-145

26 September, 2015

Survey: FINAL SURVEYS





Project: UINTAH COUNTY, UTAH (NAD 27)

Site: NW SE SEC. 9 T10S R22E (NBU 1022-9J PAD)

Well: NBU 1022-9J1CS

Wellbore: PRODUCTION - JOB #2015-113-145


Design: FINAL SURVEYS





121.6 TIE ON TO SURFACE SURVEYS


460.8 LAST SURVEY - SEP 26, 2015

462.8 EXTRAPOLATION TO TD











Inc Azi 4.75 359.90 2.11 104.52

2416.7 2421.0





ANNOTATIONS

94.1 366.7 VSecDeparture Annotation

Survey Report



Company: ANADARKO PETROLEUM CORP Project: UINTAH COUNTY, UTAH (NAD 27) Site: NW SE SEC. 9 T10S R22E (NBU 102

Well-NBU 1022-9J1CS

Wellbore: PRODUCTION - JOB #2015-113-145 Design:

FINAL SURVEYS

Local Co-ordinate Reference:

TVD Reference: **MD Reference:** North Reference:

Survey Calculation Method:

Database:

Well NBU 1022-9J1CS

13ft RKB @ 5221.0usft (ENS 145) 13ft RKB @ 5221.0usft (ENS 145)

True

Minimum Curvature EDM 5000.1 Single User Db

Project UINTAH COUNTY, UTAH (NAD 27)

Map System: Universal Transverse Mercator (US Survey Fee System Datum:

NAD 1927 (NADCON CONUS)

Zone 12N (114 W to 108 W)

Mean Sea Level

Using geodetic scale factor

Site NW SE SEC. 9 T10S R22E (NBU 1022-9J PAD)

Northing: 14,515,856.74 usft Site Position: Latitude: 39° 57' 41.538 N Lat/Long Easting: 109° 26' 27.849 W From: 2,077,262.59 usft Longitude: 0.0 usft Slot Radius: 13-3/16' 1.00° **Position Uncertainty:** Grid Convergence:

NBU 1022-9J1CS Well

Well Position +N/-S 0.0 usft 14,515,856.74 usft Latitude: 39° 57' 41.538 N Northing:

+E/-W 0.0 usft Easting: 2,077,262.59 usft Longitude: 109° 26' 27.849 W

Wellhead Elevation: **Position Uncertainty** 0.0 usft **Ground Level:** usft 5,208.0 usft

PRODUCTION - JOB #2015-113-145

Declination **Magnetics Dip Angle** Field Strength **Model Name Sample Date** (°) (°) (nT) IGRF2015 21/09/2015 10.56 65.73 51,789

Design FINAL SURVEYS

Audit Notes:

Wellbore

Geo Datum:

Map Zone:

Version: 1.0 Phase: **ACTUAL** Tie On Depth: 0.0

Vertical Section: Depth From (TVD) +N/-S +E/-W Direction (usft) (usft) (usft) (°) 0.0 0.0 0.0 356.51

Date 26/09/2015 **Survey Program**

> From To

(usft) (usft) Survey (Wellbore) **Tool Name** Description

8,902.0 FINAL SURVEYS (PRODUCTION - JOB # MWD 145.0 MWD - Standard

Survey Vertical Build Measured Vertical Dogleg Turn Subsea Depth Depth +N/-S Section Rate Rate Rate Inclination **Azimuth** Depth +E/-W (usft) (usft) (usft) (°/100usft) (°/100usft) (°/100usft) (usft) (usft) (usft) (°) (°) 0.00 0.0 0.00 0.0 5,221.0 0.0 0.0 0.0 0.00 0.00 0.00 0.33 145.0 5,076.0 0.2 0.3 0.23 0.00 145.0 30.10 0.4 0.23 0.34 4,986.0 8.0 0.5 0.7 235.0 43.57 235.0 0.09 0.01 14.97 4,886.0 335.0 0.26 49.48 335.0 1.1 0.9 1.1 0.09 -0.08 5.91 425.0 0.35 83.41 425.0 4,796.0 1.3 1.3 1.2 0.22 37.70 0.10 0.06 515.0 0.40 64.48 515.0 4,706.0 1.5 1.9 1.4 0.15 -21.03 605.0 0.70 30.05 605.0 -38.26 4.616.0 2.1 2.4 1.9 0.48 0.33 695.0 0.91 24.96 695.0 4,526.0 3.2 3.0 3.0 0.25 0.23 -5.66 785.0 348.58 785.0 4.7 4.5 -40.42 4,436.0 3.1 0.74 0.23 1.12 875.0 2.15 320.97 874.9 4,346.1 6.9 1.9 6.8 1.41 1.14 -30.68 965.0 3.82 317.86 964.8 4,256.2 10.4 -1.2 10.5 1.86 1.86 -3.46 -6.0 1,055.0 5.21 315.32 1,054.5 4,166.5 15.6 15.9 1.56 1.54 -2.824,076.8 -11.8 1,145.0 5.14 313.77 1,144.2 21.2 21.9 0.17 -0.08 -1.72

Survey Report



Company: Project: Site: Well: ANADARKO PETROLEUM CORP UINTAH COUNTY, UTAH (NAD 27) NW SE SEC. 9 T10S R22E (NBU 102

NBU 1022-9J1CS

Wellbore: PRODUCTION - JOB #2015-113-145

Design: FINAL SURVEYS

Local Co-ordinate Reference:

TVD Reference: MD Reference: North Reference:

Survey Calculation Method:

Database:

Well NBU 1022-9J1CS

13ft RKB @ 5221.0usft (ENS 145) 13ft RKB @ 5221.0usft (ENS 145)

True

Minimum Curvature

EDM 5000.1 Single User Db

Survey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	Subsea Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
1,235.0	4.83	308.73	1,233.8	3,987.2	26.4	-17.7	27.4	0.60	-0.34	-5.60
1,325.0	4.77	306.76	1,323.5	3,897.5	31.0	-23.7	32.4	0.19	-0.07	-2.19
1,415.0	4.89	303.92	1,413.2	3,807.8	35.4	-29.8	37.1	0.30	0.13	-3.16
1,505.0	4.67	296.28	1,502.9	3,718.1	39.2	-36.3	41.3	0.75	-0.24	-8.49
1,595.0	4.23	298.75	1,592.6	3,628.4	42.4	-42.5	44.9	0.53	-0.49	2.74
1,685.0	4.15	320.41	1,682.4	3,538.6	46.5	-47.5	49.3	1.75	-0.09	24.07
1,775.0	3.20	343.51	1,772.2	3,448.8	51.4	-50.3	54.4	1.93	-1.06	25.67
1,865.0	3.08	13.68	1,862.1	3,358.9	56.2	-50.4	59.1	1.82	-0.13	33.52
1,955.0	3.67	15.69	1,951.9	3,269.1	61.3	-49.1	64.2	0.67	0.66	2.23
2,045.0	4.35	1.82	2,041.7	3,179.3	67.5	-48.2	70.3	1.31	0.76	-15.41
2,135.0	4.18	357.25	2,131.4	3,089.6	74.2	-48.2	77.0	0.42	-0.19	-5.08
2,225.0	3.60	355.68	2,221.2	2,999.8	80.3	-48.6	83.1	0.66	-0.64	-1.74
2,315.0	3.82	359.24	2,311.0	2,910.0	86.1	-48.8	88.9	0.35	0.24	3.96
2,412.0	4.75	359.90	2,407.8	2,813.2	93.3	-48.9	96.1	0.96	0.96	0.68
	TO SURFAC									
2,421.0 2,478.0 2,573.0	4.75 5.01 3.91	359.90 1.33 355.18	2,416.7 2,473.5 2,568.2	2,804.3 2,747.5 2,652.8	94.1 98.9 106.3	-48.9 -48.8 -49.0	96.9 101.7 109.1	0.00 0.50 1.26	0.00 0.46 -1.16	0.00 2.51 -6.47
2,668.0	3.82	9.07	2,663.0	2,558.0	112.6	-48.8	115.4	0.99	-0.09	14.62
2,762.0	4.57	5.29	2,756.8	2,464.2	119.5	-48.0	122.2	0.85	0.80	-4.02
2,857.0	3.87	0.72	2,851.5	2,369.5	126.4	-47.6	129.1	0.82	-0.74	-4.81
2,951.0	5.10	0.80	2,945.2	2,275.8	133.8	-47.5	136.4	1.31	1.31	0.09
3,046.0	4.57	354.21	3,039.9	2,181.1	141.8	-47.8	144.4	0.81	-0.56	-6.94
3,140.0	4.17	355.44	3,133.6	2,087.4	148.9	-48.4	151.6	0.44	-0.43	1.31
3,235.0	4.48	2.56	3,228.3	1,992.7	156.1	-48.5	158.7	0.65	0.33	7.49
3,329.0	5.14	6.78	3,322.0	1,899.0	163.9	-47.9	166.5	0.80	0.70	4.49
3,423.0	4.44	4.58	3,415.7	1,805.3	171.7	-47.1	174.3	0.77	-0.74	-2.34
3,518.0	5.19	12.23	3,510.3	1,710.7	179.6	-45.9	182.0	1.04	0.79	8.05
3,613.0	3.96	10.47	3,605.0	1,616.0	187.0	-44.4	189.4	1.30	-1.29	-1.85
3,707.0	4.00	7.40	3,698.8	1,522.2	193.4	-43.4	195.7	0.23	0.04	-3.27
3,802.0	4.13	18.65	3,793.6	1,427.4	200.0	-41.9	202.1	0.85	0.14	11.84
3,896.0	4.97	8.10	3,887.3	1,333.7	207.2	-40.2	209.3	1.26	0.89	-11.22
3,991.0	6.20	11.35	3,981.8	1,239.2	216.3	-38.6	218.3	1.34	1.29	3.42
4,085.0	5.63	11.00	4,075.3	1,145.7	225.8	-36.7	227.6	0.61	-0.61	-0.37
4,180.0	4.22	8.80	4,170.0	1,051.0	233.8	-35.3	235.6	1.50	-1.48	-2.32
4,274.0	5.05	14.60	4,263.7	957.3	241.3	-33.7	242.9	1.01	0.88	6.17
4,369.0	6.33	11.26	4,358.2	862.8	250.4	-31.7	251.9	1.39	1.35	-3.52
4,463.0	5.80	11.53	4,451.7	769.3	260.2	-29.7	261.5	0.56	-0.56	0.29
4,558.0	5.23	12.76	4,546.2	674.8	269.1	-27.8	270.3	0.61	-0.60	1.29
4,652.0	4.61	14.34	4,639.9	581.1	276.9	-25.9	278.0	0.68	-0.66	1.68
4,747.0	5.23	5.99	4,734.5	486.5	285.0	-24.5	285.9	1.00	0.65	-8.79
4,841.0	4.61	7.31	4,828.2	392.8	293.0	-23.6	293.9	0.67	-0.66	1.40
4,936.0	6.81	10.21	4,922.7	298.3	302.3	-22.1	303.1	2.33	2.32	3.05
5,030.0	6.37	12.05	5,016.1	204.9	312.9	-20.0	313.5	0.52	-0.47	1.96
5,125.0	5.36	11.09	5,110.6	110.4	322.4	-18.1	322.9	1.07	-1.06	-1.01
5,219.0	4.22	359.20	5,204.3	16.7	330.2	-17.3	330.6	1.60	-1.21	-12.65
5,314.0	4.97	358.08	5,299.0	-78.0	337.8	-17.5	338.2	0.80	0.79	-1.18
5,409.0	4.57	0.80	5,393.6	-172.6	345.7	-17.5	346.1	0.48	-0.42	2.86
5,503.0	3.82	0.01	5,487.4	-266.4	352.5	-17.5	352.9	0.80	-0.80	-0.84
5,598.0	3.16	7.31	5,582.2	-361.2	358.3	-17.2	358.7	0.84	-0.69	7.68
5,692.0	3.03	334.79	5,676.1	-455.1	363.1	-17.9	363.5	1.85	-0.14	-34.60
5,787.0	2.81	331.45	5,770.9	-549.9	367.4	-20.1	368.0	0.29	-0.23	-3.52
5,882.0	2.15	337.86	5,865.9	-644.9	371.1	-21.8	371.8	0.75	-0.69	6.75

Survey Report



Company: Project: Site: Well:

ANADARKO PETROLEUM CORP UINTAH COUNTY, UTAH (NAD 27) NW SE SEC. 9 T10S R22E (NBU 102

NBU 1022-9J1CS

Wellbore: PRODUCTION - JOB #2015-113-145

FINAL SURVEYS Design:

Local Co-ordinate Reference:

TVD Reference: MD Reference: North Reference:

Survey Calculation Method:

Database:

Well NBU 1022-9J1CS

13ft RKB @ 5221.0usft (ENS 145) 13ft RKB @ 5221.0usft (ENS 145)

True

Minimum Curvature

EDM 5000.1 Single User Db

urvey										
Measured Depth (usft)	Inclination (°)	Azimuth (°)	Vertical Depth (usft)	Subsea Depth (usft)	+N/-S (usft)	+E/-W (usft)	Vertical Section (usft)	Dogleg Rate (°/100usft)	Build Rate (°/100usft)	Turn Rate (°/100usft)
5,976.0	2.02	341.73	5,959.8	-738.8	374.3	-23.0	375.0	0.20	-0.14	4.12
6,071.0	1.71	347.97	6,054.7	-833.7	377.3	-23.9	378.1	0.39	-0.33	6.57
6,165.0	1.10	7.13	6,148.7	-927.7	379.6	-24.0	380.3	0.81	-0.65	20.38
6,260.0	0.88	26.82	6,243.7	-1,022.7	381.1	-23.6	381.9	0.42	-0.23	20.73
6,355.0	0.70	47.91	6,338.7	-1,117.7	382.2	-22.8	382.9	0.36	-0.19	22.20
6,449.0	1.05	38.95	6,432.7	-1,211.7	383.2	-21.9	383.8	0.40	0.37	-9.53
6,544.0	0.53	93.53	6,527.7	-1,306.7	383.9	-20.9	384.4	0.90	-0.55	57.45
6,638.0	0.66	88.17	6,621.7	-1,400.7	383.9	-19.9	384.4	0.15	0.14	-5.70
6,733.0	0.44	113.48	6,716.7	-1,495.7	383.7	-19.0	384.2	0.34	-0.23	26.64
6,827.0	0.70	127.81	6,810.7	-1,589.7	383.2	-18.2	383.6	0.31	0.28	15.24
6,922.0	0.48	123.85	6,905.7	-1,684.7	382.7	-17.4	383.0	0.24	-0.23	-4.17
7,017.0	0.62	125.78	7,000.6	-1,779.6	382.1	-16.7	382.5	0.15	0.15	2.03
7,111.0	1.27	142.92	7,094.6	-1,873.6	381.0	-15.7	381.3	0.75	0.69	18.23
7,206.0	1.27	144.42	7,189.6	-1,968.6	379.3	-14.4	379.5	0.03	0.00	1.58
7,300.0	1.54	138.97	7,283.6	-2,062.6	377.5	-13.0	377.6	0.32	0.29	-5.80
7,395.0	1.67	149.25	7,378.5	-2,157.5	375.4	-11.4	375.4	0.33	0.14	10.82
7,489.0	1.10	152.42	7,472.5	-2,251.5	373.4	-10.3	373.3	0.61	-0.61	3.37
7,584.0	0.57	111.19	7,567.5	-2,346.5	372.4	-9.4	372.3	0.81	-0.56	-43.40
7,678.0	1.49	128.95	7,661.5	-2,440.5	371.5	-8.1	371.3	1.02	0.98	18.89
7,773.0	0.48	180.19	7,756.5	-2,535.5	370.3	-7.1	370.0	1.31	-1.06	53.94
7,867.0	1.01	168.85	7,850.5	-2,629.5	369.1	-6.9	368.8	0.58	0.56	-12.06
7,962.0	0.57	132.02	7,945.5	-2,724.5	368.0	-6.4	367.7	0.68	-0.46	-38.77
8,057.0	0.92	121.39	8,040.5	-2,819.5	367.2	-5.4	366.9	0.39	0.37	-11.19
8,151.0	0.97	110.14	8,134.4	-2,913.4	366.6	-4.0	366.1	0.20	0.05	-11.97
8,246.0	1.23	95.02	8,229.4	-3,008.4	366.2	-2.3	365.7	0.41	0.27	-15.92
8,340.0	1.27	85.88	8,323.4	-3,102.4	366.2	-0.2	365.5	0.22	0.04	-9.72
8,435.0	1.14	78.41	8,418.4	-3,197.4	366.5	1.8	365.7	0.21	-0.14	-7.86
8,529.0	1.23	78.24	8,512.4	-3,291.4	366.9	3.7	366.0	0.10	0.10	-0.18
8,624.0	1.63	82.28	8,607.3	-3,386.3	367.2	6.0	366.2	0.43	0.42	4.25
8,713.0	1.76	93.73	8,696.3	-3,475.3	367.3	8.6	366.1	0.41	0.15	12.87
8,802.0	2.02	98.71	8,785.2	-3,564.2	367.0	11.5	365.6	0.35	0.29	5.60
	SURVEY - SEI									
8,849.0	2.11	104.52	8,832.2	-3,611.2	366.7	13.2	365.2	0.48	0.19	12.36
	APOLATION T	-								
8,902.0	2.11	104.52	8,885.2	-3,664.2	366.2	15.1	364.6	0.00	0.00	0.00

Survey Report



Company: ANADARKO PETROLEUM CORP
Project: UINTAH COUNTY, UTAH (NAD 27)
Site: NW SE SEC. 9 T10S R22E (NBU 102
Well: NBU 1022-9J1CS
Wellbore: PRODUCTION - JOB #2015-113-145

Wellbore: PRODUCTION - JOB #2015-113-145
Design: FINAL SURVEYS

Local Co-ordinate Reference: TVD Reference: MD Reference: North Reference:

Survey Calculation Method: Database: Well NBU 1022-9J1CS

13ft RKB @ 5221.0usft (ENS 145) 13ft RKB @ 5221.0usft (ENS 145)

True

Minimum Curvature EDM 5000.1 Single User Db

Targets									
Target Name - hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (usft)	+N/-S (usft)	+E/-W (usft)	Northing (usft)	Easting (usft)	Latitude	Longitude
NBU 205 (ABDN) - survey misses to Circle (radius 30		0.00 by 307.0usft	7,263.0 at 7285.3u	70.8 sft MD (7268		14,515,927.28 77.8 N, -13.2 E)	2,077,246.25	39° 57′ 42.238 N	109° 26' 28.043 W
BHL - NBU 1022-9J1 - survey misses to - Circle (radius 25	arget center b	0.00 by 37.3usft a	8,880.0 at 8895.6us	360.1 ft MD (8878.	-22.0 7 TVD, 366	14,516,216.38 6.2 N, 14.8 E)	2,077,234.34	39° 57' 45.097 N	109° 26' 28.131 W

Survey Ann	otations				
	Measured Depth	Vertical Depth	Local Coor		
	(usft)	(usft)	+N/-S (usft)	+E/-W (usft)	Comment
	2,421.0	2,416.7	94.1	-48.9	TIE ON TO SURFACE SURVEYS
	8,849.0	8,832.2	366.7	13.2	LAST SURVEY - SEP 26, 2015
	8,902.0	8,885.2	366.2	15.1	EXTRAPOLATION TO TD

Checked By:	Approved By:	Date:
Checked by.	Approved by.	Date.

				U	S ROC	KIES RI	EGION	
				Opera	tion S	Summa	ary Report	
Well: NBU 1022	-9J1CS BLACK						Spud date: 6/2	4/2015
Project: UTAH-U	IINTAH		Site: NBU	J 1022-9J	PAD			Rig name no.:
Event: COMPLE	TION		Start date	e: 11/9/20	15			End date: 12/9/2015
Active datum: RI	KB @5,221.00usft (al	bove Mean Sea	a	UWI: NV	N/SE/0/1	0/S/22/E/	9/0/0/26/PM/S/19	013/E/0/1793/0/0
Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD from (usft)	Operation
10/3/2015	-							
10/27/2015	0:00 -		SUBSPR	52	Α	Р		HSM, 150 PSI ON SURFACE CSG, BLEED OFF, FILL SURFACE & 4 1/2" CSG W/ BRINE MIRU CAMERON TEST TRUCK
								PRESSURE TEST CSG & FRAC VALVES TO 7053 PSI, LOST 46 PSI IN 15 MIN, NO COMMUNICATION OR MIGRATION WITH SURFACE CSG, BLEED OFF PSI. TEST SURFACE CSG TO 534 PSI, LOST 95 PSI IN 5
								MIN. RDMO CAMERON
11/13/2015	14:00 - 16:00	2.00	FRAC	37	E	P		RU WL PERFED 1ST STAGE AS DESIGNED
11/14/2015	0:00 - 0:00	24.00	FRAC	36	Н	P		FRAC & PERF 24 HR OPERATIONS
11/15/2015	0:00 - 0:00	24.00	FRAC	36	Н	Р		FRAC STAGE # 1) WHP 1580 PSI, BRK 3375 PSI @ 2.9 BPM. ISIP 2719 PSI, FG. 0.74 ISIP 2724 PSI, FG. 0.75, NPI 5 PSI.
								SET HAL 8K CBP & PERF STG # 2 AS PER DESIGN
11/16/2015	0:00 - 0:00	24.00	FRAC	36	Н	Р		FRAC STAGE 2) WHP 1820 PSI, BRK 4623 PSI @ 3.5 BPM. ISIP 2676 PSI, FG. 0.76 ISIP 2930 PSI, FG. ,79, NPI 254 PSI.
								SET HAL 8K CBP & PERF STG # 3 AS PER DESIGN
11/17/2015	0:00 - 0:00	24.00	FRAC	36	Н	Р		FRAC STAGE # 3) BEGIN FRACING
11/18/2015	0:00 - 0:00	24.00	FRAC	36	Н	Р		FRAC STAGE #3) WHP 2188 PSI, BRK 4518 PSI @ 3 BPM. ISIP 2715 PSI, FG. 0.77 ISIP 3218 PSI, FG. 0.84, NPI 503 PSI.
								SET KILL PLUG RD FRAC AND WL COMPANIES SWI FLUID PUMPED: 56,312
								TOTAL SAND: 115,090
12/8/2015	7:00 - 7:30	0.50	DRLOUT	48		Р		HSM, PICKING UP TBG W/ PIPE WRANGLER.
	7:30 - 15:00	7.50	DRLOUT	31	I	Р		6 OF 7, TALLY & PU 37/8 BIT POBS, 247 JTS 23/8 P-110, TAG UP @ 7895 ', RU DRLG EQUIP PREP TO D/O IN AM, SWI SDFN
12/9/2015	7:00 - 7:15	0.25	DRLOUT	48				HSM, MAKING SURE ALL LINE ARE CLEAR BEFORE DRILL OUT.

12/28/2015 1:08:02PM 1

Sundry Number: 68916 API Well Number: 43047552660000 **US ROCKIES REGION Operation Summary Report** Spud date: 6/24/2015 Well: NBU 1022-9J1CS BLACK Project: UTAH-UINTAH Site: NBU 1022-9J PAD Rig name no.: Event: COMPLETION End date: 12/9/2015 Start date: 11/9/2015 UWI: NW/SE/0/10/S/22/E/9/0/0/26/PM/S/1913/E/0/1793/0/0 Active datum: RKB @5,221.00usft (above Mean Sea Date P/U Phase Code Operation Time Duration Sub MD from Start-End Code (usft) (hr) 7:15 - 15:00 7.75 **DRLOUT** 31 6 OF 7, BROKE CIRC CONV, TEST BOPS TO 3,000 PSI, RIH. C/O 5' SAND TAG 1ST PLUG @ 7908' DRL PLG IN 5 MIN, 900 PSI INCREASE RIH. C/O 50' SAND TAG 2ND PLUG @ 8196' DRL PLG IN 5 MIN, 400 PSI INCREASE RIH. C/O 40' SAND TAG 3RD PLUG @ 8457' DRL PLG IN 5 MIN, 500 PSI INCREASE RIH. C/O TO 8829', CIRC CLN, RD SWIVEL, L/D 9JTS, LAND TBG, ND BOPS NU WH, TEST FL, PUMPED OFF BIT, TURN WELL TO FB CREW.RIGGED DWN MOVED OVER ON 7 OF 7, RIGGED UP, ND WH NU BOPS SWI SDFN. KB = 13' 41/16 HANGER = .83' 268 JTS 23/8 P-110 = 8545.50' POBS W/ 1.875 X/N = 2.20' EOT @ 8561.53' TWTR = 56,312 BBLS TWR = 1800 BBLS TWLTR = 54,512 BBLS 316 JT HAULED OUT, P-110. 268 LANDED

48 TO RETURN

12/28/2015 1:08:02PM 2

US ROCKIES REGION

General

1.1 Customer Information

Company	US ROCKIES REGION
Representative	
Address	

1.2 Well/Wellbore Information

Well	NBU 1022-9J1CS BLACK	Wellbore No.	НО
Well Name	NBU 1022-9J1CS	Wellbore Name	NBU 1022-9J1CS
Report no.	1	Report date	11/9/2015
Project	UTAH-UINTAH	Site	NBU 1022-9J PAD
Rig Name/No.		Event	COMPLETION
Start date	11/9/2015	End date	12/9/2015
Spud date	6/24/2015	Active datum	RKB @5,221.00usft (above Mean Sea Level)
UWI	NW/SE/0/10/S/22/E/9/0/0/26/PM/S/1913/E/0/1793/0/0		

1.3 General

Contractor	Job method	Supervisor	
Perforated Assembly	Conveyed method		

Summary

1.5

1.4 Initial Conditions

Fluid type	Fluid density	Gross Interval	7,958.0 (usft)-8,756.0 (usft Start Date/Time	Start Date/Time	11/9/2015 12:00AM
Surface press.	Estimate res press	No. of intervals	23	23 End Date/Time	11/9/2015 12:00AM
TVD fluid top	Fluid head	Total shots	72	72 Net perforation interval	24.00 (usft)
Hydrostatic press.	Press. difference	Avg. shot density	3.00 (shot/ft)	3.00 (shot/ft) Final surface pressure	
Balance Cond NEUTRAL				Final press. date	

! Intervals

2.1 Perforated Interval

Misrun How Guns	Conveyed		0		
Misrun					
Reason			19.00 PRODUCTION		
Charge	weight	(gram)	19.00		
Charge desc.	/Charge	manufacturer			
Phasing	©		120.00		
	size	(ii)	3.125		
Carr type /Stage No			.410 EXP/3		
Diameter	(ii)		0.410		
Misfires/	Add.	Shot			
Shot	density		3.00		
MD	pase	(nstt)	7,958.0 7,959.0		
MD	top	(nstt)	7,958.0		
CCL-TS	(nstt)				
@TOO	(nst)				
Formation/	Reservoir		MESAVE	RDE/	
Date			11/9/2015	12:00AM	

OpenWells

US ROCKIES REGION

Perforated Interval (Continued) 2.1

MES AVE FOLD 3004 0 340 0 4410 EXP3 3125 12000 FOLD EXP3 BLES AVE FOLD 3004 0 300 0 4410 EXP3 3125 12000 FOLD EXP3 BLES AVE FOLD 300 0 4410 EXP3 3125 12000 FOLD EXP3 BLES AVE FOLD EXP3 310 0 4410 EXP3 3125 12000 FOLD EXP3 BLES AVE FOLD EXP3 310 0 4410 EXP3 3125 12000 FOLD EXP3 BLES AVE FOLD EXP3 310 0 4410 EXP3 3125 12000 FOLD EXP3 BLES AVE FOLD EXP3 310 0 4410 EXP3 3125 12000 FOLD EXP3 BLES AVE FOLD EXP3 310 0 4410 EXP3 310 0 4410 EXP3 BLES AVE FOLD EXP3 BLES AVE	Date	Formation/ Reservoir	(nsft)	(nsft)	MD top (usft)	MD base (usft)	Shot N density (shot/ft)	Misfires/ Add. Shot	Diameter (in)	Carr type /Stage No	Carr size (in)	Phasing (°)	Charge desc. /Charge manufacturer	Charge weight (gram)	Reason	Misrun	How Guns Conveyed
RES AVE 8,00340 8,00440 3.00 0.410 EXP/3 3.125 120.00 RDE. MES AVE 8,06540 3.00 0.410 EXP/3 3.125 120.00 RDE. MES AVE 8,06540 3.00 0.410 EXP/3 3.125 120.00 RDE. AVE 8,1400 8111.0 3.00 0.410 EXP/3 3.125 120.00 RDE. AVE 8,1400 8,181.0 3.00 0.410 EXP/3 3.125 120.00 RDE. AVE 8,1400 8,181.0 3.00 0.410 EXP/3 3.125 120.00 RDE. AVE 8,1400 8,181.0 3.00 0.410 EXP/3 3.125 120.00 ME S AVE 8,222.0 8,220.0 3.00 0.410 EXP/2 3.125 120.00 RDE. ME S AVE 8,371.0 8,371.0 3.00 0.410 EXP/2 3.125 120.00 RDE. ME S AVE 8,371.0 8,371.0 3.00 0.410 EXP/2 3.125 120.00	11/9/2015 12:00AM	> A					3.00		0.410 E	XP/3	3.125	120.00		19.00 PF	RODUCTION		0
MES AVE 8,053.0 8,054.0 3.00 0.410 EXP/3 3,125 120.00 MES AVE 8,050.0 8,054.0 3.00 0.410 EXP/3 3,125 120.00 MES AVE 8,090.0 8,081.0 3.00 0.410 EXP/3 3,125 120.00 MES AVE 8,170.0 8,181.0 3.00 0.410 EXP/3 3,125 120.00 RDEAL 8,170.0 8,181.0 3.00 0.410 EXP/3 3,125 120.00 RDEAL 8,180.0 8,181.0 3.00 0.410 EXP/3 3,125 120.00 RDEAL 8,180.0 8,181.0 3.00 0.410 EXP/2 3,125 120.00 RDEAL 8,280.0 8,290.0 3.00 0.410 EXP/2 3,125 120.00 RDEAL 8,370.0 8,381.0 3.00 0.410 EXP/2 3,125 120.00 RDEAL 8,370.0 8,390.0 3.00 0.410 EXP/2 3,125 120.00 RDEAL 8,370.0 8,390.0 3.00 0.410 EXP/2 3,125 120.00 RDEAL 8,370.0 8,390.0 3.00 0.410 EXP/2 3,125 120.00 RDEAL 8,394.0 8,394.0 3.00 0.410 EXP/2 3,125 120.00 RDEAL 8,394.0 8,394.0 3.00 0.410 EXP/1 3,125 120.00 RDEAL 8,394.0 8,394.0 3.00 0.410 EX	11/9/2015 12:00AM	> A				8,004.0	3.00		0.410 E	XP/3	3.125	120.00		19.00 PF	RODUCTION		0
MESAVE 6.0801 8.0810 3.00 0.410 EXP/3 3.125 120.00 MESAVE 8.137.0 8.1380 3.00 0.410 EXP/3 3.125 120.00 MESAVE 8.1800 8.1811 0 3.00 0.410 EXP/3 3.125 120.00 MESAVE 8.1800 8.1810 3.00 0.410 EXP/3 3.125 120.00 MESAVE 8.2220 8.2230 3.00 0.410 EXP/2 3.125 120.00 MESAVE 8.3300 8.3400 0.410 EXP/2 3.125 120.00 MESAVE 8.3300 8.3400 0.410 EXP/2 3.125 120.00 MESAVE 8.3300 8.3400 0.410 EXP/1 3.125 120.00 MESAVE 8.3300 8.3410 3.00 0.410 EXP/1 3.125 120.00 MESAVE 8.3300 8.3410 3.00 0.410 EXP/1 3.125 120.00 MESAVE 8.3300 8.3410 3.00 0.410 EXP/1 3.125 120.00 MESAVE 8.3300 8.3300 0.410 EXP/1 3.125 120.00 MESAVE 8.3300 8.3410 3.00 0.410 EXP/1 3.125 120.00 MESAVE 8.3300 8.3410 3.00 0.410 EXP/1 3.125 120.00 MESAVE 8.3300 8.3410 3.00 0.410 EXP/1 3.125 120.00 MESAVE 8.3300 8.3300 0.410 EXP/1 3.125 120.00 MESAVE 8.3300	11/9/2015 12:00AM	> A				8,054.0	3.00		0.410 E	XP/3	3.125	120.00		19.00 PF	RODUCTION		0
MESAVE 8,1100 8,1110 3.00 0.410 EXP/3 3.125 120.00 POEM MESAVE 8,137.0 8,136.0 3.0410 EXP/3 3.125 120.00 MESAVE 8,137.0 8,137.0 0.410 EXP/3 3.125 120.00 MESAVE 8,222.0 8,222.0 3.00 0.410 EXP/2 3.125 120.00 MESAVE 8,236.0 8,297.0 3.00 0.410 EXP/2 3.125 120.00 RESAVE 8,336.0 8,297.0 3.00 0.410 EXP/2 3.125 120.00 RESAVE 8,336.0 8,340.0 3.00 0.410 EXP/2 3.125 120.00 MESAVE 8,336.0 8,340.0 3.00 0.410 EXP/2 3.125 120.00 MESAVE 8,336.0 8,440.0 3.00 0.410 EXP/2 3.125 120.00 MESAVE 8,440.0 8,336.0 3.00 0.410 EXP/2 3.125 120.00 MESAVE 8,620.0 8,630.0 3.00 0.410 EXP/2 3.125	11/9/2015 12:00AM	\ \ \				8,081.0	3.00		0.410 E	XP/3	3.125	120.00		19.00 PF	RODUCTION		0
MESAVE 8,1370 8,1380 3.00 0.410 EXP/3 3,125 12000 RDEAL RESAVE 8,1800 8,1810 3.00 0.410 EXP/3 3,125 12000 RDEAL RESAVE 8,2280 8,2230 3.00 0.410 EXP/2 3,125 120.00 RDEAL 8,2800 8,2310 3.00 0.410 EXP/2 3,125 120.00 RDEAL 8,3100 8,3110 3.00 0.410 EXP/2 3,125 120.00 RDEAL RESAVE 8,330 8,340 3.00 0.410 EXP/2 3,125 120.00 RDEAL RESAVE 8,330 8,340 3.00 0.410 EXP/2 3,125 120.00 RDEAL RESAVE 8,330 0.410 EXP/2 3,125 120.00 RDEAL RESAVE 8,340 3,360 0.410 EXP/2 3,125 120.00 RDEAL RESAVE 8,630 8,594 3,00 0.410 EXP/2 3,125 120.00 RDEAL RESAVE 8,630<	11/9/2015 12:00AM	A <				8,111.0	3.00		0.410 E	XP/3	3.125	120.00		19.00 PF	RODUCTION		0
MESAVE 8,180.0 8,181.0 3.00 0,410 EXP/2 3.125 120.00 RESAVE 8,222.0 8,223.0 3.00 0,410 EXP/2 3.125 120.00 RDE/A 8,296.0 8,297.0 3.00 0,410 EXP/2 3.125 120.00 RDE/A 8,390.0 8,371.0 3.00 0,410 EXP/2 3.125 120.00 RDE/A 8,391.0 8,371.0 3,372.0 0,410 EXP/2 3.125 120.00 RDE/A 8,394.0 8,394.0 3.00 0,410 EXP/2 3.125 120.00 RDE/A 8,394.0 8,371.0 8,371.0 8,410.0 8,411.0 3.00 0,410 EXP/2 3.125 120.00 RDE/A 8,000.0 8,410.0 8,411.0 3.00 0,410 EXP/2 3.125 120.00 RDE/A 8,620.0 8,630.0 0,410 EXP/1 3.125 120.00 RDE/A 8,630.0 8,630.0 0,410 EXP/1 3.125 120.00 RDE/A 8,630.0 8,630.0	11/9/2015 12:00AM	> A			8,137.0	8,138.0	3.00		0.410 E	XP/3	3.125	120.00		19.00 PF	RODUCTION		0
MES AVE 8,2220 8,2220 3.00 0.410 EXPIZED 3.125 120.00 MES AVE 8,296 0 8,297 0 3.00 0.410 EXPIZED 3.125 120.00 MES AVE 8,390 0 8,394 0 3.00 0.410 EXPIZED 3.125 120.00 MES AVE 8,394 0 8,394 0 3.00 0.410 EXPIZED 3.125 120.00 MES AVE 8,394 0 8,394 0 3.00 0.410 EXPIZED 3.125 120.00 MES AVE 8,394 0 8,394 0 3.00 0.410 EXPIZED 3.125 120.00 MES AVE 8,426 0 8,427 0 3.00 0.410 EXPIZED 3.125 120.00 MES AVE 8,630 0 8,630 0 3.00 0.410 EXPIZED 3.125 120.00 MES AVE 8,630 0 8,630 0 3.00 0.410 EXPIZED 3.125 120.00 MES AVE 8,630 0 8,630 0 3.00 0.410 EXPIZED 3.125 120.00 MES AVE 8,630 0 8,630 0 3.00	11/9/2015	> A				8,181.0	3.00		0.410 E	XP/3	3.125	120.00		19.00 PF	RODUCTION		0
MESAVE 8,296.0 8,297.0 3.00 0.410 EXP/2 3.125 120.00 RDE/ NDE/ NESAVE 8,310.0 8,311.0 3.00 0.410 EXP/2 3.125 120.00 RDE/ NDE/ NESAVE 8,339.0 8,340.0 3.00 0.410 EXP/2 3.125 120.00 RDE/ NDE/ NDE/ NDE/ NDE/ NDE/ NDE/ NDE/ N	11/9/2015	A >				8,223.0	3.00		0.410 E	XP/2	3.125	120.00		19.00 PF	RODUCTION		0
MESAVE 8,310.0 8,311.0 3.00 0.410 EXP/2 3.125 120.00 RDE/ RDE/ MESAVE 8,339.0 8,340.0 3.00 0.410 EXP/2 3.125 120.00 MESAVE RDE/ MESAVE 8,340.0 3.00 0.410 EXP/2 3.125 120.00 MESAVE RDE/ MESAVE 8,410.0 8,411.0 3.00 0.410 EXP/2 3.125 120.00 MESAVE RDE/ MESAVE 8,426.0 8,426.0 8,426.0 8,426.0 8,426.0 8,426.0 9,410.0 8,410.0	11/9/2015 12:00AM	> A				8,297.0	3.00		0.410 E	XP/2	3.125	120.00		19.00 PF	RODUCTION		0
MES AVE 8.3390 8,3400 3.00 0.410 EXP/2 3.125 120.00 RDE/ RDE/ MES AVE 8.3710 8,3720 3.00 0.410 EXP/2 3.125 120.00 RDE/ RDE/ MES AVE 8.3940 8,3950 3.00 0.410 EXP/2 3.125 120.00 RDE/ RDE/ MES AVE 8.4100 8,4110 3.00 0.410 EXP/2 3.125 120.00 RDE/ RDE/ MES AVE 8.5930 8,5940 3.00 0.410 EXP/1 3.125 120.00 RDE/ RDE/ MES AVE 8.6020 8,6030 3.00 0.410 EXP/1 3.125 120.00 RDE/ RDE/ MES AVE 8.6030 8,6030 3.00 0.410 EXP/1 3.125 120.00 RDE/ RDE/ MES AVE 8.600 8,6030 3.00 0.410 EXP/1 3.125 120.00 RDE/ RDE/ RDE/ RDE/ RDE/ RDE/ RDE/ RDE/	11/9/2015 12:00AM	\ \ \				8,311.0	3.00		0.410 E	XP/2	3.125	120.00		19.00 PF	RODUCTION		0
ME S AVE 8,3710 8,3720 3.00 0.410 EXP/2 3.125 120.00 PDE/ MES AVE 8,3940 8,395.0 3.00 0.410 EXP/2 3.125 120.00 ME S AVE 8,410.0 8,411.0 3.00 0.410 EXP/2 3.125 120.00 ME S AVE 8,426.0 8,427.0 3.00 0.410 EXP/1 3.125 120.00 ME S AVE 8,593.0 8,594.0 3.00 0.410 EXP/1 3.125 120.00 ME S AVE 8,602.0 8,603.0 3.00 0.410 EXP/1 3.125 120.00 ME S AVE 8,657.0 8,657.0 0.410 EXP/1 3.125 120.00 ME S AVE 8,657.0 8,657.0 8,658.0 3.00 0.410 EXP/1 3.125 120.00 ME S AVE 8,657.0 8,657.0 8,657.0 0.410 EXP/1 3.125 120.00 ME S AVE 8,657.0 8,680.0 3.00 0.410 EXP/1 3.125 120.00 ME S AVE 8,713.0 8,713.0 0.410 EXP/	11/9/2015 12:00AM	> A				8,340.0	3.00		0.410 E	XP/2	3.125	120.00		19.00 PF	RODUCTION		0
MESAVE 8,394.0 8,395.0 3.00 0.410 EXP/2 3.125 120.00 RDE/ NESAVE 8,410.0 8,411.0 3.00 0.410 EXP/2 3.125 120.00 ME SAVE RDE/ NESAVE 8,426.0 8,427.0 3.00 0.410 EXP/2 3.125 120.00 ME SAVE RDE/ NESAVE 8,593.0 8,693.0 3.00 0.410 EXP/1 3.125 120.00 ME SAVE RDE/ RDE/ NESAVE 8,667.0 8,663.0 3.00 0.410 EXP/1 3.125 120.00 ME SAVE RDE/ RDE/ RDE/ RDE/ RDE/ RDE/ RDE/ RDE	11/9/2015 12:00AM	A A				8,372.0	3.00		0.410 E	XP/2	3.125	120.00		19.00 PF	RODUCTION		0
MESAVE 8,410.0 8,410.0 8,410.0 3.00 0.410 EXP/2 3.125 120.00 MESAVE 8,693.0 8,594.0 3.00 0.410 EXP/1 3.125 120.00 MESAVE 8,602.0 8,693.0 3.00 0.410 EXP/1 3.125 120.00 MESAVE 8,602.0 8,693.0 3.00 0.410 EXP/1 3.125 120.00 MESAVE 8,602.0 8,632.0 3.00 0.410 EXP/1 3.125 120.00 MESAVE 8,630.0 8,688.0 3.00 0.410 EXP/1 3.125 120.00 MESAVE 8,680.0 8,680.0 3.00 0.410 EXP/1 3.125 120.00 MESAVE 8,680.0 8,680.0 3.00 0.410 EXP/1 3.125 120.00 MESAVE 8,713.0 8,713.0 3.714.0 3.00 0.410 EXP/1 3.125 120.00 MESAVE 8,713.0 8,755.0 8,756.0 3.00 0.410 EXP/1 3.125 120.00 MESAVE 8,713.0	11/9/2015 12:00AM	> A				8,395.0	3.00		0.410 E	XP/2	3.125	120.00		19.00 PF	RODUCTION		0
MESAVE	11/9/2015 12:00AM	\ \ \				8,411.0	3.00		0.410 E	XP/2	3.125	120.00		19.00 PF	RODUCTION		0
ME S AVE 8,593.0 8,594.0 3.00 0.410 EXP/1 3.125 120.00 RDE/ RDE/ ME S AVE 8,602.0 8,603.0 3.00 0.410 EXP/1 3.125 120.00 ME S AVE 8,630.0 8,632.0 3.00 0.410 EXP/1 3.125 120.00 ME S AVE 8,657.0 8,658.0 3.00 0.410 EXP/1 3.125 120.00 ME S AVE 8,680.0 8,681.0 3.00 0.410 EXP/1 3.125 120.00 ME S AVE 8,713.0 8,714.0 3.00 0.410 EXP/1 3.125 120.00 ME S AVE 8,775.0 8,756.0 3.00 0.410 EXP/1 3.125 120.00 ME S AVE 8,775.0 8,756.0 3.00 0.410 EXP/1 3.125 120.00 ME S AVE 8,775.0 8,756.0 3.00 0.410 EXP/1 3.125 120.00	11/9/2015 12:00AM	\ \ \				8,427.0	3.00		0.410 E	XP/2	3.125	120.00		19.00 PF	RODUCTION		0
MESAVE 8,602.0 8,603.0 3.00 0.410 EXP/1 3.125 120.00 RDE/ RDE/ MESAVE 8,630.0 8,632.0 3.00 0.410 EXP/1 3.125 120.00 MESAVE 8,687.0 8,688.0 3.00 0.410 EXP/1 3.125 120.00 MESAVE 8,680.0 8,681.0 3.00 0.410 EXP/1 3.125 120.00 MESAVE 8,713.0 8,714.0 3.00 0.410 EXP/1 3.125 120.00 MESAVE 8,755.0 8,756.0 3.00 0.410 EXP/1 3.125 120.00 MESAVE 8,755.0 8,756.0 3.00 0.410 EXP/1 3.125 120.00	11/9/2015 12:00AM	> A				8,594.0	3.00		0.410 E	XP/1	3.125	120.00		19.00 PF	RODUCTION		0
MESAVE 8,630.0 8,632.0 3.00 0.410 EXP/1 3.125 120.00 RDE/ RDE/ MESAVE 8,657.0 8,658.0 3.00 0.410 EXP/1 3.125 120.00 MESAVE 8,680.0 8,681.0 3.00 0.410 EXP/1 3.125 120.00 MESAVE 8,713.0 8,714.0 3.00 0.410 EXP/1 3.125 120.00 MESAVE 8,755.0 8,756.0 3.00 0.410 EXP/1 3.125 120.00 RDE/ RDE/ 8,755.0 8,756.0 3.00 0.410 EXP/1 3.125 120.00	11/9/2015 12:00AM	\ \ \				8,603.0	3.00		0.410 E	XP/1	3.125	120.00		19.00 PF	RODUCTION		0
MESAVE 8,657.0 8,658.0 3.00 0.410 EXP/1 3.125 120.00 RDE/ RDE/ MESAVE 8,680.0 8,681.0 3.00 0.410 EXP/1 3.125 120.00 MESAVE 8,713.0 8,714.0 3.00 0.410 EXP/1 3.125 120.00 MESAVE 8,755.0 8,756.0 3.00 0.410 EXP/1 3.125 120.00 RDE/ RDE/ 8,755.0 8,756.0 3.00 0.410 EXP/1 3.125 120.00	11/9/2015 12:00AM	A				8,632.0	3.00		0.410 E	XP/1	3.125	120.00		19.00 PF	RODUCTION		
MESAVE 8,680.0 8,681.0 3.00 0.410 EXP/1 3.125 120.00 RDE/ MESAVE 8,713.0 8,714.0 3.00 0.410 EXP/1 3.125 120.00 MESAVE 8,755.0 8,756.0 3.00 0.410 EXP/1 3.125 120.00	11/9/2015 12:00AM	\ \ \				8,658.0	3.00		0.410 E	XP/1	3.125	120.00		19.00 PF	RODUCTION		0
MESAVE 8,713.0 8,714.0 3.00 0.410 EXP/1 3.125 120.00 RDE/ RDE/ RSAVE 8,755.0 8,756.0 3.00 0.410 EXP/1 3.125 120.00	11/9/2015 12:00AM	\ \ \				8,681.0	3.00		0.410 E	XP/1	3.125	120.00		19.00 PF	RODUCTION		0
MESAVE 8,755.0 8,756.0 3.00 0.410 EXP/1 3.125 120.00 RDE/	11/9/2015 12:00AM	> A				8,714.0	3.00		0.410 E	XP/1	3.125	120.00		19.00 PF	RODUCTION		0
	11/9/2015 12:00AM	MESAVE RDE/				8,756.0	3.00		0.410 E	XP/1	3.125	120.00		19.00 PF	RODUCTION		0

RECEIVED: Jan. 06, 2016

December 28, 2015 at 3:13 pm

OpenWells